

Label
Town and PIN

BEFORE SUBMITTING YOUR BID

- 1. Use pen and ink to complete the Bid.**
- 2. Have you signed and completed the Contract Agreement, Offer & Award Forms?**
- 3. As a minimum, the Bidder will submit a Bid Package consisting of the Notice to Contractors, the completed Acknowledgement of Bid Amendments & Submission of Bid Bond Validation Number form, the completed Schedule of Items, 2 copies of the completed Agreement, Offer, & Award form, a Bid Bond or Bid Guarantee, and any other Certifications or Bid Requirements listed in the Bid Book.**
- 4. Have you included prices for all Bid Items? (“Zero is not considered a bid price.”)**
- 5. Have you included a bid guarantee? Acceptable forms are:**
 - A. Bid Bond on the Department’s prescribed form for 5% of the Bid Amount. (Or forms that do not contain any significant variations from the Department’s forms as solely determined by the Department.)**
 - B. Official Bank Check, Cashier’s Check, Certified Check, U.S. Postal Money Order or Negotiable Certificate of Deposit in the amount stated in the Notice to Contractors.**
- 6. If the written Bid is to be sent, Federal Express overnight delivery is suggested as the package is delivered directly to the DOT Headquarters Building in Augusta. Other means, such as U.S. Postal Services’ Express Mail has proven not to be reliable.**

AND FOR FEDERAL AID PROJECTS

- 7. Have you included your DBE Utilization commitment in the proper amounts and signed the DBE Certification?**

If you need further information regarding Bid preparation, call the DOT Contracts Section at (207)624-3410.

For complete specifications regarding bidding requirements, refer to Section 102 of the Maine Department of Transportation, Standard Specifications, Revision December 2002.

NOTICE

The Maine Department of Transportation is attempting to improve the way Bid Amendments/Addendums are handled, and allow for an electronic downloading of bid packages from our website, while continuing to maintain a planholders list.

Prospective bidders, subcontractors or suppliers who wish to download a copy of the bid package and receive a courtesy notification of project specific bid amendments, must provide an email address to Diane Barnes at the MDOT Contracts mailbox at: MDOT.contracts@maine.gov. Each bid package will require a separate request.

Additionally, interested parties will be responsible for reviewing and retrieving the Bid Amendments from our web site, and acknowledging receipt and incorporating those Bid Amendments in their bids using the Acknowledgement of Bid Amendment Form.

The downloading of bid packages from the MDOT website is not the same as providing an electronic bid to the Department. Electronic bids must be submitted via <http://www.BIDX.com>. For information on electronic bidding contract Rebecca Pooler at rebecca.pooler@maine.gov.

NOTICE

For security and other reasons, all Bid Packages which are mailed, shall be provided in double (one envelope inside the other) envelopes. The *Inner Envelope* shall have the following information provided on it:

Bid Enclosed - Do Not Open

PIN:

Town:

Date of Bid Opening:

Name of Contractor with mailing address and telephone number:

In Addition to the usual address information, the *Outer Envelope* should have written or typed on it:

Double Envelope: Bid Enclosed

PIN:

Town:

Date of Bid Opening:

Name of Contractor:

This should not be much of a change for those of you who use Federal Express or similar services.

Hand-carried Bids may be in one envelope as before, and should be marked with the following information:

Bid Enclosed: Do Not Open

PIN:

Town:

Name of Contractor:

STATE OF MAINE DEPARTMENT OF TRANSPORTATION
Bid Guaranty-Bid Bond Form

KNOW ALL MEN BY THESE PRESENTS THAT_____

_____, of the City/Town of _____ and State of _____

as Principal, and _____ as Surety, a

Corporation duly organized under the laws of the State of _____ and having a usual place of

Business in _____ and hereby held and firmly bound unto the Treasurer of

the State of Maine in the sum of _____ for payment which Principal and Surety bind

themselves, their heirs, executors, administrators, successors and assigns, jointly and severally.

The condition of this obligation is that the Principal has submitted to the Maine Department of

Transportation, hereafter Department, a certain bid, attached hereto and incorporated as a

part herein, to enter into a written contract for the construction of _____

_____ and if the Department shall accept said bid

and the Principal shall execute and deliver a contract in the form attached hereto (properly

completed in accordance with said bid) and shall furnish bonds for this faithful performance of

said contract, and for the payment of all persons performing labor or furnishing material in

connection therewith, and shall in all other respects perform the agreement created by the

acceptance of said bid, then this obligation shall be null and void; otherwise it shall remain in full

force, and effect.

Signed and sealed this _____ day of _____ 20_____

WITNESS:

WITNESS

PRINCIPAL:

By _____

By: _____

By: _____

SURETY:

By _____

By: _____

Name of Local Agency: _____

NOTICE

Bidders:

Please use the attached “Request for Information” form when faxing questions and comments concerning specific Contracts that have been Advertised for Bid. Include additional numbered pages as required.

REQUEST FOR INFORMATION

[illegible][illegible]

Response By:_____ Date:_____

INSTRUCTIONS FOR PREPARING THE CONTRACTOR'S DISADVANTAGED BUSINESS ENTERPRISE UTILIZATION PLAN

The Contractor Shall:

1. Submit a completed Contractor's Disadvantaged Business Enterprise Utilization Plan to the Contract's Engineer by 4:30 P.M. on the Bid day.
2. Extend equal opportunity to MDOT certified DBE firms (as listed in MDOT's DBE Directory of Certified Businesses) in the selection and utilization of Subcontractors and Suppliers.

SPECIFIC INSTRUCTIONS FOR COMPLETING THE FORM:

Insert Contractor name, the name of the person(s) preparing the form, and that person(s) telephone and fax number.

Provide total Bid price, Federal Project Identification Number, and location of the Project work.

In the columns, name each DBE firm to be used, provide the Unit or Item cost of the Work/Product to be provided by the DBE firm, give a brief description of the Work, and the dollar value of the Work.

If no DBE firm is to be utilized, the Contractor must document the reason(s) why no DBE firms are being used. Specific supporting evidence of good faith efforts taken by Contractors to solicit DBE Bidders must be attached. This evidence, as a minimum, includes phone logs, e-mail and/or mail DBE solicitation records, and the documented results of these solicitations.

NOTICE

Disadvantaged Business Enterprise Proposed Utilization

The Apparent Low Bidder must submit the Disadvantaged Business Enterprise Proposed Utilization form by close of Business (4:30 P.M.) on Bid day.

The Contractor's Disadvantaged Business Enterprise Proposed Utilization Plan form contains additional information that is required by USDOT.

The Contractor's Disadvantaged Business Enterprise Proposed Utilization Plan form must be used.

A copy of the new Contractor's Disadvantaged Business Enterprise Proposed Utilization Plan and instructions for completing it are attached.

Note: Questions about DBE firms, or to obtain a printed copy of the DBE Directory, contact Equal Opportunity at (207) 624-3066.

MDOT's DBE Directory of Certified firms can also be obtained at http://www.state.me.us/mdot/humnres/o_equalo/cdwbed_h.htm

CONTRACTOR'S DISADVANTAGED BUSINESS ENTERPRISE PROPOSED UTILIZATION PLAN

Low Bidder shall furnish completed form to Contracts Section by 4:30 P.M. on Bid Opening day.

TO: MDOT Contracts Section
16 State House Station,
Augusta, Me 04333-0016
or
Fax: 207-624-3431

Contractor: _____

Prepared by: _____

Telephone: _____ Fax: _____

BID PRICE: \$ _____ FEDERAL PROJECT # _____ LOCATION: _____

TOTAL DBE PARTICIPATION AS A PERCENT OF TOTAL BID PRICE = _____ %

DBE Firm*	Unit/Item Cost	Unit #	Description of work & Item Number	Actual \$ Value
Total >				

If no DBE firm(s) are used, bidder must document efforts made to secure DBE participation and attach supporting evidence of this effort:

_____.

Examples: Bidder relies wholly upon low quote subcontractor section, DBE firm(s) were not low quote. No DBE firms bid.

*Only DBE firms certified by MDOT prior to bidding can be utilized by Contractor for DBE credit.
Directory of certified DBEs is available on MDOT's website: www.state.me.us/mdot

Equal Opportunity Use:

Plan received ____/____/____ Verified by: _____ Action: _____



Office of Human Resources

Equal Opportunity

MAINE DEPARTMENT OF TRANSPORTATION

Certified Disadvantaged and Women Business Enterprise

DBE DIRECTORY - MINORITY OWNED

WBE DIRECTORY - WOMEN OWNED

WEBSITE FOR DIRECTORY CAN BE FOUND AT:

http://www.state.me.us/mdot/humnres/o_equalo/cdwbed_h.htm

It is the responsibility of the Contractor to access the DBE Directory at this site in order to have the most current listings.

STATE OF MAINE DEPARTMENT OF TRANSPORTATION NOTICE TO CONTRACTORS

Sealed Bids addressed to the Maine Department of Transportation, Augusta, Maine 04333 and endorsed on the wrapper "Bid for the Hot Mix Asphalt Overlay, Plant Mix Recycled Asphalt Pavement, Variable and Full Depth Gravel Areas, Maintenance Surface Treatment, Drainage and Safety Improvements in the towns of **Athens, Cambridge, Cornville and Dexter**" will be received from contractors at the Reception Desk, Maine DOT Building, Child Street, Augusta, Maine, until 11:00 o'clock A.M. (prevailing time) on **July 14, 2004**, and at that time and place publicly opened and read. Bids will be accepted from contractors prequalified by the Department of Transportation for highway construction or paving projects. All other Bids may be rejected. **MDOT provides the option of electronic bidding. We accept electronic bids for those bid packages posted on the bidx.com website. Electronic bids do not have to be accompanied by paper bids. Please note: the Department will accept a facsimile of the bid bond; however, the original bid bond must then be received at the MDOT Contract Section within 72 hours of the bid opening.** Until further notice, dual bids (one paper, one electronic) will be accepted, with the paper copy taking precedence.

Description: Maine Federal Aid Project No. STP-1121(400)X, PIN 11214.00; STP-1128(500)X, PIN 11285.00; STP-A134(000)X, PIN 11340.00; 012261.00, PIN 12261.00.

Location: In Somerset County, project STP-1121(400)X (**Sections 1&3 being highway rehabilitation**) & PIN 12261.00 (**Sections 2&4 being a Maintenance Surface Treatment**) are located on Route 150. Section one begins in Athens, 0.77 of a mile southwesterly of the intersection of route 43/151 and extends northeasterly 0.73 of a mile. Section two extends northeasterly from that point another 0.40 of a mile. Section three begins at the intersection of route 151 and 150 and extends northeasterly 1.42 miles. Section four begins in Cambridge 0.20 of a mile southerly of the intersection of route 150 and 152 and extends northerly 0.66 of a mile. Project STP-1128(500)X is located on Route 150 in Cornville, beginning 0.56 miles southerly of Revere School Road and extending northerly 2.4 miles. In Penobscot County, project STP-A134(000)X is located on Route 7 in Dexter, beginning at the Corinna/Dexter town line and extending northerly 1.25 miles.

Outline of Work: Hot Mix Asphalt Overlay, Plant Mix Recycled Asphalt Pavement, Variable and Full Depth Gravel Areas, Maintenance Surface Treatment, Drainage and Safety Improvements and other incidental work.

For general information regarding Bidding and Contracting procedures, contact Scott Bickford at (207)624-3410. Our webpage at <http://www.state.me.us/mdot/project/design/homepg.htm> contains a copy of the schedule of items, Plan Holders List, written portions of bid amendments (not drawings), and bid results. For Project-specific information fax all questions to **James Andrews** at (207)624-3401. Questions received after 12:00 noon of Monday prior to bid date will not be answered. Bidders shall not contact any other Departmental staff for clarification of Contract provisions, and the Department will not be responsible for any interpretations so obtained. Hearing impaired persons may call the Telecommunication Device for the Deaf at (207) 624-3007.

Plans, specifications and bid forms may be seen at the Maine DOT Building in Augusta, Maine. They may be purchased from the Department between the hours of 8:00 a.m. to 4:30 p.m. by cash, credit card (Visa/Mastercard) or check payable to Treasurer, State of Maine sent to Maine Department of Transportation, Attn.: Mailroom, 16 State House Station, Augusta, Maine 04333-0016. They also may be purchased by telephone at (207)624-3536 between the hours of 8:00 a.m. to 4:30 p.m. Full size plans \$50.00 (\$54.50 by mail). Half size plans \$25.00 (\$28.00 by mail). Bid Book \$10 (\$13 by mail), Single Sheets \$2, payment in advance, all non-refundable.


Each Bid must be made upon blank forms provided by the Department and must be accompanied by a bid bond at 5% of the bid amount or an official bank check, cashier's check, certified check, certificate of deposit, or United States postal money order in the amount of \$65,000 payable to Treasurer, State of Maine as a Bid guarantee. A Contract Performance Surety Bond and a Contract Payment Surety Bond, each in the amount of 100 percent of the Contract price, will be required of the successful Bidder.

This Contract is subject to all applicable Federal Laws. This contract is subject to compliance with the Disadvantaged Business Enterprise program requirements as set forth by the Maine Department of Transportation.

All work shall be governed by "State of Maine, Department of Transportation, Standard Specifications, Revision of December 2002", price \$10 [\$13 by mail], and Standard Details, Revision of December 2002, price \$20 [\$25 by mail] Standard Detail updates can be found at <http://www.state.me.us/mdot/project/design/homepg.htm>

The right is hereby reserved to the MDOT to reject any or all Bids.

Augusta, Maine
Date: June 23, 2004



JOHN E. DORITY
CHIEF ENGINEER

STP-1121(400)X Athens-Cambridge
STP-1128(500)X Cornville
STP-A134(000)X Dexter
PIN 12261.00
Supercedes October 29, 2003

SPECIAL PROVISION 102.7.3
ACKNOWLEDGMENT OF BID AMENDMENTS
&
SUBMISSION OF BID BOND VALIDATION NUMBER (IF APPLICABLE)

With this form, the Bidder acknowledges its responsibility to check for all Amendments to the Bid Package. For each Project under Advertisement, Amendments are located at <http://www.maine.gov/mdot/comprehensive-list-projects/project-information.php>. It is the responsibility of the Bidder to determine if there are Amendments to the Project, to download them, to incorporate them into their Bid Package, and to reference the Amendment number and the date on the form below. The Maine DOT will not post Bid Amendments any later than noon the day before Bid opening without individually notifying all the planholders.

Amendment Number	Date

The Contractor, for itself, its successors and assigns, hereby acknowledges that it has received all of the above referenced Amendments to the Bid Package.

CONTRACTOR

Date

Signature of authorized representative

(Name and Title Printed)

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 011214.00

PROJECTS

STP-1121(400)X

STP-1128(500)X

STP-A134(000)X

012261.00

COUNTY : SOMERSET

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 1

SCHEDULE OF ITEMS

DATE: 040615

REVISED:

CONTRACT ID: 011214.00

PROJECT(S): STP-1121(400)X
 STP-1128(500)X
 STP-A134(000)X
 012261.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 HIGHWAY ITEMS						
0010	201.11 CLEARING	0.190				
		AC				
0020	202.202 REMOVING PAVEMENT SURFACE	120.000				
		SY				
0030	202.203 PAVEMENT BUTT JOINTS	1030.000				
		SY				
0040	203.20 COMMON EXCAVATION	1300.000				
		CY				
0050	203.21 ROCK EXCAVATION	350.000				
		CY				
0060	211.21 INSLOPE REHABILITATION	19125.000				
		LF				
0070	211.30 DITCH EXCAVATION	17325.000				
		LF				
0080	211.41 NEW DITCH EXCAVATION - LEDGE	900.000				
		LF				
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	17700.000				
		CY				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 2

SCHEDULE OF ITEMS

DATE: 040615

REVISED:

CONTRACT ID: 011214.00

PROJECT(S): STP-1121(400)X
 STP-1128(500)X
 STP-A134(000)X
 012261.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE ----- DOLLARS CTS		BID AMOUNT ----- DOLLARS CTS	
0100	310.23 PLANT MIX RECYCLED ASPHALT PAVEMENT - 3 INCH DEPTH	80030.000 SY				
0110	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENT ALS)	130.000 T				
0120	403.210 HOT MIX ASPHALT 9.5 MM HMA	6590.000 T				
0130	403.212 HOT MIX ASPHALT 4.75 MM HMA	485.000 T				
0140	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	6500.000 T				
0150	409.15 BITUMINOUS TACK COAT APPLIED	5145.000 G				
0160	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	115.000 CY				
0170	461.210 MAINTENANCE SURFACE TREATMENT - 9.5 MM	1000.000 T				
0180	603.16 15 INCH CULVERT PIPE OPTION I	625.000 LF				
0190	603.17 18 INCH CULVERT PIPE OPTION I	260.000 LF				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 3

SCHEDULE OF ITEMS

DATE: 040615

REVISED:

CONTRACT ID: 011214.00

PROJECT(S): STP-1121(400)X
 STP-1128(500)X
 STP-A134(000)X
 012261.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	603.179 18 INCH CULVERT PIPE OPTION III	1030.000 LF				
0210	603.199 24 INCH CULVERT PIPE OPTION III	65.000 LF				
0220	603.219 36 INCH CULVERT PIPE OPTION III	1120.000 LF				
0230	603.279 72 INCH CULVERT PIPE OPTION III	15.000 LF				
0240	603.7315 REMOVE & RELAY 15 INCH METAL PIPE	60.000 LF				
0250	604.092 CATCH BASIN TYPE B1-C	3.000 EA				
0260	605.09 6 INCH UNDERDRAIN TYPE B	230.000 LF				
0270	605.11 12 INCH UNDERDRAIN TYPE C	300.000 LF				
0280	605.13 18 INCH UNDERDRAIN TYPE C	650.000 LF				
0290	606.1722 BRIDGE TRANSITION - TYPE 2	2.000 EA				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 4

SCHEDULE OF ITEMS

DATE: 040615

REVISED:

CONTRACT ID: 011214.00

PROJECT(S): STP-1121(400)X
 STP-1128(500)X
 STP-A134(000)X
 012261.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE ----- DOLLARS CTS		BID AMOUNT ----- DOLLARS CTS	
0300	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	100.000 LF				
0310	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	12.500 LF				
0320	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	12.500 LF				
0330	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				
0340	606.35 GUARDRAIL DELINEATOR POST	3.000 EA				
0350	606.47 SINGLE WOOD POST	15.000 EA				
0360	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	1.000 EA				
0370	606.79 GUARDRAIL 350 FLARED TERMINAL	1.000 EA				
0380	609.31 CURB TYPE 3	1850.000 LF				
0390	610.08 PLAIN RIPRAP	130.000 CY				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 5

SCHEDULE OF ITEMS

DATE: 040615

REVISED:

CONTRACT ID: 011214.00

PROJECT(S): STP-1121(400)X
 STP-1128(500)X
 STP-A134(000)X
 012261.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE ----- DOLLARS CTS		BID AMOUNT ----- DOLLARS CTS	
0400	610.18 STONE DITCH PROTECTION	450.000 CY				
0410	613.319 EROSION CONTROL BLANKET	10250.000 SY				
0420	615.07 LOAM	205.000 CY				
0430	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	25.000 UN				
0440	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	600.000 UN				
0450	619.1201 MULCH - PLAN QUANTITY	625.000 UN				
0460	620.54 STABILIZATION GEOTEXTILE	8900.000 SY				
0470	620.58 EROSION CONTROL GEOTEXTILE	805.000 SY				
0480	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0490	629.05 HAND LABOR, STRAIGHT TIME	45.000 HR				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 6

SCHEDULE OF ITEMS

DATE: 040615

REVISED:

CONTRACT ID: 011214.00

PROJECT(S): STP-1121(400)X
 STP-1128(500)X
 STP-A134(000)X
 012261.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0500	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	100.000 HR				
0510	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	200.000 HR				
0520	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	40.000 HR				
0530	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	80.000 HR				
0540	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	20.000 HR				
0550	639.19 FIELD OFFICE TYPE B	1.000 EA				
0560	652.38 FLAGGER	5475.000 HR				
0570	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0580	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0590	659.10 MOBILIZATION	LUMP	LUMP			

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 7

DATE: 040615

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011214.00

PROJECT(S): STP-1121(400)X
STP-1128(500)X
STP-A134(000)X
012261.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE DOLLARS CTS	BID AMOUNT DOLLARS CTS
0600	660.21 ON-THE-JOB TRAINING (BID)	1000.000 HR		
	SECTION 0001 TOTAL			
	TOTAL BID			

CONTRACT AGREEMENT, OFFER & AWARD

AGREEMENT made on the date last signed below, by and between the State of Maine, acting through and by its Department of Transportation (Department), an agency of state government with its principal administrative offices located at Child Street, Augusta, Maine, with a mailing address at 16 State House Station, Augusta, Maine 04333-0016, and

_____ a corporation or other legal entity organized under the laws of the State of Maine, with its principal place of business located at _____

The Department and the Contractor, in consideration of the mutual promises set forth in this Agreement (the "Contract"), hereby agree as follows:

A. The Work.

The Contractor agrees to complete all Work as specified or indicated in the Contract including Extra Work in conformity with the Contract, **STP-1121(400)X, PIN 11214.00; STP-1128(500)X, PIN 11285.00, STP-A134(000)X, PIN 11340.00; 01226100, PIN 12261.00 for the Hot Mix Asphalt Overlay, Plant Mixed Recycled Asphalt Pavement, Variable Gravel Areas, Full Construction Areas, Drainage and Safety Improvements and Maintenance Surface Treatment in the towns of Cornville, Athens and Cambridge County of Somerset, Maine and in the town of Dexter County of Penobscot, Maine.** The Work includes construction, maintenance during construction, warranty as provided in the Contract, and other incidental work.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools supplies, permanent materials and temporary materials required to perform the Work including construction quality control including inspection, testing and documentation, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

The Contractor agrees to complete all Work, except warranty work, on or before **August 13, 2005.** Further, the Department may deduct from moneys otherwise due the Contractor, not as a penalty, but as Liquidated Damages in accordance with Sections 107.7 and 107.8 of the State of Maine Department of Transportation Standard Specifications, Revision of December 2002.

C. Price.

The quantities given in the Schedule of Items of the Bid Package will be used as the basis for determining the original Contract amount and for determining the amounts of the required Performance Surety Bond and Payment Surety Bond, and that the amount of this offer is _____

\$_____ Performance Bond and Payment Bond each being 100% of the amount of this Contract.

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the Contract documents as defined in the Plans, Standard Specifications, Revision of December 2002, Standard Details Revision of December 2002 as updated through advertisement, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below, the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

1. All of the statements, representations, covenants, and/or certifications required or set forth in the Bid and the Bid Documents, including those in Appendix A to Division 100 of the Standard Specifications Revision of December 2002 (Federal Contract Provisions Supplement), and the Contract are still complete and accurate as of the date of this Agreement.
2. The Contractor knows of no legal, contractual, or financial impediment to entering into this Contract.
3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Offer.

The undersigned, having carefully examined the site of work, the Plans, Standard Specifications Revision of December 2002, Standard Details Revision of December 2002 as updated through advertisement, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds contained herein for construction of: **STP-1121(400)X, PIN 11214.00; STP-1128(500)X, PIN 11285.00, STP-A134(000)X, PIN 11340.00; 01226100, PIN 12261.00 for the Hot Mix Asphalt Overlay, Plant Mixed Recycled Asphalt Pavement, Variable Gravel Areas, Full Construction Areas, Drainage and Safety Improvements and Maintenance Surface Treatment in the towns of Cornville, Athens and Cambridge County of Somerset, Maine and in the town of Dexter County of Penobscot, Maine** on which bids will be received until the time specified in the "Notice to Contractors" do(es) hereby bid and offer to enter into this contract to supply all the materials, tools, equipment and labor to construct the whole of the Work in strict accordance with the terms and conditions of this Contract at the unit prices in the attached "Schedule of Items".

The Offeror agrees to perform the work required at the price specified above and in accordance with the bids provided in the attached "Schedule of Items" in strict accordance with the terms of this solicitation, and to provide the appropriate insurance and bonds if this offer is accepted by the Government in writing.

As Offeror also agrees:

First: To do any extra work, not covered by the attached "Schedule of Items", which may be ordered by the Resident, and to accept as full compensation the amount determined upon a "Force Account" basis as provided in the Standard Specifications, Revision of December 2002, and as addressed in the contract documents.

Second: That the bid bond at 5% of the bid amount or the official bank check, cashier's check, certificate of deposit or U. S. Postal Money Order in the amount given in the "Notice to Contractors", payable to the Treasurer of the State of Maine and accompanying this bid, shall be forfeited, as liquidated damages, if in case this bid is accepted, and the undersigned shall fail to abide by the terms and conditions of the offer and fail to furnish satisfactory insurance and Contract bonds under the conditions stipulated in the Specifications within 15 days of notice of intent to award the contract.

Third: To begin the Work on the date specified in the Engineer's "Notice to Commence Work" as stated in Section 107.2 of the Standard Specifications Revision of December 2002 and complete the Work within the time limits given in the Special Provisions of this Contract.

Fourth: The Contractor will be bound to the Disadvantaged Business Enterprise (DBE) Requirements contained in the attached Notice (Additional Instructions to Bidders) and submit a completed Contractor's Disadvantaged Business Enterprise Utilization Plan by 4:30pm on the day of bid opening to the Contracts Engineer.

Fifth: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Sixth: The Bidder hereby certifies, to the best of its knowledge and belief that: the Bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

IN WITNESS WHEREOF, the Contractor, for itself, its successors and assigns, hereby execute two duplicate originals of this Agreement and thereby binds itself to all covenants, terms, and obligations contained in the Contract Documents.

CONTRACTOR

Date

(Signature of Legally Authorized Representative
of the Contractor)

Witness

(Name and Title Printed)

G. Award.

Your offer is hereby accepted.
documents referenced herein.

This award consummates the Contract, and the

MAINE DEPARTMENT OF TRANSPORTATION

Date

By: David A. Cole, Commissioner

Witness

CONTRACT AGREEMENT, OFFER & AWARD

AGREEMENT made on the date last signed below, by and between the State of Maine, acting through and by its Department of Transportation (Department), an agency of state government with its principal administrative offices located at Child Street, Augusta, Maine, with a mailing address at 16 State House Station, Augusta, Maine 04333-0016, and

_____ a corporation or other legal entity organized under the laws of the State of Maine, with its principal place of business located at _____

The Department and the Contractor, in consideration of the mutual promises set forth in this Agreement (the "Contract"), hereby agree as follows:

A. The Work.

The Contractor agrees to complete all Work as specified or indicated in the Contract including Extra Work in conformity with the Contract, **STP-1121(400)X, PIN 11214.00; STP-1128(500)X, PIN 11285.00, STP-A134(000)X, PIN 11340.00; 01226100, PIN 12261.00 for the Hot Mix Asphalt Overlay, Plant Mixed Recycled Asphalt Pavement, Variable Gravel Areas, Full Construction Areas, Drainage and Safety Improvements and Maintenance Surface Treatment in the towns of Cornville, Athens and Cambridge County of Somerset, Maine and in the town of Dexter County of Penobscot, Maine.** The Work includes construction, maintenance during construction, warranty as provided in the Contract, and other incidental work.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools supplies, permanent materials and temporary materials required to perform the Work including construction quality control including inspection, testing and documentation, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

The Contractor agrees to complete all Work, except warranty work, on or before **August 13, 2005.** Further, the Department may deduct from moneys otherwise due the Contractor, not as a penalty, but as Liquidated Damages in accordance with Sections 107.7 and 107.8 of the State of Maine Department of Transportation Standard Specifications, Revision of December 2002.

C. Price.

The quantities given in the Schedule of Items of the Bid Package will be used as the basis for determining the original Contract amount and for determining the amounts of the required Performance Surety Bond and Payment Surety Bond, and that the amount of this offer is _____

\$_____ Performance Bond and Payment Bond each being 100% of the amount of this Contract.

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the Contract documents as defined in the Plans, Standard Specifications, Revision of December 2002, Standard Details Revision of December 2002 as updated through advertisement, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below, the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

1. All of the statements, representations, covenants, and/or certifications required or set forth in the Bid and the Bid Documents, including those in Appendix A to Division 100 of the Standard Specifications Revision of December 2002 (Federal Contract Provisions Supplement), and the Contract are still complete and accurate as of the date of this Agreement.
2. The Contractor knows of no legal, contractual, or financial impediment to entering into this Contract.
3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Offer.

The undersigned, having carefully examined the site of work, the Plans, Standard Specifications Revision of December 2002, Standard Details Revision of December 2002 as updated through advertisement, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds contained herein for construction of: **STP-1121(400)X, PIN 11214.00; STP-1128(500)X, PIN 11285.00, STP-A134(000)X, PIN 11340.00; 01226100, PIN 12261.00 for the Hot Mix Asphalt Overlay, Plant Mixed Recycled Asphalt Pavement, Variable Gravel Areas, Full Construction Areas, Drainage and Safety Improvements and Maintenance Surface Treatment in the towns of Cornville, Athens and Cambridge County of Somerset, Maine and in the town of Dexter County of Penobscot, Maine** on which bids will be received until the time specified in the "Notice to Contractors" do(es) hereby bid and offer to enter into this contract to supply all the materials, tools, equipment and labor to construct the whole of the Work in strict accordance with the terms and conditions of this Contract at the unit prices in the attached "Schedule of Items".

The Offeror agrees to perform the work required at the price specified above and in accordance with the bids provided in the attached "Schedule of Items" in strict accordance with the terms of this solicitation, and to provide the appropriate insurance and bonds if this offer is accepted by the Government in writing.

As Offeror also agrees:

First: To do any extra work, not covered by the attached "Schedule of Items", which may be ordered by the Resident, and to accept as full compensation the amount determined upon a "Force Account" basis as provided in the Standard Specifications, Revision of December 2002, and as addressed in the contract documents.

Second: That the bid bond at 5% of the bid amount or the official bank check, cashier's check, certificate of deposit or U. S. Postal Money Order in the amount given in the "Notice to Contractors", payable to the Treasurer of the State of Maine and accompanying this bid, shall be forfeited, as liquidated damages, if in case this bid is accepted, and the undersigned shall fail to abide by the terms and conditions of the offer and fail to furnish satisfactory insurance and Contract bonds under the conditions stipulated in the Specifications within 15 days of notice of intent to award the contract.

Third: To begin the Work on the date specified in the Engineer's "Notice to Commence Work" as stated in Section 107.2 of the Standard Specifications Revision of December 2002 and complete the Work within the time limits given in the Special Provisions of this Contract.

Fourth: The Contractor will be bound to the Disadvantaged Business Enterprise (DBE) Requirements contained in the attached Notice (Additional Instructions to Bidders) and submit a completed Contractor's Disadvantaged Business Enterprise Utilization Plan by 4:30pm on the day of bid opening to the Contracts Engineer.

Fifth: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Sixth: The Bidder hereby certifies, to the best of its knowledge and belief that: the Bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

IN WITNESS WHEREOF, the Contractor, for itself, its successors and assigns, hereby execute two duplicate originals of this Agreement and thereby binds itself to all covenants, terms, and obligations contained in the Contract Documents.

CONTRACTOR

Date

(Signature of Legally Authorized Representative
of the Contractor)

Witness

(Name and Title Printed)

G. Award.

Your offer is hereby accepted.
documents referenced herein.

This award consummates the Contract, and the

MAINE DEPARTMENT OF TRANSPORTATION

Date

By: David A. Cole, Commissioner

Witness

CONTRACT AGREEMENT, OFFER & AWARD

AGREEMENT made on the date last signed below, by and between the State of Maine, acting through and by its Department of Transportation (Department), an agency of state government with its principal administrative offices located at 1705 U.S. Route 202, Winthrop, Maine, with a mailing address at 16 State House Station, Augusta, Maine 04333-0016, and (Name of the firm bidding the job) a corporation or other legal entity organized under the laws of the State of Maine, with its principal place of business located at (address of the firm bidding the job)

The Department and the Contractor, in consideration of the mutual promises set forth in this Agreement (the "Contract"), hereby agree as follows:

A. The Work.

The Contractor agrees to complete all Work as specified or indicated in the Contract including Extra Work in conformity with the Contract, PIN No. 1224.00

for the Hot Mix Asphalt Overlay in the town/city of West Eastport, County of Washington, Maine. The Work includes construction, maintenance during construction, warranty as provided in the Contract, and other incidental work.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools supplies, permanent materials and temporary materials required to perform the Work including construction quality control including inspection, testing and documentation, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

The Contractor agrees to complete all Work, except warranty work, on or before November 15, 2003. Further, the Department may deduct from moneys otherwise due the Contractor, not as a penalty, but as Liquidated Damages in accordance with Sections 107.7 and 107.8 of the State of Maine Department of Transportation Standard Specifications, Revision of December 2002.

C. Price.

The quantities given in the Schedule of Items of the Bid Package will be used as the basis for determining the original Contract amount and for determining the amounts of the required Performance Surety Bond and Payment Surety Bond, and that the amount of this offer is (Place bid here in alphabetical form such as One Hundred and Two dollars and 10 cents)
\$ (repeat bid here in numerical terms, such as \$102.10) Performance Bond and Payment Bond each being 100% of the amount of this Contract.

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the Contract documents as defined in the Plans, Standard Specifications, Revision of December 2002, Standard Details Revision of December 2002, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below, the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

1. All of the statements, representations, covenants, and/or certifications required or set forth in the Bid and the Bid Documents, including those in Appendix A to Division 100 of the Standard Specifications Revision of December 2002 (Federal Contract Provisions Supplement), and the Contract are still complete and accurate as of the date of this Agreement.
2. The Contractor knows of no legal, contractual, or financial impediment to entering into this Contract.
3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Offer.

The undersigned, having carefully examined the site of work, the Plans, Standard Specifications, Revision of December 2002, Standard Details Revision of December 2002, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds contained herein for construction of:

PIN 1234.00 West Eastport, Hot Mix Asphalt Overlay

State of Maine, on which bids will be received until the time specified in the "Notice to Contractors" do(es) hereby bid and offer to enter into this contract to supply all the materials, tools, equipment and labor to construct the whole of the Work in strict accordance with the terms and conditions of this Contract at the unit prices in the attached "Schedule of Items".

The Offeror agrees to perform the work required at the price specified above and in accordance with the bids provided in the attached "Schedule of Items" in strict accordance with the terms of this solicitation, and to provide the appropriate insurance and bonds if this offer is accepted by the Government in writing.

As Offeror also agrees:

First: To do any extra work, not covered by the attached "Schedule of Items", which may be ordered by the Resident, and to accept as full compensation the amount determined upon a "Force Account" basis as provided in the Standard Specifications, Revision of December 2002, and as addressed in the contract documents.

Second: That the bid bond at 5% of the bid amount or the official bank check, cashier's check, certificate of deposit or U. S. Postal Money Order in the amount given in the "Notice to Contractors", payable to the Treasurer of the State of Maine and accompanying this bid, shall be forfeited, as liquidated damages, if in case this bid is accepted, and the undersigned shall fail to abide by the terms and conditions of the offer and fail to furnish satisfactory insurance and Contract bonds under the conditions stipulated in the Specifications within 15 days of notice of intent to award the contract.

Third: To begin the Work on the date specified in the Engineer's "Notice to Commence Work" as stated in Section 107.2 of the Standard Specifications Revision of 2002 and complete the Work within the time limits given in the Special Provisions of this Contract.

Fourth: The Contractor will be bound to the Disadvantaged Business Enterprise (DBE) Requirements contained in the attached Notice (Additional Instructions to Bidders) and submit a completed Contractor's Disadvantaged Business Enterprise Utilization Plan by 4:30pm on the day of bid opening to the Contracts Engineer.

Fifth: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Sixth: The Bidder hereby certifies, to the best of its knowledge and belief that: the Bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

IN WITNESS WHEREOF, the Contractor, for itself, its successors and assigns, hereby execute two duplicate originals of this Agreement and thereby binds itself to all covenants, terms, and obligations contained in the Contract Documents

Date

(Witness Sign Here)
Witness

CONTRACTOR
(Sign Here)

(Signature of Legally Authorized Representative
of the Contractor)

(Print Name Here)
(Name and Title Printed)

G. Award.

Your offer is hereby accepted.
documents referenced herein.

This award consummates the Contract, and the

MAINE DEPARTMENT OF TRANSPORTATION

Date

By: David A. Cole, Commissioner

(Witness)

BOND # _____

CONTRACT PERFORMANCE BOND
(Surety Company Form)

KNOW ALL MEN BY THESE PRESENTS: That _____
_____ **and the State of** _____, as principal,
and _____,
a corporation duly organized under the laws of the State of _____ and having a
usual place of business _____,
as Surety, are held and firmly bound unto the Treasurer of the State of Maine in the sum
of _____ **and 00/100 Dollars (\$** _____ **)**,
to be paid said Treasurer of the State of Maine or his successors in office, for which
payment well and truly to be made, Principal and Surety bind themselves, their heirs,
executors and administrators, successors and assigns, jointly and severally by these
presents.

The condition of this obligation is such that if the Principal designated as Contractor in
the Contract to construct Project Number _____ in the Municipality of
_____ promptly and faithfully performs the Contract, then this
obligation shall be null and void; otherwise it shall remain in full force and effect.

The Surety hereby waives notice of any alteration or extension of time made by the State
of Maine.

Signed and sealed this _____ day of _____, 20....

WITNESSES:

Signature.....
Print Name Legibly

Signature

Print Name Legibly

SURETY ADDRESS:
.....
.....
.....
TELEPHONE.....

SIGNATURES:

CONTRACTOR:

Print Name Legibly
SURETY:

Print Name Legibly
NAME OF LOCAL AGENCY:
ADDRESS

BOND # _____

CONTRACT PAYMENT BOND
(Surety Company Form)

KNOW ALL MEN BY THESE PRESENTS: That _____
_____ **and the State of** _____, as principal,
and _____
a corporation duly organized under the laws of the State of _____ and having a
usual place of business in _____,
as Surety, are held and firmly bound unto the Treasurer of the State of Maine for the use
and benefit of claimants as herein below defined, in the sum of
_____ **and 00/100 Dollars (\$** _____ **)**
for the payment whereof Principal and Surety bind themselves, their heirs, executors and
administrators, successors and assigns, jointly and severally by these presents.

The condition of this obligation is such that if the Principal designated as Contractor in
the Contract to construct Project Number _____ in the Municipality of
_____ promptly satisfies all claims and demands incurred for all
labor and material, used or required by him in connection with the work contemplated by
said Contract, and fully reimburses the obligee for all outlay and expense which the
obligee may incur in making good any default of said Principal, then this obligation shall
be null and void; otherwise it shall remain in full force and effect.

A claimant is defined as one having a direct contract with the Principal or with a
Subcontractor of the Principal for labor, material or both, used or reasonably required for
use in the performance of the contract.

Signed and sealed this _____ day of _____, 20 .. .

WITNESS:

SIGNATURES:

CONTRACTOR:

Signature.....

Print Name Legibly

SURETY:

Signature.....

Print Name Legibly

SURETY ADDRESS:

NAME OF LOCAL AGENCY:

ADDRESS

.....

TELEPHONE

SPECIAL PROVISION PARTNERING

The successful bidder will have the opportunity to enter into a cooperative partnership agreement with the State Department of Transportation for the contract. The objective of this agreement is the effective completion of the work on time and to the standard of quality that will be a source of pride to both the State and the Contractor. The partnering agreement will not affect the terms of the contract. It is intended only to establish an environment of cooperation between the parties. If the partnering agreement is accepted.


1. Contractor shall select and provide a third-party facilitator to conduct the team building workshop for the Contractor and Department personnel. Facilitator selection shall require Department concurrence. The cost for the facilitator and his associated expenses will be shared equally by the Department on the next monthly estimate, following receipt of invoice(s) from the Contractor, on an extra work basis.
2. Contractor and Department will exchange lists of the key personnel to be participants in the workshop. The list will contain the name and job title of each person, a contact phone number, and the address for job related correspondence.
3. The Contractor shall select the location and make all arrangements for space as required by facilitator, and for any meals required. This cost to be shared equally.
4. A working arrangement for the partnership will be agreed upon in writing at the workshop. The arrangement will set out the mutually recognized goals and expectation of the parties.
5. The Contractor and the Department agree to make an effort to maintain identified key personnel assigned to the work for its duration. A timely notice by each shall be given if changes by either must be made.
6. Project issues shall be processed in the manner agreed upon by the parties during the orientation.
7. Follow-up workshops may be held periodically throughout the duration of the contract as agreed by the Contractor and the Department.
8. The Partnering Agreement is not intended to be a legal document. Failure by either party to follow the process identified will not be grounds for any claim under the contract.
9. ARE YOU INTERESTED IN THIS OPPORTUNITY? YES _____ NO _____

STP-1121(400)X

END SECTION 2 - STA 70+50
BEGIN SECTION 3 - STA 70+50

END SECTION 3 - STA 145+32

BEGIN SECTION 4 - STA 27+50
END SECTION 4 - STA 62+25



BEGIN SECTION 1 - STA 11+05
END SECTION 1 - STA 49+43
BEGIN SECTION 2 - STA 49+43

LOCATION MAP



Scale in Miles

PIN 11214.00 - C.H.I.P.

SECTIONS 1 AND 3

HOT MIX ASPHALT OVERLAY,
PLANT MIX RECYCLED ASPHALT PAVEMENT,
DRAINAGE AND SAFETY IMPROVEMENTS,
VARIABLE DEPTH AND FULL DEPTH
GRAVEL AREAS.

PIN 12261.00
SECTIONS 2 AND 4

MAINTENANCE SURFACE TREATMENT

TRAFFIC DATA

RTE 150 NE/O SR 43	
Current (2004) AADT	3530
Future (2024) AADT	4940
DHV - % of AADT	10
Design Hour Volume	494
% Heavy Trucks (AADT)	8
% Heavy Trucks (DHV)	6
Directional Distribution (DHV)	60
18 kip Equivalent P 2.0	433
18 kip Equivalent P 2.5	412
Design Speed (mph)	45

STATE OF MAINE

DEPARTMENT OF TRANSPORTATION



ATHENS-CAMBRIDGE

SOMERSET COUNTY

RTE 150

STP-1121(400)X


C.H.I.P.

PROJECT LENGTH : 2.14 mi

PIN 12261.00

MAINTENANCE SURFACE TREATMENT

PROJECT LENGTH : 1.06 mi



TL

Harmony

Athens

END SECTION 3
STA 145+32

END SECTION 2
BEGIN SECTION 3
STA 70+50

END SECTION 1
BEGIN SECTION 2
STA 49+43

151

150

TL

BEGIN SECTION 1
STA 11+05

INDEX OF SHEETS

Description	Sheet No.
Title Sheet	1
Plan Sheets	1-18
Cross Sections	19-49



STATE OF MAINE	DEPARTMENT OF TRANSPORTATION
APPROVED	DATE
COMMISSIONER	04/03/04

DATE	3/25/04
P.E. NUMBER	9094
SIGNATURE	[Signature]

PROJECT INFORMATION	PROGRAM
DESIGNER	REGIONAL
PROJECT MANAGER	J. DEJAN
CONSULTANT	M. LEWIS
PROJECT RESIDENT	
CONTRACTOR	

PROJECT COMPLETION DATE	
-------------------------	--

ATHENS-CAMBRIDGE	RTE 150	TITLE SHEET
------------------	---------	-------------

SHEET NUMBER	1
--------------	---

PIN 11214.00
PIN 12261.00

STP-1121(400)X
PIN 12261.00


TRAFFIC DATA	
RTE 150 E/O SR 151	
Current (2004) AADT	2610
Future (2024) AADT	3650
DHV - % of AADT	10
Design Hour Volume	365
% Heavy Trucks (AADT)	10
% Heavy Trucks (DHV)	8
Directional Distribution (DHV)	60
18 kip Equivalent P 2.0	432
18 kip Equivalent P 2.5	412
Design Speed (mph)	35

TRAFFIC DATA	
RTE 150 SW/O SR 152	
Current (2004) AADT	1500
Future (2024) AADT	2100
DHV - % of AADT	10
Design Hour Volume	210
% Heavy Trucks (AADT)	17
% Heavy Trucks (DHV)	13
Directional Distribution (DHV)	60
18 kip Equivalent P 2.0	535
18 kip Equivalent P 2.5	509
Design Speed (mph)	35

TRAFFIC DATA	
RTE 150 N/O IR 580	
Current (2004) AADT	1620
Future (2024) AADT	2270
DHV - % of AADT	10
Design Hour Volume	227
% Heavy Trucks (AADT)	16
% Heavy Trucks (DHV)	12
Directional Distribution (DHV)	60
18 kip Equivalent P 2.0	531
18 kip Equivalent P 2.5	506
Design Speed (mph)	35

HOT MIX ASPHALT OVERLAY
PLANT MIX RECYCLED ASPHALT PAVEMENT
VARIABLE DEPTH ASC GRAVEL

NORMAL



NOTE:

ITEM 211.30 DITCH EXC. SHALL
INCLUDE RESTORING THE DITCH
TO ORIGINAL TEMPLATE OR AS
DIRECTED AND SHALL INCLUDE
REGRADING OF THE BACKSLOPE
AND INSLOPE TO THE SPECIFIED
TOLERANCES.

NOTE:

SHOULDER PAVEMENT SHALL
TAPER FROM 2³/₄" DEPTH AT
EDGE OF TRAVEL LANE TO 2¹/₄"
DEPTH AT OUTSIDE EDGE OF
SHOULDER

NOT TO SCALE

SHEET NUMBER

↓

OF 4

ATHENS-CAMBRIDGE
RTE 150

TYPICAL SECTIONS


PROJ. MANAGER	JOHN DEVIN	BY	DATE
CHECKED-REVIEWED			
DESIGN-DET-ALTD			
DESIGN-DET-ALTD2			
DESIGN-DET-ALTD3			
REVISIONS 1			
REVISIONS 2			
REVISIONS 3			
REVISIONS 4			
FIELD CHANGES			

DATE _____
B. NUMBER _____
SIGNATURE _____

STATE OF MAINE DEPARTMENT OF TRANSPORTATION	STP-1121(400)X	PIN 11214.00	HIGHWAY PLANS
--	----------------	-----------------	---------------

HOT MIX ASPHALT OVERLAY
PLANT MIX RECYCLED ASPHALT PAVEMENT
VARIABLE DEPTH ASC GRAVEL

CUT SECTION



NOTE:

4" MINIMUM OF DIRTY BORROW
WILL BE PLACED ON ALL INSLOPES
UNLESS OTHERWISE DIRECTED BY
THE RESIDENT. NO SEPARATE
PAYMENT WILL BE MADE, BUT SHALL
BE INCIDENTAL TO THE CONTRACT.

NOTE:

SHOULDER PAVEMENT SHALL
TAPER FROM 2 3/4" DEPTH AT
EDGE OF TRAVEL LANE TO 2 1/4"
DEPTH AT OUTSIDE EDGE OF
SHOULDER

NOT TO SCALE

STATE OF MAINE	DEPARTMENT OF TRANSPORTATION
STP-1121(400)X	PIN 11214.00
HIGHWAY PLANS	

PROJ. MANAGER	JOHN DEYH	BT	DATE
DESIGNED BY	DATE		
CHECKED BY	DATE		
DESIGN-DET. NO.	DATE		
REVISIONS	DATE		
REVISIONS 1	DATE		
REVISIONS 2	DATE		
REVISIONS 3	DATE		
REVISIONS 4	DATE		
FIELD CHANGES	DATE		


ATHENS-CAMBRIDGE	RTE 150	TYPICAL SECTIONS
------------------	---------	------------------

SHEET NUMBER	3	OF 4
--------------	---	------

HOT MIX ASPHALT OVERLAY
PLANT MIX RECYCLED ASPHALT PAVEMENT
VARIABLE DEPTH ASC GRAVEL

FILL SECTION

NORMAL



NOTE:

4" MINIMUM OF DIRTY BORROW
WILL BE PLACED ON ALL INSLOPES
UNLESS OTHERWISE DIRECTED BY
THE RESIDENT. NO SEPARATE
PAYMENT WILL BE MADE, BUT SHALL
BE INCIDENTAL TO THE CONTRACT.

NOTE:

EXCAVATION FROM
203 ITEMS TO BE
REUSED TO
BUILD SUBGRADE
NOT TO SCALE

SHOULDER PAVEMENT SHALL
TAPER FROM 2 3/4" DEPTH AT
EDGE OF TRAVEL LANE TO 2 1/4"
DEPTH AT OUTSIDE EDGE OF
SHOULDER

ATHENS-CAMBRIDGE
RTE 150
TYPICAL SECTIONS

SHEET NUMBER
4
OF 4

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
STP-1121(400)X
PIN
11214.00
HIGHWAY PLANS

PROJ. MANAGER
JOHN DEYER
DATE
SIGNATURE
P.L. NUMBER
DATE

REVISIONS
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
841
842
843
844
845
846
847
848
849
850
851
852
853
854
855
856
857
858
859
860
861
862
863
864
865
866
867
868
869
870
871
872
873
874
875
876
877
878
879
880
881
882
883
884
885
886
887
888
889
890
891
892
893
894
895
896
897
898
899
900
901
902
903
904
905
906
907
908
909
910
911
912
913
914
915
916
917
918
919
920
921
922
923
924
925
926
927
928
929
930
931
932
933
934
935
936
937
938
939
940
941
942
943
944
945
946
947
948
949
950
951
952
953
954
955
956
957
958
959
960
961
962
963
964
965
966
967
968
969
970
971
972
973
974
975
976
977
978
979
980
981
982
983
984
985
986
987
988
989
990
991
992
993
994
995
996
997
998
999
1000


Athens
STP-1121(400)X
Route 150, C.H.I.P.

Project Stationing		
	11+24	CMP 409/26
	13+66	CMP 410/25
CMP 411/24	15+56	
CMP 438/23	17+55	
CMP 439	19+16	
CMP 440/21	20+87	
CMP 441/6000	22+31	
CMP 442/19	23+93	
CMP 443/18	25+61	
CMP 445/17	27+28	
CMP 446/16	29+10	
CMP 447/15	30+53	
CMP 448/14	32+01	
CMP 449/13	33+46	
CMP 450/12	34+93	
CMP 452/11	36+44	
CMP 452/6000/10	37+84	
CMP 453/9	39+46	
CMP 454/8	41+33	
	42+84	CMP 456.1
CMP 456/7	42+93	
CMP 458/4	45+43	
	45+89	CMP 458/4/1
CMP 460/3/6010	47+83	
Eaton Corner Rd	48+28	
CMP 461/2	48+68	
	51+93	CMP 1/4
CMP 462/2000	50+55	
	51+31	Rt. 43/151
	52+37	CMP 5/6000/3/466000
	52+77	Rt. 43/151
	53+79	CMP 1/2
CMP 1.1	54+13	
CMP 9000/0	55+12	
	56+30	CMP 559100/2
	57+34	CMP 4/3
	57+92	School St
	58+12	CMP 4.5 S 4
CMP 4/4/9110	58+13	
	58+93	CMP 5/5
	60+19	CMP 6/6
	61+28	CMP 7/9130
	63+09	CMP 8
	64+94	CMP 9/9
Rt. 151	66+00	
CMP 901.1	68+96	
CMP 2/2000/1	69+41	
CMP 901.01/1	70+67	
CMP 902/2	72+21	
CMP 1/14	77+81	

Athens
STP-1121(400)X
Route 150, C.H.I.P.

Project Stationing		
CMP 4/52/5	79+89	
	80+19	
	80+42	CMP 6/5
	81+56	Back Rd
		CMP 16/130
CMP 7/7	82+85	
CMP 18/8	84+37	
CMP 19/9	86+50	
CMP 21/2000/10	88+72	
CMP 23/11	90+47	
CMP 24/2	91+70	
CMP 25/13	93+00	
CMP 26/14	94+29	
CMP 27/15	95+78	
CMP 28/16	95+73	
CMP 29/17	97+34	
CMP 30/18	98+48	
CMP 34/19	99+54	
CMP 33/2000/20	101+14	
CMP 34/21	103+06	
CMP 35S/22/1	104+67	
	105+88	CMP 35S/22
CMP 37/24	105+91	
CMP 38/25	108+50	
CMP 39/26	110+14	
CMP 40/27	111+58	
CMP 36/23	113+14	
	114+46	CMP 41/28
CMP 43/29	114+70	
CMP 44/2000/30	116+25	
CMP 45/31	117+95	
CMP 46/32	119+36	
CMP 47/33	120+64	
CMP 49.1	122+41	
	123+48	CMP 49/34
CMP 49.1/39.1	123+56	
	123+72	CMP 50/35
CMP 51/36	125+14	
CMP 52/37	126+92	
CMP 53/38	128+39	
CMP 55/39	130+15	
CMP 56/2000/40	131+69	
CMP 41	133+04	
CMP 58/42	134+36	
CMP 59.01	135+88	
CMP 59/43	137+26	CMP 59.01
CMP 60/44	139+03	
CMP 61/45	140+73	
CMP 63/46	142+11	
CMP 64/47	143+37	

Project Striping



Superelevations

Athens
STP-1121(400)X
Route 150, C.H.I.P.

SHOULDER	LT	STATION	RT	SHOULDER
		START		
-4.00	-2.00	11+05	-2.00	-4.00
		TO		
-4.00	-2.00	24+00	-2.00	-4.00
-4.00	-2.40	24+25	-1.20	-4.00
-4.00	-2.80	24+50	-0.40	-4.00
-4.00	-3.20	24+75	0.40	-4.00
-4.00	-3.60	25+00	1.20	-3.00
-4.00	-4.00	25+25	2.00	-3.00
-4.00	-4.40	25+50	2.80	-3.00
-4.80	-4.80	25+75	3.60	-2.00
-5.20	-5.20	26+00	4.40	-2.00
-5.60	-5.60	26+25	5.20	-2.00
-6.00	-6.00	26+50	6.00	-2.00
		TO		
-6.00	-6.00	28+50	6.00	-2.00
-5.56	-5.56	28+75	5.11	-2.00
-5.11	-5.11	29+00	4.22	-2.00
-4.67	-4.67	29+25	3.33	-3.00
-4.22	-4.22	29+50	2.44	-3.00
-4.00	-3.78	29+75	1.56	-3.00
-4.00	-3.33	30+00	0.67	-3.00
-4.00	-2.89	30+25	-0.22	-4.00
-4.00	-2.44	30+50	-1.11	-4.00
-4.00	-2.00	30+75	-2.00	-4.00
		TO		
-4.00	-2.00	44+50	-2.00	-4.00
-4.00	-1.41	44+75	-2.15	-4.00
-4.00	-0.81	45+00	-2.30	-4.00
-4.00	-0.22	45+25	-2.45	-4.00
-4.00	0.38	45+50	-2.60	-4.00
-3.00	0.97	45+75	-2.75	-4.00
-3.00	1.57	46+00	-2.90	-4.00
-3.00	2.16	46+25	-3.05	-4.00
-3.00	2.76	46+50	-3.20	-4.00
-3.00	3.35	46+75	-3.35	-4.00
		TO		
-3.00	3.35	48+75	-3.35	-4.00
-3.00	2.57	49+00	-2.57	-4.00
-3.00	1.79	49+25	-1.79	-4.00
MATCH	MATCH	49+43	MATCH	MATCH
HOT MAINTENANCE OVERLAY SECTION				
MATCH	MATCH	70+50	MATCH	MATCH
-3.00	1.55	70+75	-3.78	-4.00
-3.00	0.66	71+00	-3.33	-4.00
-4.00	-0.23	71+25	-2.89	-4.00
-4.00	-1.12	71+50	-2.44	-4.00
-4.00	-2.00	71+75	-2.00	-4.00

Superelevations

Athens
STP-1121(400)X
Route 150, C.H.I.P.

SHOULDER	LT	STATION	RT	SHOULDER
-4.00	-2.00	71+75	-2.00	-4.00
		TO		
-4.00	-2.00	77+50	-2.00	-4.00
-4.00	-2.29	77+75	-1.27	-4.00
-4.00	-2.58	78+00	-0.54	-4.00
-4.00	-2.87	78+25	0.19	-4.00
-4.00	-3.16	78+50	0.92	-3.00
-4.00	-3.45	78+75	1.65	-3.00
-4.00	-3.74	79+00	2.38	-3.00
-4.03	-4.03	79+25	3.11	-2.00
-4.32	-4.32	79+50	3.84	-2.00
-4.60	-4.60	79+75	4.60	-2.00
		TO		
-4.60	-4.60	81+50	4.60	-2.00
-4.37	-4.37	81+75	4.37	-2.00
-4.15	-4.15	82+00	4.15	-2.00
-4.00	-3.92	82+25	3.92	-2.00
-4.00	-3.70	82+50	3.70	-2.00
-4.00	-3.47	82+75	3.47	-2.00
-4.00	-3.25	83+00	3.25	-3.00
-4.00	-3.02	83+25	3.02	-3.00
-4.00	-2.80	83+50	2.80	-3.00
		TO		
-4.00	-2.80	85+50	2.80	-3.00
-4.00	-2.71	85+75	2.27	-4.00
-4.00	-2.62	86+00	1.74	-4.00
-4.00	-2.53	86+25	1.21	-4.00
-4.00	-2.44	86+50	0.68	-4.00
-4.00	-2.35	86+75	0.15	-4.00
-4.00	-2.26	87+00	-0.38	-4.00
-4.00	-2.17	87+25	-0.91	-4.00
-4.00	-2.08	87+50	-1.44	-4.00
-4.00	-2.00	87+75	-2.00	-4.00
		TO		
-4.00	-2.00	100+25	-2.00	-4.00
-4.00	-2.37	100+50	-1.18	-4.00
-4.00	-2.74	100+75	-0.37	-4.00
-4.00	-3.11	101+00	0.45	-4.00
-4.00	-3.48	101+25	1.26	-4.00
-4.00	-3.85	101+50	2.08	-4.00
-4.22	-4.22	101+75	2.89	-3.00
-4.59	-4.59	102+00	3.71	-2.00
-4.96	-4.96	102+25	4.52	-2.00
-5.34	-5.34	102+50	5.34	-2.00
		TO		
-5.34	-5.34	106+25	5.34	-2.00
-5.05	-5.05	106+50	5.05	-2.00
-4.76	-4.76	106+75	4.76	-2.00
-4.47	-4.47	107+00	4.47	-2.00
-4.18	-4.18	107+25	4.18	-2.00
-4.00	-3.89	107+50	3.89	-2.00
-4.00	-3.60	107+75	3.60	-2.00

Superelevations

Athens
STP-1121(400)X
Route 150, C.H.I.P.

SHOULDER	LT	STATION	RT	SHOULDER
-4.00	-3.30	108+00	3.30	-2.00
-4.00	-3.30	108+00	3.30	-2.00
		TO		
-4.00	-3.30	109+25	3.30	-2.00
-4.00	-3.16	109+50	2.71	-3.00
-4.00	-3.02	109+75	2.12	-4.00
-4.00	-2.88	110+00	1.53	-4.00
-4.00	-2.74	110+25	0.94	-4.00
-4.00	-2.60	110+50	0.35	-4.00
-4.00	-2.46	110+75	-0.24	-4.00
-4.00	-2.31	111+00	-0.83	-4.00
-4.00	-2.16	111+25	-1.42	-4.00
-4.00	-2.00	111+50	-2.00	-4.00
		TO		
-4.00	-2.00	138+50	-2.00	-4.00
-4.00	-1.55	138+75	-2.01	-4.00
-4.00	-1.09	139+00	-2.02	-4.00
-4.00	-0.64	139+25	-2.03	-4.00
-4.00	-0.18	139+50	-2.04	-4.00
-4.00	0.27	139+75	-2.05	-4.00
-4.00	0.73	140+00	-2.06	-4.00
-3.00	1.18	140+25	-2.07	-4.00
-3.00	1.64	140+50	-2.09	-4.00
-3.00	2.10	140+75	-2.10	-4.00
		TO		
-3.00	2.10	145+00	-2.10	-4.00
-4.00	0.05	145+25	-2.05	-4.00
-4.00	-2.00	145+32	-2.00	-4.00
		END		

Superelevations were computer generated.

Superelevations shall be rounded to the nearest half percent.

PROPOSED VERSUS
EXISTING
CENTERLINE
ELEVATION

Athens
STP-1121(400)X
Route 150, C.H.I.P.

Station	Existing	Proposed	Station	Existing	Proposed
11+00	424.34	424.34	36+50	368.13	370.32
11+50	422.94	423.44	37+00	365.31	367.81
12+00	421.50	422.50	37+50	363.35	365.54
12+50	420.32	421.32	38+00	361.71	363.28
13+00	419.06	420.06	38+50	360.51	361.47
13+50	418.25	419.25	39+00	359.76	360.09
14+00	417.98	418.98	39+50	359.18	360.59
14+50	417.78	418.78	40+00	358.54	359.37
15+00	418.02	419.02	40+50	358.18	359.01
15+50	418.26	419.33	41+00	357.74	358.57
16+00	418.84	419.69	41+50	357.28	358.12
16+50	419.68	420.05	42+00	357.02	357.85
17+00	420.13	420.92	42+50	356.81	357.64
17+50	420.22	421.20	43+00	356.49	357.32
18+00	420.15	420.93	43+50	356.14	356.97
18+50	419.36	420.02	44+00	355.68	356.51
19+00	417.17	417.99	44+50	355.23	356.06
19+50	414.16	415.82	45+00	354.70	355.53
20+00	411.29	413.16	45+50	354.02	354.86
20+50	408.81	410.85	46+00	353.21	354.04
21+00	407.37	409.04	46+50	352.18	353.01
21+50	406.72	407.72	47+00	350.75	351.58
22+00	406.22	406.89	47+50	349.14	349.97
22+50	405.84	406.50	48+00	347.75	348.58
23+00	405.75	406.17		HMM	
23+50	405.58	406.42	70+00	381.01	381.67
24+00	405.43	406.26	70+50	382.04	382.70
24+50	405.30	406.13	71+00	383.07	383.73
25+00	404.92	405.76	71+50	384.17	384.83
25+50	404.36	405.19	72+00	385.38	386.05
26+00	404.07	404.91	72+50	386.51	387.18
26+50	403.98	404.82	73+00	387.63	388.30
27+00	404.21	405.16	73+50	388.50	389.16
27+50	405.08	404.99	74+00	389.61	390.27
28+00	406.42	405.31	74+50	390.78	391.44
28+50	407.04	405.06	75+00	392.12	392.78
29+00	406.07	404.05	75+50	393.40	394.07
29+50	403.07	402.27	76+00	395.03	395.69
30+00	399.13	399.72	76+50	397.22	397.88
30+50	395.43	396.61	77+00	400.07	400.73
31+00	392.18	393.48	77+50	403.43	404.09
31+50	389.63	390.35	78+00	407.02	407.68
32+00	387.57	388.23	78+50	411.02	411.69
32+50	385.95	386.62	79+00	415.39	416.05
33+00	384.52	385.19	79+50	419.55	420.21
33+50	383.09	383.76	80+00	423.26	423.93
34+00	381.56	382.22	80+50	426.24	426.90
34+50	379.92	380.59	81+00	428.77	429.43
35+00	378.28	378.94	81+50	430.95	431.62
35+50	375.89	376.86	82+00	433.01	433.68
36+00	372.03	373.61	82+50	434.98	435.64

PROPOSED VERSUS
EXISTING
CENTERLINE
ELEVATION

Athens
STP-1121(400)X
Route 150, C.H.I.P.

	Existing	Proposed		Existing	Proposed
83+00	436.51	437.17	108+50	424.39	425.05
83+50	437.35	438.01	109+00	423.24	423.90
84+00	437.62	438.29	109+50	422.35	423.02
84+50	437.37	438.03	110+00	421.38	422.05
85+00	436.56	437.22	110+50	419.89	420.55
85+50	435.62	436.28	111+00	418.20	418.86
86+00	434.64	435.30	111+50	416.79	417.46
86+50	433.58	434.24	112+00	416.03	416.69
87+00	432.25	432.91	112+50	416.10	416.66
87+50	430.38	431.05	113+00	416.98	417.64
88+00	427.83	428.43	113+50	418.54	418.70
88+50	424.37	426.31	114+00	420.38	421.05
89+00	421.10	424.10	114+50	421.82	422.48
89+50	418.67	421.67	115+00	422.51	423.17
90+00	417.14	420.14	115+50	422.96	423.62
90+50	416.19	419.19	116+00	423.68	424.34
91+00	415.80	418.80	116+50	425.00	425.67
91+50	415.56	418.56	117+00	426.72	427.38
92+00	415.72	418.72	117+50	428.27	428.94
92+50	416.27	419.27	118+00	429.61	430.28
93+00	416.77	419.77	118+50	431.09	431.75
93+50	416.72	419.72	119+00	433.18	433.84
94+00	416.91	419.91	119+50	435.81	436.48
94+50	418.00	421.00	120+00	438.13	438.79
95+00	420.24	423.24	120+50	439.41	440.07
95+50	423.64	426.26	121+00	440.08	440.74
96+00	427.61	429.46	121+50	440.52	441.18
96+50	431.13	432.22	122+00	440.46	441.12
97+00	434.31	434.97	122+50	439.98	440.64
97+50	436.55	437.21	123+00	439.52	440.18
98+00	437.30	437.96	123+50	439.02	439.68
98+50	435.70	436.00	124+00	437.87	438.53
99+00	432.04	433.07	124+50	435.40	436.06
99+50	427.42	430.22	125+00	432.53	433.19
100+00	423.48	428.10	125+50	430.52	431.18
100+50	421.28	426.88	126+00	429.00	429.67
101+00	421.12	426.56	126+50	427.41	428.07
101+50	422.98	427.13	127+00	425.27	425.93
102+00	426.23	428.54	127+50	422.66	423.32
102+50	429.77	430.43	128+00	420.01	420.67
103+00	431.87	432.54	128+50	417.40	418.07
103+50	433.64	434.31	129+00	414.89	415.55
104+00	435.22	435.88	129+50	412.36	413.03
104+50	435.32	435.98	130+00	409.87	410.53
105+00	434.62	435.29	130+50	407.27	407.94
105+50	434.06	434.73	131+00	404.76	405.42
106+00	433.55	434.21	131+50	402.58	403.24
106+50	432.45	433.11	132+00	401.07	401.73
107+00	430.57	431.23	132+50	400.10	400.77
107+50	428.33	428.99	133+00	399.80	400.46
108+00	426.28	426.94	133+50	400.17	400.83

PROPOSED VERSUS
EXISTING
CENTERLINE
ELEVATION

Athens
STP-1121(400)X
Route 150, C.H.I.P.

station	Existing	Proposed	Existing	Proposed
134+00	400.90	401.56		
134+50	401.97	402.63		
135+00	403.48	404.14		
135+50	405.46	406.12		
136+00	407.57	408.24		
136+50	409.03	409.69		
137+00	410.45	411.12		
137+50	411.37	412.03		
138+00	411.57	412.23		
138+50	411.50	412.16		
139+00	411.24	411.90		
139+50	411.02	411.69		
140+00	410.84	411.51		
140+50	410.73	411.40		
141+00	410.95	411.61		
141+50	411.37	412.03		
142+00	411.86	412.53		
142+50	412.80	413.46		
143+00	414.09	414.76		
143+50	415.67	416.33		
144+00	417.81	418.47		
144+50	420.21	420.87		
145+00	422.22	422.89		

Construction Notes

Item 201.11 Clearing

<u>STATION-STATION</u>	<u>AREA</u>
28+95-29+58 Lt.	50.6 ft ²
30+01-30+23 Rt.	28.9 ft ²
34+86-36+21 Rt.	301.4 ft ²
77+98-79+90 Lt.	555.2 ft ²
79+85-80+22 Lt.	88.2 ft ²
90+49-92+63 Lt.	478.9 ft ²
89+90-91+09 Lt.	154.5 ft ²
92+04 Lt. (outlet)	147.2 ft ²
92+33-92+59 Lt.	20.3 ft ²
93+74-94+48 Lt.	223.0 ft ²
97+79-98+05 Lt.	20.9 ft ²
99+27-101+63 Lt.	2577.9 ft ²
100+10-101+31 Rt.	1025.8 ft ²
108+00-108+50 Lt.	279.2 ft ²
112+03-112+34 Rt.	140.6 ft ²
113+27-115+27 Lt.	607.4 ft ²
114+76-115+85 Rt.	397.9 ft ²
119+19-120+06 Rt.	297.7 ft ²
124+74-125+05 Lt.	56.7 ft ²
126+71-126+85 Lt.	72.6 ft ²
131+25-131+75 Lt.	529.0 ft ²
140+20-140+42 Lt.	26.1 ft ²
140+66-140+78 Lt.	14.5 ft ²

Item 202.202 Removing Pavement Surface

Station 49+43 – 49+87 Bridge Deck

Item 202.203 Pavement Butt Joints

STATION

11+05 ML
145+32 ML
1 Side Roads
11 Paved Drives

Construction Notes

Item 203.20 Common Excavation

Full Construction area: 27+45 – 29+85

- Excavation of drives in the Full Construction area will be paid as 203.20

Item 203.21 Rock Excavation

See cross sections for full reconstruction areas. Only one boring was taken in the ledge area so assumptions were made.

Item 211.21 Inslope Rehabilitation

<u>LEFT</u>	<u>LENGTH</u>	<u>RIGHT</u>	<u>LENGTH</u>
11+00 - 11+25	25	11+00 - 11+25	25
39+36 - 40+00	64	16+52 - 16+81	29
66+85 - 68+77	192	17+22 - 18+31	109
69+37 - 69+80	43	18+66 - 18+75	9
71+43 - 71+87	44	23+25 - 25+38	213
72+12 - 77+11	499	25+62 - 27+45	183
77+40 - 79+44	204	39+00 - 42+41	341
97+00 - 97+11	11	48+12 - 48+40	28
98+39 - 98+60	21	77+56 - 80+06	250
102+45 - 103+17	72	80+74 - 81+96	122
103+58 - 113+37	979	83+83 - 84+22	39
114+66 - 116+27	161	84+51 - 86+54	203
117+93 - 120+73	280	87+46 - 87+90	44
127+59 - 134+33	674	102+45 - 103+94	149
143+86 - 145+32	146	104+37 - 110+84	647
		111+17 - 113+89	272
		114+65 - 119+18	453
		125+14 - 126+67	156
		127+58 - 132+12	454
		132+47 - 137+04	457
		137+86 - 140+41	255
		141+82 - 142+10	28
		142+47 - 142+71	24
		144+20 - 145+32	112

Construction Notes

Item 211.30 Ditch Excavation

<u>LEFT</u>	<u>LENGTH</u>	<u>RIGHT</u>	<u>LENGTH</u>
16+50 - 16+73	23	69+30 - 70+07	77
18+35 - 18+75	40	74+86 - 77+56	270
23+25 - 23+52	27	81+96 - 82+08	12
23+90 - 24+70	80	82+29 - 83+83	154
25+20 - 26+80	160	86+79 - 87+46	67
40+00 - 40+12	12	97+00 - 97+25	25
40+56 - 41+11	55	97+56 - 98+60	104
47+70 - 47+85	15	113+89 - 114+37	48
67+25 Connect	70	119+18 - 120+64	146
69+80 - 70+00	20	123+30 - 123+87	57
70+34 - 71+43	109	124+13 - 125+14	101
85+82 - 86+58	76	126+67 - 127+58	91
86+91 - 87+90	99	140+41 - 141+82	141
97+11 - 98+39	128	142+71 - 144+20	149
113+37 - 114+66	129		
116+27 - 116+62	35		
116+86 - 117+93	107		
125+91 - 127+59	168		
134+33 - 134+65	32		
135+00 - 137+65	265		
137+92 - 140+37	245		
140+66 - 143+86	320		

Item 211.41 New Ditch Excavation - Ledge

<u>LEFT</u>	<u>LENGTH</u>	<u>RIGHT</u>	<u>LENGTH</u>
79+44 - 81+16	172	66+85 - 68+86	201
81+43 - 85+82	439	69+30 - 70+07	77

- Notes:**
1. The stations listed under item 211.41 are the only areas that will be considered for new ditch.
 2. Inslope and ditch work within the following areas will be paid for by Item 203.20 common excavation. Inslope fill sections will be incidental to item 203.20 common excavation. Stations 11+25-16+50, 18+75-23+25, 27+45-39+00, 87+90-97+00, 98+60-102+45.

Construction Notes

Item 304.10 Aggregate Subbase Course-Gravel

<u>STATION - STATION</u>	<u>DESCRIPTION</u>	<u>COMMENTS</u>
11+25 – 16+50*	Variable Gravel	6" max depth
16+50 – 18+75	Gravel	6" depth
18+75 – 23+25*	Variable Gravel	18" max depth
23+25 - 27+45	Gravel	6" depth
27+45 – 29+85*	Full Construction	24" depth
29+85 – 39+00*	Variable Gravel	24" max depth
39+00 - 48+00	Gravel	6" depth
70+50 -87+90	Gravel	4" depth
87+90 – 97+00*	Variable Gravel	See crosssections
97+00 - 98+60	Gravel	4" depth
98+60 – 102+45*	Variable Gravel	See crosssections
102+45 - 145+12	Gravel	4" Depth
Various Drives	Variable Gravel	

*See cross sections

Item 310.23 3" Plant Mixed Recycled Asphalt Pavement

11+25 – 49+43 and 70+50 – 145+12 Full Width

Average depth of existing pavement on travel way are as follows:

Station	Offset (ft)	Pavement Depth (in)
14+89	7.4 Rt.	7.2
16+39	8.4 Rt.	6.0
19+39	7.7 Rt.	6.0
22+39	8.7 Rt.	6.0
26+89	9.0 Rt.	4.8
28+89	8.5 Rt.	6.0
32+89	8.0 Rt.	2.4
43+39	8.0 Rt.	3.6
47+69	9.0 Rt.	2.4
68+69	6.7 Rt.	8.4
70+19	7.6 Rt.	6.0
76+19	7.0 Rt.	7.2
83+69	7.0 Rt.	7.2
86+69	7.5 Rt.	7.2
94+19	8.6 Rt.	7.2
109+19	9.3 Rt.	7.2
116+69	9.0 Rt.	7.2
122+69	9.0 Rt.	6.0
125+69	9.2 Rt.	7.2
133+69	9.2 Rt.	7.2

Construction Notes

Item 403.210 HMA 9.5 mm Surface

STATION - STATION

11+05 – 49+87 Mainline and Shoulders

70+50 – 145+32 Mainline and Shoulders

NOTE:

- Shoulder pavement shall taper from 1-1/4" depth at edge of travel lane to 1" depth at edge of shoulder except in Full Construction area

Item 403.213 HMA 12.5mm Base

STATION - STATION

11+25 – 49+43 Mainline and Shoulders

70+50 – 145+12 Mainline and Shoulders

NOTE:

- Shoulder pavement shall taper from 1-1/2" depth at edge of travel lane to 1-1/4" depth at edge of shoulder except in Full Construction area

Item 411.10 Untreated Aggregate Surface Course, Truck Measure

This item to be used to back up paved lips, entrances and turnouts as directed by MDOT Resident (or his/her designee). Depths over 4" will be backed up utilizing 304.103.

Item 603.16 15" Culvert Pipe Option I

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
12+32 Rt.	30	Replace Existing
19+30 Lt.	40	New Location
20+05 Lt.	40	New Location
23+74 Lt.	30	Replace Existing
24+97 Lt.	50	New Location
31+46 Lt.	30	Replace Existing
42+80 Rt.	55	New Outlet in Catch Basin
69+11 Rt.	50	New Location
82+17 Rt.	30	New Location
102+14 Rt.	30	Replace Existing
116+75 Lt.	30	New Location
137+79 Lt.	50	New Location
Undetermined Locations	60 Feet	

Construction Notes

Item 603.17 18" Culvert Pipe Option I

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
70+18 Lt.	30	Replace Existing
69+10 Lt.	50	Replace Existing
Undetermined locations	40 Feet	

Item 603.179 18" Culvert Pipe Option III

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
14+09	50	Replace Existing
21+80	50	Replace Existing
26+63	55	Replace Existing
35+28	60	Replace Existing
41+80	42	Connects to CB 42+80 Rt.
48+11	70	Replace Existing
67+27	70	Replace Existing
92+04	66	Replace Existing
108+39	65	Replace Existing
115+57	5	Extend Rt.
140+75	45	New Location (Replaces 142+04)

Item 603.199 24" Culvert Pipe Option III

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
112+12	5	Extend Rt.

Item 603.219 36" Culvert Pipe Option III

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
100+70	94	Replace Existing

Item 603.279 72" Culvert Pipe Option III

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
131+46	15	Extend Lt.

Construction Notes

Item 603.7315 Remove & Relay 15" Metal Pipe

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
140+49 Lt.	30	
32+46 Lt.	28	

Item 604.092 Catch Basin Type B1-C

<u>STATION</u>	<u>QUANTITY</u>
41+80 Rt.	1
44+80 Rt.	1
44+80 Lt.	1

Item 605.09 6" U.D. Type B

<u>STATION - STATION</u>	<u>LENGTH</u>
42+50 – 44+80 Lt.	230

Item 605.11 12" U.D. Type C

<u>STATION - STATION</u>	<u>LENGTH</u>
44+80 – 47+75 Lt.	295

Item 605.13 18" U.D. Type C

<u>STATION - STATION</u>	<u>LENGTH</u>
41+80 – 44+80 Rt.	300
44+80 – 48+25 Rt.	345

Item 606.1722 Bridge Transition Type II

<u>STATION - STATION</u>	<u>QUANTITY</u>
49+28.75-49+43 Lt.	1
49+28.75-49+43 Rt.	1

Item 606.23 Guardrail Type 3c – Single Rail

<u>STATION-STATION</u>	<u>LENGTH</u>
48+79 – 48+28 Rt.	50
48+79 – 48+28 Lt.	50

Construction Notes

Item 606.231 Guardrail Type 3c – 15 ft Radius or Less

<u>STATION-STATION</u>	<u>LENGTH</u>
48+70.00 – 48+78.75 Lt.	12.5

Item 606.22 Guardrail Type 3c - Over 15 ft Radius

<u>STATION-STATION</u>	<u>LENGTH</u>
48+70.00 – 48+78.75 Lt.	12.5

Item 606.265 Terminal End - Single Rail - Galvanized

<u>STATION</u>	<u>QUANTITY</u>
48+70 Lt.	1

Item 606.754 Widen Shoulder for 350 End Treatment

<u>STATION - STATION</u>	<u>QUANTITY</u>
47+72.325 – 48+78.75 Rt.	1

Item 606.79 Guardrail 350 Flared Terminal

<u>STATION - STATION</u>	<u>QUANTITY</u>
48+41.25 – 48+78.75 Rt.	1

Item 609.31 Curb Type 3

<u>LEFT</u>	<u>LENGTH</u>	<u>RIGHT</u>	<u>LENGTH</u>
16+50 - 16+73	23	27+59 - 28+26	67
16+97 - 18+35	138	28+46 - 29+64	118
27+05 - 28+33	128	42+73 - 46+33	360
42+73 - 43+01	28	46+51 - 48+12	161
43+39 - 44+27	88		
44+60 - 45+83	123		
46+00 - 47+70	170		
123+32 - 123+70	38		
123+91 - 125+91	200		

Construction Notes

Item 610.08 Plain Rip Rap

<u>STATION</u>	<u>COMMENTS</u>
14+09	Pipe end treatments and pad
21+80	Pipe end treatments and pad
26+63	Pipe end treatments and pad
35+28	Pipe end treatments and pad
47+75 Lt.	Underdrain outlet
48+25 Rt.	Underdrain outlet
48+41	Pipe end treatments and pad
48+41 Rt.	Level spreader
67+27	Pipe end treatments and pad
78+25	Pipe end treatments and pad
92+04	Pipe end treatments and pad
100+70	Pipe end treatments
108+39	Pipe end treatments and pad
112+12 Rt.	Pipe end treatment and pad
131+46 Lt.	Pipe end treatment

And as directed by the Resident

Item 610.18 Stone Ditch Protection

<u>LEFT</u>	<u>RIGHT</u>
<u>STATION - STATION</u>	<u>STATION - STATION</u>
30+50- 31+25	76+75-77+50
88+25-88+75	96+50-97+30
125+91-127+50	124+25-125+15
	127+00-127+50

Item 613.319 Erosion Control Blanket

This item to be used in all ditches. Some ditches may require a double width. The MDOT Resident (or his/her designee) may also require this item placed on some slopes, pipe ends and driveway radii.

Item 615.07 Loam

This item to be used at the discretion of the MDOT Resident (or his/her designee).

Construction Notes

Item 618.1301 Seeding Method 1 - Plan Quantity

This item to be used at the discretion of the MDOT Resident (or his/her designee)

Item 618.1401 Seeding Method 2 - Plan Quantity

This item to be used in all disturbed areas other than Method 1.

Item 619.1201 Mulch - Plan Quantity

This item to be used in all disturbed areas. Areas shall be maintained on a daily Basis until an acceptable growth of grass is obtained.

Item 620.58 Erosion Control Geotextile

This Item to be used under Rip Rap and Stone Ditch Protection as directed by the MDOT Resident (or his/her designee).

Item 629.05 and 631's

Rental Items to be used for miscellaneous tasks. A dug well on the property of John M. and Cynthia J. Anderson shall be filled with excavation and paid for under equipment rental items.

GENERAL NOTES

- 1) All joints between existing and proposed hot bituminous pavement shall be butted. Payment shall be made under Item 202.203 Pavement Butt Joint.
- 2) Construct Butt Joints at all paved drives and entrances, as directed by the Resident.
- 3) The Contractor shall place suitable existing material or other material acceptable to the Resident, on all pavement edges to allow no greater than a 1 ¼ inch drop-off and flatten all non guardrail inslopes to a minimum slope of 3:1. Payment will be incidental to the contract and/or appropriate inslope and ditch items.
- 4) All wood posts on 350 terminal end installations shall be cut so that no more than 1 inch is exposed above the beam.
- 5) All waste material not used on the project shall be disposed of off the project in waste areas approved by the MDOT personnel. All work necessary to dispose of waste material (including grading, seeding, and mulching) will be considered incidental to the contract items.
- 6) Any damage to the slopes caused by the Contractor's equipment, personnel, or operation shall be repaired to the satisfaction of the MDOT personnel. All work, equipment and materials required to make repairs shall be at the Contractor's expense.
- 7) Any necessary cleaning of existing pavement prior to paving shall be incidental to the related paving items.
- 8) When super elevation exceeds the slope of the low side shoulder, the shoulder will have same slope as traveled way.
- 9) The following shall be incidental to the 603 item(s):
 - Any cutting of existing culverts and or connectors necessary to install new culvert replacements or extensions
 - All pipe excavation including any cutting and removal of pavement
 - All ditching at pipe ends
 - Furnishing, placing, grading, and compacting of any new gravel and/or fill material including Granular Borrow used under pipes and for temporary detours to maintain traffic during pipe installation (excavation is also incidental)
 - Granular Borrow under the pipe shall meet the requirements for Underwater Backfill
 - All work necessary to connect to existing pipes
 - Flow lines may be changed by 18 inches
 - Any necessary clearing of brush, small trees, and headwalls at culvert ends
- 10) No existing drainage shall be abandoned, removed or plugged without prior approval of the MDOT personnel.

GENERAL NOTES


- 11) Where existing excavation in drainage trenches is deemed unusable, a suitable similar or impervious material, acceptable to the Resident, will be obtained for use as backfill in drainage trenches to subgrade. Payment will be incidental to 603 items.
- 12) Existing culverts and catch basins will be cleaned as directed by the MDOT personnel under the appropriate Pay Items.
- 13) As directed by the MDOT personnel, all existing Underdrain Outlets shall be located, cleaned out, and ditched as required or replaced as necessary. Payment will be made under appropriate hourly contract items.
- 14) All connections for Underdrain to roadway culverts will be incidental to U.D. pipe items.
- 15) Backing up bituminous curb is incidental to the curb items. In areas where new bituminous curb is designated to replace existing, the removal of the old bituminous curb shall be incidental to the new curb.
- 16) Trim all tree branches to 20 ft above pavement. Payment shall be made under the appropriate labor and equipment rental items.
- 17) "Undetermined Locations" shall be determined by the MDOT personnel.
- 18) Stations referenced are approximate.
- 19) All work shall be done in accordance with the Maine Department of Transportation's Best Management Practices for Erosion Control & Sediment Control, January, 2000.
- 20) MDOT will final stripe the project.
- 21) Tacking of joints shall be in accordance with 2002 specifications
- 22) Project stationing will be laid out first time only by MDOT personnel on existing pavement and will then be maintained by the Contractor immediately after loss of said stationing due to paving, milling, or reclaiming operations.
- 23) Dust control will not be paid for directly, but will be considered incidental to the Erosion Control Plan (SEWPCP) and Traffic Control Plan.
- 24) All pavement milling areas will have all pavement removed with minimal contamination. Any remaining material not broken up will require reclaiming or some other means of removal. Shoulder material shall be graded smooth (to be graded to match existing gravel grade) to drain prior to shutdown on the day the millings are removed. This grading will be considered incidental to the contract. The removal of and disposing of this material shall be considered incidental to Items 211.21, 211.30 and this contract.

GENERAL NOTES

- 25) The existing gravel structure will be graded to proposed x-slopes and compacted immediately following removal of pavement and shall be considered incidental to item 310.23. See Special Provision 310. A minimum of 4" ASC gravel will be placed, graded and compacted to the proper cross slope and will be paid under Item 304.10.
- 26) All roadway drainage installation trenches will require a minimum of 3 inches of 12.5mm base pavement on the same day or as directed by the Resident. Payment will be incidental to the contract as per Standard Specification 105.4.1.
- 27) The contractor shall back up the 3" drop off from the edge of shoulder the same day as the PM RAP is placed. This work shall be considered incidental to the contract.
- 28) The contractor is responsible for the careful **side staking** of existing centerline as per standard specification 105.6.2. Side stakes shall be placed safely outside of the construction limits and the existing centerline grades for the existing gravel (after re-grading and compacting) shall be transferred to these stakes and the appropriate additional gravel added. All layout, stakes, and grades will be checked and must be acceptable to the Resident.
- 29) The contractor will be responsible for maintaining all existing mailboxes to ensure that the mail will be deliverable. No separate payment will be made for this work; it shall be considered incidental to the contract.
- 30) Dredge Material (See MDOT Standard Specifications § 101.2) is regulated as a Special Waste. Fifty cubic yards or less of Dredge Material **Beneficially Used in the area adjacent to and draining into the dredged water body** is exempt from Beneficial Use Permits. The Contractor shall ensure that Dredge Material is placed into the fill areas specified by MDOT. No more than the fifty cubic yards (38 cubic meters) of Dredge Material may be excavated without authorization from the Resident. Any Dredge Material not Beneficial Used (excess Dredge Material) shall be disposed of at a landfill licensed by the Maine Department of Environmental Protection to accept Special Waste. The Contractor shall be responsible for making all necessary arrangements for dewatering and proper disposal of the Dredge Material, including any additional laboratory testing, in accordance with the landfill's license. The Contractor shall provide documentation to the Resident that any such Dredge Material was disposed of as specified.

STP-1121(400)X

END SECTION 2 - STA 70+50
BEGIN SECTION 3 - STA 70+50
END SECTION 3 - STA 145+32
BEGIN SECTION 4 - STA 27+50
END SECTION 4 - STA 62+25



BEGIN SECTION 1 - STA 11+05
END SECTION 1 - STA 49+43
BEGIN SECTION 2 - STA 49+43



PIN 11214.00 - C.H.I.P.
SECTIONS 1 AND 3
HOT MIX ASPHALT OVERLAY
PLANT MIX RECYCLED ASPHALT PAVEMENT,
DRAINAGE AND SAFETY IMPROVEMENTS,
VARIABLE DEPTH AND FULL DEPTH
GRAVEL AREAS.

PIN 12261.00
SECTIONS 2 AND 4
MAINTENANCE SURFACE TREATMENT

TRAFFIC DATA	
RTE 150 NE/O SR 43	
Current (2004) AADT	3530
Future (2024) AADT	4940
DHV - % of AADT	10
Design Hour Volume	494
% Heavy Trucks (AADT)	8
% Heavy Trucks (DHV)	6
Directional Distribution (DHV)	60
18 kip Equivalent P 2.0	433
18 kip Equivalent P 2.5	412
Design Speed (mph)	45

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION




ATHENS-CAMBRIDGE
SOMERSET COUNTY

RTE 150
STP-1121(400)X
C.H.I.P.

PROJECT LENGTH : 2.14 mi
PIN 12261.00
MAINTENANCE SURFACE TREATMENT
PROJECT LENGTH : 1.06 mi

INDEX OF SHEETS

Description	Sheet No.
Title Sheet	1
Plan Sheets	1-18
Cross Sections	19-49



TRAFFIC DATA	
RTE 150 SW/O SR 152	
Current (2004) AADT	1500
Future (2024) AADT	2100
DHV - % of AADT	10
Design Hour Volume	210
% Heavy Trucks (AADT)	17
% Heavy Trucks (DHV)	13
Directional Distribution (DHV)	60
18 kip Equivalent P 2.0	535
18 kip Equivalent P 2.5	509
Design Speed (mph)	35

TRAFFIC DATA	
RTE 150 N/O IR 580	
Current (2004) AADT	1620
Future (2024) AADT	2270
DHV - % of AADT	10
Design Hour Volume	227
% Heavy Trucks (AADT)	16
% Heavy Trucks (DHV)	12
Directional Distribution (DHV)	60
18 kip Equivalent P 2.0	531
18 kip Equivalent P 2.5	506
Design Speed (mph)	35

PIN 11214.00
PIN 12261.00

STATE OF MAINE DEPARTMENT OF TRANSPORTATION	
APPROVED	DATE
CHIEF ENGINEER	
COMMISSIONER	
DATE	



SIGNATURE	DATE
P.E. NUMBER	3/25/07
9094	

PROJECT INFORMATION	
PROGRAM	REGIONAL
PROJECT MANAGER	J. DENIN
DESIGNER	M. LEMKO
CONSULTANT	
PROJECT RESIDENT	
CONTRACTOR	
PROJECT COMPLETION DATE	

ATHENS-CAMBRIDGE	RTE 150	TITLE SHEET
------------------	---------	-------------

SHEET NUMBER	1
--------------	---

Section I in town Athens

STATIONING

Eaton Corner Rd	48+28	
Begin MST	49+43	
CMP 462/2000	50+55	
	51+31	Rt. 43/151
	52+77	Rt. 43/151
	53+79	CMP 1/2
CMP 1.1	54+13	
CMP 9000/0	55+12	
	57+92	School St
	58+12	CMP 4.5 S 4
CMP 4/4/9110	58+13	
	58+93	CMP 5/5
	61+28	CMP 7/9130
	63+09	CMP 8
	64+94	CMP 9/9
Rt. 151	66+00	
CMP 901.1	68+96	
CMP 2/2000/1	69+41	
End MST	70+50	

Section II in town Cambridge

STATIONING

Begin MST	27+50	
CMP 6	28+86	
CMP 5	30+44	
CMP 3	33+96	
CMP 2	35+57	
	36+59	CMP 1
CMP 4300/1	37+11	
	37+94	Route 152
	38+85	Route 152
CMP 153	39+36	
	41+16	Dexter Rd
	42+38	Dexter Rd
	43+20	CMP 156
Ham Hill Rd	44+20	
	45+04	CMP 158
CMP 160/40	47+58	
CMP 161/41	49+00	
CMP 163/43	51+77	
CMP 164/44	53+46	
North Rd	55+15	
	58+90	CMP 168/47
	60+36	CMP 169/48
	61+89	CMP 170/49
End MST	62+25	

Section I in town Athens

Double
Yellow

Section II in town Cambridge

North Road

Ham Hill Road

End Project
62+25

STA 55+56

STA 54+74

STA 44+41

STA 44+00

STA 42+62
Dexter Road
STA 42+13

STA 41+33

STA 40+98

STA 39+09
Route 152
37+67

BEGIN PROJ 27+50

Construction Notes

Item 409.15 Tack Coat

A tack coat shall be applied at a rate of 0.025 G/SY prior to Shimming and surfacing.

Item 461.210 Maintenance Surface Treatment 9.5 mm

STATION - STATION

Section I 49+43 -70+50 Drag Shim and 5/8" Surface

Section II 27+50-62+25 5/8" Surface

NOTE: This item shall conform to the requirements for a 9.5mm fine HMA
As per the standard Specifications.

Item 652.39 Work Zone Traffic Control

The contractor will be responsible for supplying all traffic control
Devises and the maintenance there of.


GENERAL NOTES

1. Any damage to the slopes caused by the Contractor's equipment, personnel, or operation shall be repaired to the satisfaction of the Resident. All work, equipment and materials required to make repairs shall be at the Contractor's expense.
2. Any necessary cleaning of existing pavement prior to paving shall be incidental to the related paving items.
3. Shoulder shim shall taper to 0 at the midway of the shoulder.
4. Stations referenced are approximate.
5. Grind transition tapers at Catch Basins under Item No. 202.203, Pavement Butt Joints, as directed by the Resident.
6. All work shall be done in accordance with the Maine Department of Transportation's Best Management Practices for Erosion Control & Sediment Control, January, 2000.
7. The State will final stripe the project. The Contractor is responsible for transferring the existing striping pattern to the surface course.
8. T.O.M.s may be used as temporary striping.

STP-1128(500)X

BEG PROJ STA 3+73

END PROJ STA 130+23



LOCATION MAP



HOT MIX ASPHALT OVERLAY,
PLANT MIX RECYCLED ASPHALT PAVEMENT,
PAVED SHOULDERS,
DRAINAGE & SAFETY IMPROVEMENTS

TRAFFIC DATA
SR 150 S/O IR 374

Current (2004) AADT	2590
Future (2024) AADT	3630
DHV - % of AADT	9
Design Hour Volume	327
% Heavy Trucks (AADT)	22
% Heavy Trucks (DHV)	17
Directional Distribution (DHV)	55
18 kip Equivalent P 2.0	779
18 kip Equivalent P 2.5	742
Design Speed (mph)	45



CORNVILLE
SOMERSET COUNTY

ROUTE 150

STP-1128(500)X

PROJECT LENGTH : 2.40 mi

LEVEL 2

Cornville

WOOD RD
STA 33+55

VERE SCHOOL RD
STA 33+55

END PROJ
STA 130+23

150

BEG PROJ
STA 3+73

74

STP-1128(500)X PN 11285.00

PIN 11285.00



PROJECT INFORMATION	PROGRAM	PROJECT MANAGER	DESIGNER	CONSULTANT	PROJECT RESIDENT	CONTRACTOR	PROJECT COMPLETION DATE
	REGIMIN	↓ DEVI	↓ PIRECH, EIT 5262				

CORNVILLE	TITLE SHEET
ROUTE 150	

SHEET NUMBER


1

1 of 1

STATE OF MAINE DEPARTMENT OF TRANSPORTATION		APPROVED	DATE
 COMMISSIONER		 CHIEF ENGINEER	4/15/94 04/03/94

HOT MIX ASPHALT OVERLAY
PLANT MIX RECYCLED ASPHALT PAVEMENT
VARIABLE DEPTH ASC GRAVEL

NORMAL



NOTE:

ITEM 211.30 DITCH EXC. SHALL INCLUDE RESTORING THE DITCH TO ORIGINAL TEMPLATE OR AS DIRECTED AND SHALL INCLUDE REGRADING OF THE BACKSLOPE AND INSLOPE TO THE SPECIFIED TOLERANCES.


NOTE:

SHOULDER PAVEMENT SHALL
TAPER FROM 2³/₄" DEPTH AT
EDGE OF TRAVEL LANE TO 2¹/₄"
DEPTH AT OUTSIDE EDGE OF
SHOULDER


NOT TO SCALE

CORNVILLE ROUTE 150 TYPICAL SECTIONS		SHEET NUMBER <div>1</div>		OF 2
FIELD CHANGES REVISIONS 4 REVISIONS 3 REVISIONS 2 REVISIONS 1 REVISIONS 0 DESIGN - DETAILING DESIGN - FIELD CHECKED - REVIEWED DESIGN - DETAILING		DATE BY JOHN DEYAN		STATE OF MAINE DEPARTMENT OF TRANSPORTATION STP-1128(600)X PIN 11286.00 HIGHWAY PLANS
SIGNATURE		DATE		P.E. NUMBER
DATE		BY		FIELD CHANGES

Cross Pipe Low Shallow Pipe Application



Cross Pipe High Shallow Pipe Application



Station 67+08


Not to Scale

Cornville
STP-1128(500)X
Route 150 Level 2

STATIONING

545/S	4+12	
	4+18	NET & T 545/107 1/2
	5+68	CMP 545-1/2 /108
	9+03	CMP 546/109
	10+72	CMP 546-1/2 /109-1/2
	15+39	548/111
	18+36	549/112
550/S/113S	21+14	
	21+30	550/113
551/S/114S	23+40	
	23+62	551/114
552/S/115S	25+82	
	25+89	552/1/115
553/S/116S	28+20	
	28+26	553/116
	33+33	555/118
556/15>/1/164	34+60	
	36+44	NET & T 1/165
	39+09	166
	41+59	167
	46+21	169
	50+33	NET & T 1/175
	53+25	NET & T 176
	57+07	NET & T 178
	61+25	NET & T 184/79
	63+96	NET & T 1/18S/78
	66+88	NET & T 186/77
	72+74	NET & T 188/75
	75+55	NET & T 1/189/74
CMP 73/196	77+38	
CMP 71/198	82+13	
CMP 69/1/200	87+10	
CMP 67/202	92+06	
CMP 65/204	96+91	
CMP 63/206	101+81	
CMP 61/208	106+80	
CMP 60/209	109+27	
CMP 58/211	113+11	
CMP 56/213	117+95	
CMP 55/214	120+47	
CMP 53/216	125+42	
CMP 51/1/218	130+25	

CORNVILLE
STP-1128(500)X
Route 150, Level 2



LEFT		STATION	RIGHT	
-4.00	-2.00	3+73	-2.00	-4.00
-4.00	-2.44	4+00	-0.76	-4.00
-4.00	-2.88	4+25	0.48	-4.00
-4.00	-3.32	4+50	1.72	-3.00
-4.00	-3.76	4+75	2.96	-3.00
-4.20	-4.20	5+00	4.20	-2.00
		TO		
-4.20	-4.20	8+75	4.20	-2.00
-4.16	-4.16	9+00	4.16	-2.00
-4.12	-4.12	9+25	4.12	-2.00
-4.08	-4.08	9+50	4.08	-2.00
-4.04	-4.04	9+75	4.04	-2.00
-4.00	-4.00	10+00	4.00	-2.00
		TO		
-4.00	-4.00	12+00	4.00	-2.00
-4.00	-3.67	12+25	3.67	-2.00
-4.00	-3.33	12+50	3.33	-2.00
-4.00	-3.00	12+75	3.00	-3.00
-4.00	-2.67	13+00	2.67	-3.00
-4.00	-2.33	13+25	2.33	-3.00
-4.00	-2.00	13+50	2.00	-3.00
		TO		
-4.00	-2.00	15+00	2.00	-3.00
-4.00	-2.00	15+25	1.43	-4.00
-4.00	-2.00	15+50	0.86	-4.00
-4.00	-2.00	15+75	0.29	-4.00
-4.00	-2.00	16+00	-0.29	-4.00
-4.00	-2.00	16+25	-0.86	-4.00
-4.00	-2.00	16+50	-1.43	-4.00
-4.00	-2.00	16+75	-2.00	-4.00
		TO		
-4.00	-2.00	17+00	-2.00	-4.00
-4.00	-1.48	17+25	-2.08	-4.00
-4.00	-0.96	17+50	-2.16	-4.00
-4.00	-0.43	17+75	-2.23	-4.00
-4.00	0.09	18+00	-2.31	-4.00
-4.00	0.61	18+25	-2.39	-4.00
-3.00	1.13	18+50	-2.47	-4.00
-3.00	1.66	18+75	-2.54	-4.00
-3.00	2.18	19+00	-2.62	-4.00
-3.00	2.70	19+25	-2.70	-4.00
		TO		
-3.00	2.70	20+25	-2.70	-4.00
-3.00	3.10	20+50	-3.10	-4.00
-2.00	3.50	20+75	-3.50	-4.00
-2.00	3.90	21+00	-3.90	-4.00
-2.00	4.30	21+25	-4.30	-4.30
-2.00	4.70	21+50	-4.70	-4.70
		TO		
-2.00	4.70	28+75	-4.70	-4.70
-2.00	3.96	29+00	-4.40	-4.40

-3.00	3.21	29+25	-4.10	-4.10
-3.00	2.47	29+50	-3.80	-4.00
-3.00	1.72	29+75	-3.50	-4.00
-4.00	0.98	30+00	-3.20	-4.00
-4.00	0.23	30+25	-2.90	-4.00
-4.00	-0.51	30+50	-2.60	-4.00
-4.00	-1.26	30+75	-2.30	-4.00
-4.00	-2.00	31+00	-2.00	-4.00
		TO		
-4.00	-2.00	130+23	-2.00	-4.00

Superelevations were computer generated.
Superelevations will be rounded to the nearest half percent.

Construction Notes

Item 202.203 Pavement Butt Joints

STATION

3+73 ML
130+23 ML
33+57 Rt. Revere School Road
32+98 Lt. Wood Road
33+65 Lt. Wood Road
6 Paved Drives

Item 211.21 Inslope Rehabilitation

<u>LEFT</u>	<u>LENGTH</u>	<u>RIGHT</u>	<u>LENGTH</u>
14+30 - 14+89	59	22+05 - 22+21	16
16+46 - 22+23	577	25+97 - 32+18	621
24+92 - 25+20	28	33+13 - 43+15	1002
25+51 - 26+79	128	43+75 - 55+11	1136
27+04 - 27+38	34	71+73 - 71+92	19
33+11 - 33+41	30	114+23 - 118+40	417
45+10 - 54+85	975	126+39 - 126+84	45
58+85 - 62+73	388		
67+20 - 73+13	593		
73+41 - 74+50	109		
74+80 - 77+29	249		
77+53 - 83+93	640		
84+19 - 101+73	1754		
102+98 - 107+73	475		
107+97 - 116+43	846		
118+90 - 121+64	274		
121+84 - 123+58	174		
124+36 - 126+43	207		
127+00 - 129+51	251		
129+73 - 130+23	50		

Construction Notes

Item 211.30 Ditch Excavation

<u>LEFT</u>	<u>LENGTH</u>	<u>RIGHT</u>	<u>LENGTH</u>
3+73 - 4+15	42	3+73 - 5+25	152
4+36 - 5+54	118	5+53 - 10+45	492
5+77 - 10+56	479	10+50 - 20+41	991
14+89 - 16+46	157	20+70 - 22+05	135
22+23 - 24+92	269	22+21 - 25+97	376
27+38 - 32+83	545	32+18 - 33+13	95
33+79 - 42+89	910	43+15 - 43+75	60
43+19 - 45+10	191	55+11 - 59+08	397
54+85 - 58+85	400	60+50 - 68+61	811
62+73 - 67+20	447	68+92 - 71+73	281
67+08 Lt. Ditch Outlet	222	71+92 - 88+70	1678
72+64 Lt. Ditch Outlet	220	89+11 - 102+87	1376
76+22 Lt. Ditch Outlet	210	103+27 - 108+12	485
101+73 - 102+98	125	108+38 - 112+48	410
116+43 - 117+15	72	112+68 - 114+23	155
117+37 - 118+90	153	118+40 - 119+43	103
123+96 - 124+36	40	119+68 - 121+93	225
126+43 - 127+00	57	122+33 - 126+39	406
		126+84 - 128+40	156
		128+53 - 130+23	170

The removal of stumps in these areas will be incidental to item 211.30

Item 304.10 Aggregate Subbase Course-Gravel

<u>STATION - STATION</u>	<u>DESCRIPTION</u>	<u>COMMENTS</u>
4+45 - 33+79	Gravel	6" Depth
33+79 - 60+50	Gravel	9" Depth
60+50 - 61+80	Gravel	6" Depth
61+80 - 129+81	Gravel	4" Depth

Construction Notes

Item 310.23 3" Plant Mixed Recycled Asphalt Pavement

STATION - STATION
3+73-129+81 Full Width

AREA
42030 yd²

Existing pavement depths

Station	Offset (ft)	Pavement Depth (in)
11+73	9.0 Rt.	4.8
15+73	8.3 Rt.	6.0
23+73	9.2 Rt.	7.2
29+73	8.7 Rt.	2.4
37+73	8.7 Rt.	4.8
44+73	8.7 Rt.	3.6
49+49	6.8 Rt.	3.6
53+73	8.2 Rt.	4.8
59+73	9.0 Rt.	4.8
75+73	8.2 Rt.	6.0
83+73	9.3 Rt.	4.8
89+73	8.9 Rt.	4.8
95+73	9.0 Rt.	6.0
101+73	8.7' Rt.	6.0
111+73	8.3' Rt.	4.8
125+73	8.8' Rt.	6.0

Item 403.210 HMA 9.5 mm Surface

STATION - STATION
3+73-130+23 Mainline and Shoulders

NOTE:

Shoulder pavement shall taper from 1-1/4" depth at edge of travel lane to 1" depth at edge of shoulder.

Item 403.213 HMA 12.5mm Base

STATION - STATION
3+73-129+81 Mainline and shoulders

NOTE:

Shoulder pavement shall taper from 1-1/2" depth at edge of travel lane to 1-1/4" depth at edge of shoulder.

Construction Notes

Item 411.10 Untreated Aggregate Surface Course, Truck Measure

This item to be used to back up paved lips, entrances and turnouts as directed by MDOT personnel. Depths over 4" will be backed up with Item 304.103

Item 603.16 15" Culvert Pipe Option I

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
58+40 Rt.	40'	Replace Existing
117+26 Lt.	36'	New
128+46 Rt.	36'	New

Item 603.17 18" Culvert Pipe Option I

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
35+30 Lt.	36'	New
42+58 Lt.	36'	New
116+42 Rt.	36'	Replace Existing

Item 603.179 18" Culvert Pipe Option III

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
23+62	56'	Replace Existing
42+89*	56'	Replace Existing/ See typical
67+08*	56'	Replace Existing/ See typical
72+64*	56'	Replace Existing/ See typical
103+68	60'	Replace Existing
106+90	60'	Replace Existing
113+11	60'	Replace Existing

*** See typical** All work associated with this culvert pipe including but not limited to extra excavation, extra aggregate sub-base course gravel and Styrofoam insulation shall be considered incidental to the 603 items.

***Pipes are part of University of Maine/MDOT research project - see General Notes for details**

Construction Notes

Item 603.199 24" Culvert Pipe Option III

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
76+22	60'	Replace Existing

Item 603.219 36" Culvert Pipe Option III

<u>STATION</u>	<u>LENGTH</u>	<u>NOTES</u>
56+11(twin pipes)	80' each	Stream realignment

These pipes are to be installed on a skew to replace pipes at station 57+23. This is instream work.

Item 609.31 Curb Type 3

<u>LEFT</u>	<u>LENGTH (ft)</u>
10+86-11+86	100
12+17-13+07	90

Item 610.08 Plain Rip Rap

This Item to be used as directed by the MDOT personnel.

Item 610.18 Stone Ditch Protection

<u>LEFT</u>	<u>RIGHT</u>
<u>STATION - STATION</u>	<u>STATION - STATION</u>
5+23 – 5+54	5+53 – 10+45
5+77 – 7+23	10+50 – 14+73

Item 613.319 Erosion Control Blanket

This item to be used in all ditches. Some ditches may require a double width. MDOT personnel may also require this item placed on some slopes, pipe ends and driveway radii.

Construction Notes

Item 619.1201 Mulch - Plan Quantity

This item to be used in all disturbed areas. Areas will be maintained on a daily basis until an acceptable growth of grass is obtained.

Item 620.54 Stabilization Geotextile

This Item to be used under Gravel areas 33+85-60+50 Right and 33+79-60+50 Left as directed by the MDOT personnel.

Item 620.58 Erosion Control Geotextile

This Item to be used under Rip Rap and Stone Ditch Protection as directed by the MDOT personnel.

Item 629.05 and 631's Rental Items

Rental Items to be used for misc. ditching and other miscellaneous tasks. Sceded excavation shall be used to build a berm and fix lawn area on the left just prior to the beginning of the project as directed by the Resident.

GENERAL NOTES

STP-1128(500)X
Cornville Route 150

- 1) All joints between existing and proposed hot bituminous pavement shall be butted. Payment shall be made under Item 202.203 Pavement Butt Joint.
- 2) Construct Butt Joints at all paved drives and entrances, as directed by the Resident.
- 3) The Contractor shall place suitable existing material or other material acceptable to the Resident, on all pavement edges to allow no greater than a 1 ¼ inch drop-off and flatten all non guardrail inslopes to a minimum slope of 3:1. Payment will be incidental to the contract and/or appropriate inslope and ditch items.
- 4) All waste material not used on the project shall be disposed of off the project in waste areas approved by the MDOT personnel. All work necessary to dispose of waste material (including grading, seeding, and mulching) will be considered incidental to the contract items.
- 5) Any damage to the slopes caused by the Contractor's equipment, personnel, or operation shall be repaired to the satisfaction of the MDOT personnel. All work, equipment and materials required to make repairs shall be at the Contractor's expense.
- 6) Any necessary cleaning of existing pavement prior to paving shall be incidental to the related paving items.
- 7) When super elevation exceeds the slope of the low side shoulder, the shoulder will have same slope as traveled way.
- 8) **The following shall be incidental to the 603 item(s):**
Any cutting of existing culverts and or connectors necessary to install new culvert replacements or extensions
All pipe excavation including any cutting and removal of pavement
All ditching at pipe ends
Furnishing, placing, grading, and compacting of any new gravel and/or fill material including Granular Borrow used under pipes and for temporary detours to maintain traffic during pipe installation (excavation is also incidental)
Granular Borrow under the pipe shall meet the requirements for Underwater Backfill.
All work necessary to connect to existing pipes
Flow lines may be changed by 18 inches
Any necessary clearing of brush, small trees, and headwalls at culvert ends
- 9) No existing drainage shall be abandoned, removed or plugged without prior approval of the MDOT personnel.
- 10) Where existing excavation in drainage trenches is deemed unusable, a suitable similar or impervious material, acceptable to the Resident, will be obtained for use as backfill in drainage trenches to subgrade. Payment will be incidental to 603 items.

GENERAL NOTES

**STP-1128(500)X
Cornville Route 150**

- 11) Existing culverts and catch basins will be cleaned as directed by the MDOT personnel under the appropriate Pay Items.
- 12) As directed by the MDOT personnel, all existing Underdrain Outlets shall be located, cleaned out, and ditched as required or replaced as necessary. Payment will be made under appropriate hourly contract items.
- 13) All connections for Underdrain to roadway culverts will be incidental to U.D. pipe items.
- 14) Backing up bituminous curb is incidental to the curb items. In areas where new bituminous curb is designated to replace existing, the removal of the old bituminous curb shall be incidental to the new curb.
- 15) Trim all tree branches to 20 ft above pavement. Payment shall be made under the appropriate labor and equipment rental items.
- 16) All work shall be done in accordance with the Maine Department of Transportation's Best Management Practices for Erosion Control & Sediment Control, January, 2000.
- 17) MDOT will final stripe the project.
- 18) Tacking of joints shall be in accordance with 2002 specifications.
- 19) All ditches that are excavated/re-graded must receive erosion control immediately.
- 20) Project stationing will be laid out first time only by MDOT personnel on existing pavement and will then be maintained by the Contractor immediately after loss of said stationing due to paving, milling, or reclaiming operations.
- 21) Dust control will not be paid for directly, but will be considered incidental to the Erosion Control Plan (SEWPCP) and Traffic Control Plan.
- 22) All pavement milling areas will have all pavement removed with minimal contamination. Any remaining material not broken up will require reclaiming or some other means of removal. Shoulder material shall be graded smooth (to be graded to match existing gravel grade) to drain prior to shutdown on the day the millings are removed. This grading will be considered incidental to the contract. The removal of and disposing of this material shall be considered incidental to Items 211.21, 211.30 and this contract.
- 23) The existing gravel structure will be graded to proposed x-slopes and compacted immediately following removal of pavement and shall be considered incidental to item 310.23. See Special Provision 310. A minimum of 4" ASC gravel will be placed, graded and compacted to the proper cross slope and will be paid under Item 304.10.

GENERAL NOTES

STP-1128(500)X
Cornville Route 150

- 24) All roadway drainage installation trenches will require a minimum of 3 inches of 12.5mm base pavement on the same day or as directed by the Resident. Payment will be incidental to the contract as per Standard Specification 105.4.1.
- 25) The contractor shall back up the 3" drop off from the edge of shoulder the same day as the PM RAP is placed. This work shall be considered incidental to the contract.
- 26) The contractor is responsible for the careful **side staking** of existing centerline as per standard specification 105.6.2. Side stakes shall be placed safely outside of the construction limits and the existing centerline grades for the existing gravel (after re-grading and compacting) shall be transferred to these stakes and the appropriate additional gravel added. All layout, stakes, and grades will be checked and must be acceptable to the Resident.
- 27) The contractor will be responsible for maintaining all existing mailboxes to ensure that the mail will be deliverable. No separate payment will be made for this work; it shall be considered incidental to the contract.
- 28) Dredge Material (See MDOT Standard Specifications § 101.2) is regulated as a Special Waste. Fifty cubic yards or less of Dredge Material **Beneficially Used in the area adjacent to and draining into the dredged water body** is exempt from Beneficial Use Permits. The Contractor shall ensure that Dredge Material is placed into the fill areas specified by MDOT. No more than the fifty cubic yards (38 cubic meters) of Dredge Material may be excavated without authorization from the Resident. Any Dredge Material not Beneficially Used (excess Dredge Material) shall be disposed of at a landfill licensed by the Maine Department of Environmental Protection to accept Special Waste. The Contractor shall be responsible for making all necessary arrangements for dewatering and proper disposal of the Dredge Material, including any additional laboratory testing, in accordance with the landfill's license. The Contractor shall provide documentation to the Resident that any such Dredge Material was disposed of as specified.
- 29) This project has been selected for a shallow cross pipe research project conducted by the University of Maine and MDOT. This will require cooperation and coordination between Contractor, State, and University personnel. The test requires installation of rigid Styrofoam insulation on 2 of 3 shallow cross pipes at Station 42+89, 67+08 or 23+62 and 72+64. Rigid Styrofoam insulation (1" thick boards) is to be placed 24 sq. ft per lineal foot of culvert. The cost for supplying and installing insulation, including any modifications, will be considered incidental to placement of pipes. MDOT will supply a drill rig and install 4" PVC sleeves prior to pipe installation in the trench area and these must be protected and preserved. University of Maine personnel will install test meters after pipe installation in the sleeves and then the sleeves will have to be pulled. University personnel will also monitor the test areas. A discussion of this research project and all requirements will be included as part of the Pre-Construction Meeting.

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION




DEXTER
PENOBSCOT

ROUTE 7



STP-A134(000)X

PROJECT LENGTH : 1.24 mi.




BEG PROJ STA 1+00

END PROJ STA 66+70




3/4" HOT MIX ASPHALT OVERLAY




TRAFFIC DATA		
SR 7 S/O SR 94		
Current (2004) AADT	6070	
Future (2024) AADT	8500	
DHV - % of AADT	11	
Design Hour Volume	935	
% Heavy Trucks (AADT)	10	
% Heavy Trucks (DHV)	8	
Directional Distribution (DHV)	55	
18 kip Equivalent P 2.0	432	
18 kip Equivalent P 2.5	412	
Design Speed (mph)	50	

SHEET NUMBER	1	DEXTER ROUTE 7 TITLE SHEET	PROJECT INFORMATION PROJECT: M. LENO PROJECT: MANAGER: J. DEVIN DESIGNER: REGIONAL PROJECT: COMPLETE DATE:	DATE: 3/25/04 P.E. NUMBER: 7994 SIGNATURE: [Signature] REGIONAL PROJECT: COMPLETE DATE:	STATE OF MAINE PROFESSIONAL ENGINEER JOHN REGIONAL PROJECT: COMPLETE DATE:	CHIEF ENGINEER: [Signature] COMMISSIONER: [Signature] APPROVED: [Signature] DEPARTMENT OF TRANSPORTATION STATE OF MAINE DATE: 3/25/04 3/25/04

HOT MIX ASPHALT OVERLAY
CURB AND GUARDRAIL SECTIONS




NOTE:
DEPTH OF SHIM SHALL BE
MAXIMUM OF 3/4\" COMPACTED
AND SHALL BE PLACED ON ML
ONLY EXCEPTING AREAS WHERE
EXTENSIVE CRACKING SHOWS
ON PAVED SHOULDER.



NOT TO SCALE

HOT MIX ASPHALT OVERLAY



NOTE:

DEPTH OF SHIM SHALL BE
MAXIMUM OF 3/4" COMPACTED
AND SHALL BE PLACED ON ML
ONLY EXCEPTING AREAS WHERE
EXTENSIVE CRACKING SHOWS
ON PAVED SHOULDER.


NOTE:

SHOULDER CROSS SLOPE SHALL BE -2% ON THE HIGH SIDE OF THE SUPERELEVATION WHEN THE ALGEBRAIC DIFFERENCE IN THE RATE OF CROSS SLOPE EXCEEDS 9%

NOT TO SCALE

PROJECT STATIONING

STATION	
START	1+00 Dexter Town Line Sign
	1+81 NET & T 501
	4+99 25/29
	8+22 24/28
	11+44 23/27
	13+60 22
NET & T 25	14+95
	16+46 21D
NET & T 285/20/24	17+49
	19+36 50/20D
NET & T 18/22	22+61
	25+46 NET & T 17/21
	26+97 16
NET & T 14S/17.1	29+11
	29+79 NET & T 14/17
	31+84 NET & T 13/16
	35+25 VZ 11
	40+07 8
	49+66 NET & T 4/4
	55+30 NET & T 2
	57+43 NET & T 50/1/1
	64+21 CMP 44/39
END PROJECT	66+70



CONSTRUCTION NOTES

ITEM 403.209 HMA HAND PLACED

This item to be used to resurface drives.

ITEM 403.210 9.5MM HMA SURFACE

This item shall be placed at $\frac{3}{4}$ " at all pavement surfaces. See also Special Provision 403 on $\frac{3}{4}$ " overlays.

ITEM 403.212 4.75MM HMA SHIM

This item shall be used at variable depths prior to placing surface HMA.

ITEM 409.15 TACK APPLIED

Tack will be applied prior to placing shim and surface. Both applications will be paid for.

GENERAL NOTES

1. All joints between existing and proposed hot bituminous pavement shall be butted. Payment shall be made under Item 202.203 Pavement Butt Joint.
2. Construct Butt Joints at all paved drives and entrances.
3. Any damage to the slopes caused by the Contractor's equipment, personnel, or operation shall be repaired to the satisfaction of the Resident. All work, equipment and materials required to make repairs shall be at the Contractor's expense.
4. Any necessary cleaning of existing pavement prior to paving shall be incidental to the related paving items.
5. All existing paved shoulders and widenings to be resurfaced as directed by the Resident.
6. Shoulder shim shall taper to 0 in at face of existing curb and guardrail.
7. Stations referenced are approximate.
8. Grind transition tapers at Catch Basins under Item No. 202.203, Pavement Butt Joints, as directed by the Resident.
9. All work shall be done in accordance with the Maine Department Transportation's Best Management Practices for Erosion Control & Sediment Control, January, 2000.
10. The State will final stripe the project. The Contractor is responsible for transferring the existing striping pattern to the surface course.
12. T.O.M.s may be used as temporary striping.

General Decision Number ME030009 06/13/2003 ME9

Superseded General Decision No. ME020009

State: Maine

Construction Type:
HIGHWAY

County(ies):

AROOSTOOK	KNOX	SAGADAHOC
FRANKLIN	LINCOLN	SOMERSET
HANCOCK	OXFORD	WALDO
KENNEBEC	PISCATAQUIS	YORK

HIGHWAY CONSTRUCTION PROJECTS excluding major bridging (for example: bascule, suspension and spandrel arch bridges; those bridging waters presently navigating or to be navigatable; and those involving marine construction in any degree); tunnels, building structures in rest area projects and railroad construction.

Modification Number	Publication Date
0	06/13/2003

COUNTY(ies):

AROOSTOOK	KNOX	SAGADAHOC
FRANKLIN	LINCOLN	SOMERSET
HANCOCK	OXFORD	WALDO
KENNEBEC	PISCATAQUIS	YORK

ENGI0004V 04/01/2003

	Rates	Fringes
POWER EQUIPMENT OPERATORS:		
Pavers	16.51	6.00
Rollers	16.51	6.00

SUME4024A 10/24/2000

	Rates	Fringes
CARPENTERS	11.60	1.51
IRONWORKERS		
Structural	12.03	1.58
LABORERS		
Drillers	10.00	2.50
Flaggers	6.00	
Guardrail Installers	7.92	
Landscape	7.87	.16
Line Stripper	8.69	.23
Pipelayers	9.21	2.31
Rakers	9.00	1.51
Sign Erectors	10.00	
Unskilled	8.66	1.38
Wheelman	8.50	.43
POWER EQUIPMENT OPERATORS		
Backhoes	11.87	2.05
Bulldozers	12.33	2.88

Cranes	14.06	1.75
Excavators	12.38	2.48
Graders	13.06	3.73
Loaders	11.41	2.87
Mechanics	13.18	2.57

TRUCK DRIVERS

Dump	9.35	3.10
Tri axle	8.70	1.18
Two axle	8.56	2.19

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29 CFR 5.5(a)(1)(ii)).

In the listing above, the "SU" designation means that rates listed under that identifier do not reflect collectively bargained wage and fringe benefit rates. Other designations indicate unions whose rates have been determined to be prevailing.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations
Wage and Hour Division
U. S. Department of Labor
200 Constitution Avenue, N. W.
Washington, D. C. 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator

(See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N. W.
Washington, D. C. 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U. S. Department of Labor
200 Constitution Avenue, N. W.
Washington, D. C. 20210

4.) All decisions by the Administrative Review Board are final.
END OF GENERAL DECISION

STP-1121(400)X

END SECTION 2 - STA 70+50

BEGIN SECTION 3 - STA 70+50

END SECTION 3 - STA 145+32

BEGIN SECTION 4 - STA 27+50

END SECTION 4 - STA 62+25



BEGIN SECTION 1 - STA 11+05

END SECTION 1 - STA 49+43

BEGIN SECTION 2 - STA 49+43

LOCATION MAP



Scale in Miles

Project No. STP-1121(400)X
& PIN 12261.00

SPECIAL PROVISION
CONSTRUCTION AREA

A Construction Area located in the **Towns of Athens and Cambridge** has been established by the Maine Department of Transportation in accordance with provisions of Title 29, Section 1703, Maine Revised Statutes Annotated.

The sections of highway under construction in Somerset County, project STP-1121(400)X & PIN 12261.00 are located on Route 150. Section one begins in Athens, 0.77 of a mile southwesterly of Rte 43/151 and extends northeasterly 0.73 of a mile. Section two extends northeasterly from that point 0.40 of a mile. Section three extends northeasterly 1.42 miles from the end of section two. Section four begins in Cambridge 0.2 of a mile southerly of Rte 152 and extends northerly 0.66 of a mile. STP-1121(400)X being a C.H.I.P. project of section one and three; PIN 12261.00 being a Maintenance Surface Treatment of sections two and four.

The State Department of Transportation or the State's Engineer may issue permits for stated periods of time for moving construction equipment without loads, low-bed trailers with overloads, over-height, over-width or over-length equipment or materials over all State maintained sections described in the "Construction Area" above and in addition may issue permits for stated periods of time for moving overweight vehicles and loads over the section described in (a) above. The right to revoke such a permit at any time is reserved by the State Department of Transportation and the issuance of such permits shall be subject to any Special Provisions or Supplemental Specifications written for this project.

A Temporary Permit for each move may be issued by the State Department of Transportation or the State's Engineer for moving Contractor's construction equipment used on the project which exceeds the legal limits (shovels, bulldozers, etc.) to sources of construction material over highways maintained by the State reasonably within the area of the project.

The Municipal Officers for the **Town of Athens and Cambridge** agreed that a permit will be issued to the Contractor for the purpose of hauling loads in excess of the limits as specified in Title 29, Maine Revised Statutes Annotated, on the town ways as described in the "Construction Area" and that single move permits will be issued for moving Contractor's construction equipment used on the project which exceeds the legal limits (shovels, bulldozers, etc.) to sources of construction material over town ways reasonably within the area of the project.


In the event it is necessary to transport gravel, borrow, or other construction material in legally registered vehicles carrying legal loads over town ways, a Contractor's Bond of not more than Nine Thousand (\$9,000.00) per kilometer of traveled length may be required by the town, the exact amount of said bond to be determined prior to use of any town way.

The maximum speed limits for trucks on any town way will be forty (40) km per hour [25 mph], unless a higher legal limit is specifically agreed upon in writing by the Municipal Officers concerned.

STP-1128(500)X

BEG PROJ STA 3+73

END PROJ STA 130+23



LOCATION MAP



Scale in Miles

SPECIAL PROVISION
CONSTRUCTION AREA

A Construction Area located in the **Town of Cornville** has been established by the Maine Department of Transportation in accordance with provisions of Title 29, Section 1703, Maine Revised Statutes Annotated.

The section of highway under construction in Somerset County, project STP-1128(500)X is located on Route 150, beginning 0.56 miles southerly of Revere School Road and extending northerly 2.4 miles.

The State Department of Transportation or the State's Engineer may issue permits for stated periods of time for moving construction equipment without loads, low-bed trailers with overloads, over-height, over-width or over-length equipment or materials over all State maintained sections described in the "Construction Area" above and in addition may issue permits for stated periods of time for moving overweight vehicles and loads over the section described in (a) above. The right to revoke such a permit at any time is reserved by the State Department of Transportation and the issuance of such permits shall be subject to any Special Provisions or Supplemental Specifications written for this project.

A Temporary Permit for each move may be issued by the State Department of Transportation or the State's Engineer for moving Contractor's construction equipment used on the project which exceeds the legal limits (shovels, bulldozers, etc.) to sources of construction material over highways maintained by the State reasonably within the area of the project.

The Municipal Officers for the **Town of Cornville** agreed that a permit will be issued to the Contractor for the purpose of hauling loads in excess of the limits as specified in Title 29, Maine Revised Statutes Annotated, on the town ways as described in the "Construction Area" and that single move permits will be issued for moving Contractor's construction equipment used on the project which exceeds the legal limits (shovels, bulldozers, etc.) to sources of construction material over town ways reasonably within the area of the project.


In the event it is necessary to transport gravel, borrow, or other construction material in legally registered vehicles carrying legal loads over town ways, a Contractor's Bond of not more than Nine Thousand (\$9,000.00) per kilometer of traveled length may be required by the town, the exact amount of said bond to be determined prior to use of any town way.

The maximum speed limits for trucks on any town way will be forty (40) km per hour [25 mph], unless a higher legal limit is specifically agreed upon in writing by the Municipal Officers concerned.

STP-A134(000)X

BEG PROJ STA 1+00

END PROJ STA 66+70



LOCATION MAP



Scale in Miles

SPECIAL PROVISION
CONSTRUCTION AREA

A Construction Area located in the **Town of Dexter** has been established by the Maine Department of Transportation in accordance with provisions of Title 29, Section 1703, Maine Revised Statutes Annotated.

The section of highway under construction in Penobscot County, project STP-A134(000)X is located on Route 7, beginning at the Corinna/Dexter town line and extending northerly 1.25 miles.

The State Department of Transportation or the State's Engineer may issue permits for stated periods of time for moving construction equipment without loads, low-bed trailers with overloads, over-height, over-width or over-length equipment or materials over all State maintained sections described in the "Construction Area" above and in addition may issue permits for stated periods of time for moving overweight vehicles and loads over the section described in (a) above. The right to revoke such a permit at any time is reserved by the State Department of Transportation and the issuance of such permits shall be subject to any Special Provisions or Supplemental Specifications written for this project.

A Temporary Permit for each move may be issued by the State Department of Transportation or the State's Engineer for moving Contractor's construction equipment used on the project which exceeds the legal limits (shovels, bulldozers, etc.) to sources of construction material over highways maintained by the State reasonably within the area of the project.

The Municipal Officers for the **Town of Dexter** agreed that a permit will be issued to the Contractor for the purpose of hauling loads in excess of the limits as specified in Title 29, Maine Revised Statutes Annotated, on the town ways as described in the "Construction Area" and that single move permits will be issued for moving Contractor's construction equipment used on the project which exceeds the legal limits (shovels, bulldozers, etc.) to sources of construction material over town ways reasonably within the area of the project.

In the event it is necessary to transport gravel, borrow, or other construction material in legally registered vehicles carrying legal loads over town ways, a Contractor's Bond of not more than Nine Thousand (\$9,000.00) per kilometer of traveled length may be required by the town, the exact amount of said bond to be determined prior to use of any town way.

The maximum speed limits for trucks on any town way will be forty (40) km per hour [25 mph], unless a higher legal limit is specifically agreed upon in writing by the Municipal Officers concerned.

SPECIAL PROVISION
CONSTRUCTION AREA

Title 29A, M.R.S.A., Subsection 2383. Overlimit movement permits

1. Overlimit movement permits issued by State. The Secretary of State, acting under guidelines and advice of the Commissioner of Transportation, may grant permits to move non-divisible objects having a length, width, height or weight greater than specified in this Title over a way or bridge maintained by the Department of Transportation.
2. Permit Fee. The Secretary of State, with the advice of the Commissioner of Transportation, may set the fee for these permits, at not less than \$3, nor more than \$15, based on weight, height, length and width.
3. County and municipal permits. A permit may be granted, for a reasonable fee, by county commissioners or municipal officers for travel over a way or bridge maintained by that county or municipality.
4. Permits for weight. A vehicle granted a permit for excess weight must first be registered for the maximum gross vehicle weight allowed for that vehicle.
5. Special mobile equipment. The Secretary of State may grant a permit, for no more than one year, to move pneumatic-tire equipment under its own power, including Class A and Class B special mobile equipment, over ways and bridges maintained by the Department of Transportation. The fee for that permit is \$15 for each 30-day period.
6. Scope of permit. A permit is limited to the particular vehicle or object to be moved and particular ways and bridges.
7. Construction permits. A permit for a stated period of time may be issued for loads and equipment employed on public way construction projects, United States Government projects or construction of private ways, when within construction areas established by the Department of Transportation. The Permit:
 - A. Must be procured from the municipal officers for a construction area within that municipality;
 - B. May require the Contractor to be responsible for damage to ways used in the construction areas and may provide for:
 - (1) Withholding by the agency of the work of final payment under contract;
or
 - (2) The furnishing of a bond by the Contractor to guarantee suitable repair or payment of damages.
 - C. May be granted by the Department of Transportation or by the state engineer in charge of the construction contract; and
 - D. For construction areas, carries no fee and does not come within the scope of this section.
8. Gross vehicle weight permits. The following may grant permits to operate a vehicle having a gross vehicle weight exceeding the prescribed limit:

- A. The Secretary of State, with the consent of the Department of Transportation, for state and state aid highways and bridges within city or compact village limits;
 - B. Municipal officers, for all other ways and bridges within that city and compact village limits; and
 - C. The county commissioners, for county roads and bridges located in unorganized territory.
9. Pilot vehicles and state police escorts. Pilot vehicles required by a permit must be equipped with warning lights and signs as required by the Secretary of State with the advice of the Department of Transportation.

Warning lights may only be operated and lettering on the signs may only be visible on a pilot vehicle while it is escorting on a public way a vehicle with a permit.

The Secretary of State shall require a State Police escort for a single vehicle or a combination of vehicles of 125 feet or more in length or 16 feet or more in width. The Secretary of State, with the advice of the Commissioner of Transportation, may require vehicles of lesser dimensions to be escorted by the State Police.

The Bureau of State Police shall establish a fee for State Police escorts.

All fees collected must be used to defray the cost of services provided.

With the advice of the Commissioner of Transportation and the Chief of the State Police, the Secretary of State shall establish rules for the operation for the operation of pilot vehicles.

10. Taxes paid. A permit for a mobile home may not be granted unless the applicant provides reasonable assurance that all property taxes, sewage disposal charges and drain and sewer assessments applicable to the mobile home, including those for the current tax year, have been paid or that the mobile home is exempt from those taxes.

1993, c. 683, § S-2, eff. January 1, 1995.

Historical and Statutory Notes

Derivation:

R.S. 1954, c. 22 § 98
Laws 1955, c. 389
Laws 1967, c. 3.
Laws 1971, c. 593, § 22.
Laws 1973, c. 213.
Laws 1975, c. 130, §
Laws 1975, c. 319, § 2

Laws 1977, c. 73, § 5.
Laws 1981, c. 413.
Laws 1985, c. 225, § 1
Laws 1987, c. 52.
Laws 1987, 781, § 3.
Laws 1989, c. 866, § B-13.
Laws 1991, c. 388, § 8.
Laws 1993, c. 683, § A-1.
Former 29 M.R.S.A. § 2382.

Cross Reference

Collection by Secretary of State, See 29-A
M.R.S.A. § 154.

SPECIAL PROVISION
(Consolidated Special Provisions)

SPECIAL PROVISION SECTION 101
CONTRACT INTERPRETATION

101.2 Definitions - Closeout Documentation

Replace the sentence “A letter stating the amount.... DBE goals.” with “DBE Goal Attainment Verification Form”

SPECIAL PROVISION SECTION 102
DELIVERY OF BIDS
(Location and Time)

102.7.1 Location and Time Add the following sentence “As a minimum, the Bidder will submit a Bid Package consisting of the Notice to Contractors, the completed Acknowledgement of Bid Amendments & Submission of Bid Bond Validation Number form, the completed Schedule of Items, 2 copies of the completed Agreement, Offer, & Award form, a Bid Bond or Bid Guarantee, and any other Certifications or Bid Requirements listed in the Bid Book.”

SPECIAL PROVISION SECTION 103
AWARD AND CONTRACTING

103.3.1 Notice and Information Gathering Change the first paragraph to read as follows:
“After Bid Opening and as a condition for Award of a Contract, the Department may require an Apparent Successful Bidder to demonstrate to the Department’s satisfaction that the Bidder is responsible and qualified to perform the Work.”

SPECIAL PROVISION SECTION 104
GENERAL RIGHTS AND RESPONSIBILITIES

Delete the entire Section 104.5.9 and replace with the following:

104.5.9 Landscape Subcontractors The Contractor shall retain only Landscape Subcontractors that are certified by the Department’s Environmental Office Landscape Unit.

SPECIAL PROVISION SECTION 105 GENERAL SCOPE OF WORK

Delete the entire Section 105.6 and replace with the following:

105.6.1 Department Provided Services The Department will provide the Contractor with the description and coordinates of vertical and horizontal control points, set by the Department, within the Project Limits, for full construction Projects and other Projects where survey control is necessary. For Projects of 1,500 feet in length, or less: The Department will provide three points. For Projects between 1,500 and 5,000 feet in length: The Department will provide one set of two points at each end of the Project. For Projects in excess of 5,000 feet in length, the Department will provide one set of two points at each end of the Project, plus one additional set of two points for each mile of Project length. For non-full construction Projects and other Projects where survey control is not necessary, the Department will not set any control points and, therefore, will not provide description and coordinates of any control points. Upon request of the Contractor, the Department will provide the Department's survey data management software and Survey Manual to the Contractor, or its survey Subcontractor, for the exclusive use on the Department's Projects.

105.6.2 Contractor Provided Services Utilizing the survey information and points provided by the Department, described in Subsection 105.6.1, Department Provided Services, the Contractor shall provide all additional survey layout necessary to complete the Work. This may include, but not be limited to, reestablishing all points provided by the Department, establishing additional control points, running axis lines, providing layout and maintenance of all other lines, grades, or points, and survey quality control to ensure conformance with the Contract. The Contractor is also responsible for providing construction centerline, or close reference points, for all Utility Facilities relocations and adjustments as necessary to complete the Work. When the Work is to connect with existing Structures, the Contractor shall verify all dimensions before proceeding with the Work. The Contractor shall employ or retain competent engineering and/or surveying personnel to fulfill these responsibilities.

The Contractor must notify the Department of any errors or inconsistencies regarding the data and layout provided by the Department as provided by Section 104.3.3 - Duty to Notify Department If Ambiguities Discovered.

105.6.2.1 Survey Quality Control The Contractor is responsible for all construction survey quality control. Construction survey quality control is generally defined as, first, performing initial field survey layout of the Work and, second, performing an independent check of the initial layout using independent survey data to assure the accuracy of the initial layout; additional iterations of checks may be required if significant discrepancies are discovered in this process. Construction survey layout quality control also requires written documentation of the layout

process such that the process can be followed and repeated, if necessary, by an independent survey crew.

105.6.3 Survey Quality Assurance It is the Department's prerogative to perform construction survey quality assurance. Construction survey quality assurance may, or may not, be performed by the Department. Construction survey quality assurance is generally defined as an independent check of the construction survey quality control. The construction survey quality assurance process may involve physically checking the Contractor's construction survey layout using independent survey data, or may simply involve reviewing the construction survey quality control written documentation. If the Department elects to physically check the Contractor's survey layout, the Contractor's designated surveyor may be required to be present. The Department will provide a minimum notice of 48 hours to the Contractor, whenever possible, if the Contractor's designated surveyor's presence is required. Any errors discovered through the quality assurance process shall be corrected by the Contractor, at no additional cost to the Department.

105.6.4 Boundary Markers The Contractor shall preserve and protect from damage all monuments or other points that mark the boundaries of the Right-of-Way or abutting parcels that are outside the area that must be disturbed to perform the Work. The Contractor indemnifies and holds harmless the Department from all claims to reestablish the former location of all such monuments or points including claims arising from 14 MRSA § 7554-A. For a related provision, see Section 104.3.11 - Responsibility for Property of Others.

SPECIAL PROVISION SECTION 106 QUALITY

106.6 Acceptance Add the following to paragraph 1 of A: "This includes Sections 401 - Hot Mix Asphalt, 402 - Pavement Smoothness, and 502 - Structural Concrete - Method A - Air Content."

Add the following to the beginning of paragraph 3 of A: "For pay factors based on Quality Level Analysis, and"

SPECIAL PROVISION SECTION 107 TIME

107.3.1 General Add the following: "If a Holiday occurs on a Sunday, the following Monday shall be considered a Holiday. Sunday or Holiday work must be approved by the Department, except that the Contractor may work on Martin Luther King Day, President's Day, Patriot's Day, the Friday after Thanksgiving, and Columbus Day without the Department's approval."

SPECIAL PROVISION SECTION 108
PAYMENT

108.4 Payment for Materials Obtained and Stored First paragraph, second sentence, delete the words "...Delivered on or near the Work site at acceptable storage places."

SPECIAL PROVISION SECTION 109
CHANGES

109.1.1 Changes Permitted Add the following to the end of the paragraph: "There will be no adjustment to Contract Time due to an increase or decrease in quantities, compared to those estimated, except as addressed through Contract Modification(s)."

109.1.2 Substantial Changes to Major Items Add the following to the end of the paragraph: "Contract Time adjustments may be made for substantial changes to Major Items when the change affects the Critical Path, as determined by the Department"

109.4.4 Investigation / Adjustment In the third sentence, delete the words "subsections (A) - (E)"

109.7.2 Basis of Payment Replace with the following: "Equitable Adjustments will be established by mutual Agreement for compensable items listed in Section 109.7.3- Compensable Items, based upon Unit or Lump Sum Prices. If Agreement cannot be reached, the Contractor shall accept payment on a Force Account basis as provided in Section 109.7.5 - Force Account Work, as full and complete compensation for all Work relating to the Equitable Adjustment."

109.7.3 Compensable Items Replace with the following: "The Contractor is entitled to compensation for the following items, with respect to agreed upon Unit or Lump Sum Prices:

1. Labor expenses for non-salaried Workers and salaried foremen.
2. Costs for Materials.
3. A markup on the totals of Items 1 and 2 of this subsection 109.7.3 for home office overhead and profit of the Contractor, its Subcontractors and suppliers, and any lower tier Subcontractors or suppliers, with no mark-ups on mark-ups.
4. Cost for Equipment, based on Blue Book Rates or leased rates, as set forth in Section 109.7.5(C), or the Contractor's Actual Costs.
5. Costs for extended job-site overhead.

6. Time.

7. Subcontractor quoted Work, as set forth below in Section 109.7.5 (F)."

109.7.5 Force Account Work

C. Equipment

Paragraph 2, delete sentence 1 which starts; "Equipment leased..."

Paragraph 6, change sentence 2 from "The Contractor may furnish..." to read "If requested by the Department, the Contractor will produce cost data to assist the Department in the establishment of such rental rate, including all records that are relevant to the Actual Costs including rental Receipts, acquisition costs, financing documents, lease Agreements, and maintenance and operational cost records."

Add the following paragraph; "Equipment leased by the Contractor for Force Account Work and actually used on the Project will be paid for at the actual invoice amount plus 10% markup for administrative costs."

Add the following section;

"F. Subcontractor Quoted Work When accomplishing Force Account Work that utilizes Subcontractor quoted Work, the Contractor will be allowed a maximum markup of 5% for profit and overhead."

SPECIAL PROVISION SECTION 110
INDEMNIFICATION, BONDING, AND INSURANCE

Delete the entire Section 110.2.3 and replace with the following:

110.2.3 Bonding for Landscape Establishment Period The Contractor shall provide a signed, valid, and enforceable Performance, Warranty, or Maintenance Bond complying with the Contract, to the Department at Final Acceptance.

The bond shall be in the full amount for all Pay Items for work pursuant to Sec 621, Landscape, payable to the "Treasurer - State of Maine," and on the Department's forms, on exact copies thereof, or on forms that do not contain any significant variations from the Department's forms as solely determined by the Department.

The Contractor shall pay all premiums and take all other actions necessary to keep said bond in effect for the duration of the Landscape Establishment Period described in Special Provision 621.0036 - Establishment Period. If the Surety becomes financially insolvent, ceases to be licensed or approved to do business in the State of Maine, or stops operating in the United States, the Contractor shall file new bonds complying with this Section within 10 Days of the date the Contractor is notified or becomes aware of such change.

All Bonds shall be procured from a company organized and operating in the United States, licensed or approved to do business in the State of Maine by the State of Maine Department of Business Regulation, Bureau of Insurance, and listed on the latest Federal Department of the Treasury listing for “Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies.”

By issuing a bond, the Surety agrees to be bound by all terms of the Contract, including those related to payment, time for performance, quality, warranties, and the Department’s self-help remedy provided in Section 112.1 - Default to the same extent as if all terms of the Contract are contained in the bond(s).

Regarding claims related to any obligations covered by the bond, the Surety shall provide, within 60 Days of Receipt of written notice thereof, full payment of the entire claim or written notice of all bases upon which it is denying or contesting payment. Failure of the Surety to provide such notice within the 60-day period constitutes the Surety’s waiver of any right to deny or contest payment and the Surety’s acknowledgment that the claim is valid and undisputed.

SPECIAL PROVISION SECTION 401 HOT MIX ASPHALT PAVEMENT

401.18 Quality Control Method A & B Make the following change to paragraph a. QCP Administrator; in the final sentence, change “...certified as a Plant Technician or Paving Inspector...” to “...certified as a Quality Assurance Technologist...”

401.201 Method A Under a. Lot Size, add the following; ‘Each lot will be divided into a minimum of four sublots for mix properties and five sublots for percent TMD.’

SPECIAL PROVISION SECTION 402 PAVEMENT SMOOTHNESS

Add the following: “Projects to have their pavement smoothness analyzed in accordance with this Specification will be so noted in Special Provision 403 - Bituminous Box.”

“402.02 Lot Size Lot size for smoothness will be 1000 lane-meters [3000 lane-feet]. A subplot will consist of 20 lane-meters [50 lane-feet]. Partial lots will be included in the previous lot if less than one-half the size of a normal lot. If greater than one-half the normal lot size, it will be tested as a separate lot.”

SPECIAL PROVISION SECTION 502 STRUCTURAL CONCRETE

502.0502 Quality Assurance Method A - Rejection by Resident Change the first sentence to read: “For an individual subplot with test results failing to meet the criteria in Table #1, or if the calculated pay factor for Air Content is less than 0.80.....”

502.0503 Quality Assurance Method B - Rejection by Resident Change the first sentence to read: “For material represented by a verification test with test results failing to meet the criteria in Table #1, the Department will.....”

502.0505 Resolution of Disputed Acceptance Test Results Combine the second and third sentence to read: “Circumstances may arise, however, where the Department may”

SPECIAL PROVISION SECTION 504 REINFORCING STEEL

504.18 Plates for Fabricated Members Change the second paragraph, first sentence from: “...ASTM A 898/A 898 M...” to “...ASTM A 898/A 898 M or ASTM A 435/A 435 M as applicable and...”

SPECIAL PROVISION SECTION 535 PRECAST, PRESTRESSED CONCRETE SUPERSTRUCTURE

535.02 Materials Change “Steel Strand for Concrete Reinforcement” to “Steel Strand.” Add the following to the beginning of the third paragraph; “Concrete shall be Class P conforming to the requirements in this section. 28 day compressive strength shall be as stated on the plans. Coarse aggregate....”

535.26 Lateral Post-Tensioning Replace the first paragraph; “A final tension...” with “Overstressing strands for setting losses cannot be accomplished for chuck to chuck lengths of 7.6 m [25 ft] and less. In such instances, refer to the Plans for all materials and methods. Otherwise, post-tensioning shall be in accordance with PCI standards and shall provide the anchorage force noted in the Plans. The applied jacking force shall be no less than 100% of the design jacking force.”

SPECIAL PROVISION SECTION 604
MANHOLES, INLETS, AND CATCH BASINS

604.02 Materials Add the following:

“Tops and Traps	712.07
Corrugated Metal Units	712.08
Catch Basin and Manhole Steps	712.09”

SPECIAL PROVISION SECTION 605
UNDERDRAINS

605.05 Underdrain Outlets Make the following change:

In the first paragraph, second sentence, delete the words “metal pipe”.

SPECIAL PROVISION SECTION 615
LOAM

615.02 Materials Make the following change:

<u>Organic Content</u>	<u>Percent by Volume</u>
Humus	“5% - 10%”, as determined by Ignition Test

SPECIAL PROVISION SECTION 618
SEEDING

618.01 Description Change the first sentence to read as follows: “This work shall consist of furnishing and applying seed” Also remove “,and cellulose fiber mulch” from 618.01(a).

618.03 Rates of Application In 618.03(a), remove the last sentence and replace with the following: “These rates shall apply to Seeding Method 2, 3, and Crown Vetch.”

In 618.03(c) “1.8 kg [4 lb]/unit.” to “1.95 kg [4 lb]/unit.”

618.09 Construction Method In 618.09(a) 1, sentence two, replace “100 mm [4 in]” with “25 mm [1 in] (Method 1 areas) and 50 mm [2 in] (Method 2 areas)”

618.15 Temporary Seeding Change the Pay Unit from Unit to Kg [lb].

SPECIAL PROVISION SECTION 620
GEOTEXTILES

620.03 Placement Section (c)

Title: Replace “Non-woven” in title with “Erosion Control”.

First Paragraph: Replace first word “Non-woven” with “Woven monofilament”.

Second Paragraph: Replace second word “Non-woven” with “Erosion Control”.

620.07 Shipment, Storage, Protection and Repair of Fabric Section (a)

Replace the third sentence with the following: “Damaged geotextiles, as identified by the Resident, shall be repaired immediately.”

620.09 Basis of Payment

Pay Item 620.58: Replace “Non-woven” with “Erosion Control”

Pay Item 620.59: Replace “Non-woven” with “Erosion Control”

SPECIAL PROVISION SECTION 621
LANDSCAPING

621.0036 Establishment Period In paragraph 4 and 5, change “time of Final Acceptance” to “end of the period of establishment”. In Paragraph 7, change “Final Acceptance date” to “end of the period of establishment” and change “date of Final Acceptance” to “end of the period of establishment”.

SPECIAL PROVISION SECTION 626
HIGHWAY SIGNING

626.034 Concrete Foundations Add to the following to the end of the second paragraph: “Pre-cast and cast-in-place foundations shall be warranted against leaning and corrosion for two years after the project is completed. If the lean is greater than 2 degrees from normal or the foundation is spalling within the first two years, the Contractor shall replace the foundation at no extra cost.”

SPECIAL PROVISION SECTION 637
DUST CONTROL

637.06 Basis of Payment Add the following after the second sentence of the third paragraph: “Failure by the Contractor to follow Standard Specification or Special Provision - Section 637 and/or the Contractor’s own Soil Erosion and Pollution Control Plan concerning Dust Control and/or the Contractor’s own Traffic Control Plan concerning Dust Control and/or visible evidence of excessive dust problems, as determined by the Resident, will result in a reduction in

payment, computed by reducing the Lump Sum Total by 5% per occurrence per day. The Department's Resident or any other representative of the Department reserves the right to suspend the work at any time and request a meeting to discuss violations and remedies. The Department shall not be held responsible for any delay in the work due to any suspension under this item. Additional penalties may also be assessed in accordance with Special Provision 652 - Work Zone Traffic Control and Standard Specification 656 - Temporary Soil Erosion and Water Pollution Control."

SPECIAL PROVISION SECTION 639 **ENGINEERING FACILITIES**

639.04 Field Offices Change the forth to last paragraph from: "The Contractor shall provide a fully functional desktop copier..." to "...desktop copier/scanner..."

SPECIAL PROVISION SECTION 652 **MAINTENANCE OF TRAFFIC**

652.3.5 Installation of Traffic Control Devices In the first paragraph, first sentence; change "Signs shall be erected..." to "Portable signs shall be erected..." In the third sentence; change "Signs must be erected so that the sign face..." to "Post-mounted signs must also be erected so that the sign face..."

652.8.2 Other Items Replace the last paragraph with the following: "There will be no payment made under any 652 pay items after the expiration of the adjusted total contract time."

SPECIAL PROVISION SECTION 656 **TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL**

656.5.1 If Pay Item 656.75 Provided Replace the second paragraph with the following: "Failure by the Contractor to follow Standard Specification or Special Provision - Section 656 and/or the Contractor's own Soil Erosion and Pollution Control Plan will result in a reduction in payment, computed by reducing the Lump Sum Total by 5% per occurrence per day. The Department's Resident or any other representative of the Department reserves the right to suspend the work at any time and request a meeting to discuss violations and remedies. The Department shall not be held responsible for any delay in the work due to any suspension under this item."

SPECIAL PROVISION SECTION 703
AGGREGATES

703.06 Aggregate for Base and Subbase Delete the first paragraph: “The material shall have...” and replace with “The material shall have a minimum degradation value of 15 as determined by Washington State DOT Test Method T113, Method of Test for Determination of Degradation Value (March 2002 version), except that the reported degradation value will be the result of testing a single specimen from that portion of a sample that passes the 12.5 mm [½ in] sieve and is retained on the 2.00 mm [No. 10] sieve, minus any reclaimed asphalt pavement used.”

703.07 Aggregates for HMA Pavements Delete the forth paragraph: “The composite blend shall have...” and replace with “The composite blend, minus any reclaimed asphalt pavement used, shall have a Micro-Deval value of 18.0 or less as determined by AASHTO TP 58. In the event the material exceeds the Micro Deval limit, a Washington Degradation test shall be performed. The material shall be acceptable if it has a value of 30 or more as determined by Washington State DOT Test Method T 113, Method of Test for Determination of Degradation Value (March 2002 version) except that the reported degradation value will be the result of testing a single composite specimen from that portion of the sample that passes the 12.5mm [1/2 inch] sieve and is retained on the 2.00mm [No 10] sieve, minus any reclaimed asphalt pavement used.”

703.22 Underdrain Backfill Material Change the first paragraph from “...for Underdrain Type B...” to “...for Underdrain Type B and C...”

SPECIAL PROVISION SECTION 709
REINFORCING STEEL AND WELDED STEEL WIRE FABIC

709.03 Steel Strand Change the second paragraph from “...shall be 12mm [½ inch] AASHTO M203M/M203 (ASTM A416/A416M)...” to “...shall be 15.24 mm [0.600 inch] diameter AASHTO M203 (ASTM A416)...”

SPECIAL PROVISION SECTION 712
MISCELLANEOUS HIGHWAY MATERIALS

Add the following:

“712.07 Tops, and Traps These metal units shall conform to the plan dimensions and to the following specification requirements for the designated materials.

Gray iron castings shall conform to the requirements of AASHTO M105, Class 30, unless otherwise designated.

Carbon steel castings shall conform to the requirements of AASHTO M103/M103M. Grade shall be 450-240 [65-35] unless otherwise designated.

Structural steel shall conform to the requirements of AASHTO M183/M183M or ASTM A283/A283M, Grade B or better. Galvanizing, where specified for these units, shall conform to the requirements of AASHTO M111.

712.08 Corrugated Metal Units The units shall conform to plan dimensions and the metal to AASHTO M36/M36M. Bituminous coating, when specified, shall conform to AASHTO M190 Type A.

712.09 Catch Basin and Manhole Steps Steps for catch basins and for manholes shall conform to ASTM C478M [ASTM C478], Section 13 for either of the following material:

- (a) Aluminum steps-ASTM B221M, [ASTM B211] Alloy 6061-T6 or 6005-T5.
- (b) Reinforced plastic steps Steel reinforcing bar with injection molded plastic coating copolymer polypropylene. Polypropylene shall conform to ASTM D 4101.

712.23 Flashing Lights Flashing Lights shall be power operated or battery operated as specified.

- (a) Power operated flashing lights shall consist of housing, adapters, lamps, sockets, reflectors, lens, hoods and other necessary equipment designed to give clearly visible signal indications within an angle of at least 45 degrees and from 3 to 90 m [10 to 300 ft] under all light and atmospheric conditions.

Two circuit flasher controllers with a two-circuit filter capable of providing alternate flashing operations at the rate of not less than 50 nor more than 60 flashes per minute shall be provided.

The lamps shall be 650 lumens, 120 volt traffic signal lamps with sockets constructed to properly focus and hold the lamp firmly in position.

The housing shall have a rotatable sun visor not less than 175 mm [7 in] in length designed to shield the lens.

Reflectors shall be of such design that light from a properly focused lamp will reflect the light rays parallel. Reflectors shall have a maximum diameter at the point of contact with the lens of approximately 200 mm [8 in].

The lens shall consist of a round one-piece convex amber material which, when mounted, shall have a visible diameter of approximately 200 mm [8 in]. They shall distribute light and not diffuse it. The distribution of the light shall be asymmetrical in a downward direction. The light distribution of the lens shall not be uniform, but shall consist of a small high intensity portion with narrow distribution for long distance throw and a larger low intensity portion with wide distribution for short distance throw. Lenses shall be marked to indicate the top and bottom of the lens.

(b) Battery operated flashing lights shall be self-illuminated by an electric lamp behind the lens. These lights shall also be externally illuminated by reflex-reflective elements built into the lens to enable it to be seen by reflex-reflection of the light from the headlights of oncoming traffic. The batteries must be entirely enclosed in a case. A locking device must secure the case. The light shall have a flash rate of not less than 50 nor more than 60 flashes per minute from minus 30 °C [minus 20 °F] to plus 65 °C [plus 150 °F]. The light shall have an on time of not less than 10 percent of the flash cycle. The light beam projected upon a surface perpendicular to the axis of the light beam shall produce a lighted rectangular projection whose minimum horizontal dimension shall be 5 degrees each side of the horizontal axis. The effective intensity shall not have an initial value greater than 15.0 candelas or drop below 4.0 candelas during the first 336 hours of continuous flashing. The illuminated lens shall appear to be uniformly bright over its entire illuminated surface when viewed from any point within an angle of 9 degrees each side of the vertical axis and 5 degrees each side of the horizontal axis. The lens shall not be less than 175 mm [7 in] in diameter including a reflex-reflector ring of 13 mm [½ in] minimum width around the periphery. The lens shall be yellow in color and have a minimum relative luminous transmittance of 0.440 with a luminance of 2854° Kelvin. The lens shall be one-piece construction. The lens material shall be plastic and meet the luminous transmission requirements of this specification. The case containing the batteries and circuitry shall be constructed of a material capable of withstanding abuse equal to or greater than 1.21 mm thick steel [No. 18 U.S. Standard Gage Steel]. The housing and the lens frame, if of metal shall be properly cleaned, degreased and pretreated to promote adhesion. It shall be given one or more coats of enamel which, when dry shall completely obscure the metal. The enamel coating shall be of such quality that when the coated case is struck a light blow with a sharp tool, the paint will not chip or crack and if scratched with a knife will not powder. The case shall be so constructed and closed as to exclude moisture that would affect the proper operation of light. The case shall have a weep hole to allow the escape of moisture from condensation. Photoelectric controls, if provided, shall keep the light operating whenever the ambient light falls below 215 lx [20

foot candles]. Each light shall be plainly marked as to the manufacturer's name and model number.

If required by the Resident, certification as to conformance to these specifications shall be furnished based on results of tests made by an independent testing laboratory. All lights are subject to random inspection and testing. All necessary random samples shall be provided to the Resident upon request without cost to the Department. All such samples shall be returned to the Contractor upon completion of the tests.

712.32 Copper Tubing Copper tubing and fittings shall conform to the requirements of ASTM B88M Type A [ASTM B88, Type K] or better.

712.33 Non-metallic Pipe, Flexible Non-metallic pipe and pipe fittings shall be acceptable flexible pipe manufactured from virgin polyethylene polymer suitable for transmitting liquids intended for human or animal consumption.

712.34 Non-metallic Pipe, Rigid Non-metallic pipe shall be Schedule 40 polyvinylchloride (PVC) that meets the requirement of ASTM D1785. Fittings shall be of the same material.

712.341 Metallic Pipe Metallic pipe shall be ANSI, Standard B36.10, Schedule 40 steel pipe conforming to the requirements of ASTM A53 Types E or S, Grade B. End plates shall be steel conforming to ASTM A36/A36M.

Both the sleeve and end plates shall be hot dip galvanized. Pipe sleeve splices shall be welded splices with full penetration weld before galvanizing.

712.35 Epoxy Resin Epoxy resin for grouting or sealing shall consist of a mineral filled thixotropic, flexible epoxy resin having a pot life of approximately one hour at 10°C [50°F]. The grout shall be an approved product suitable for cementing steel dowels into the preformed holes of curb inlets and adjacent curbing. The sealant shall be an approved product, light gray in color and suitable for coating the surface.

712.36 Bituminous Curb The asphalt cement for bituminous curb shall be of the grade required for the wearing course, or shall be Viscosity Grade AC-20 meeting the current requirements of Subsection 702.01 Asphalt Cement. The aggregate shall conform to the requirements of Subsection 703.07. The coarse aggregate portion retained on the 2.36 mm [No. 8] sieve may be either crushed rock or crushed gravel.

The mineral constituents of the bituminous mixture shall be sized and graded and combined in a composite blend that will produce a stable durable curbing with an acceptable texture. Bituminous material for curb shall meet the requirements of Section 403 - Hot Bituminous Pavement.

712.37 Precast Concrete Slab Portland cement concrete for precast slabs shall meet the requirements of Section 502 - Structural Concrete, Class A.

The slabs shall be precast to the dimension shown on the plans and cross section and in accordance with the Standard Detail plans for Concrete Sidewalk Slab. The surface shall be finished with a float finish in accordance with Subsection 502.14(c). Lift devices of sufficient strength to hold the slab while suspended from cables shall be cast into the top or back of the slab.

712.38 Stone Slab Stone slabs shall be of granite from an acceptable source, hard, durable, predominantly gray in color, free from seams which impair the structural integrity and be of smooth splitting character. Natural color variations characteristic of the deposit will be permitted. Exposed surfaces shall be free from drill holes or indications of drill holes. The granite slabs in any one section of backslope must be all the same finish.

The granite slabs shall be scabble dressed or sawed to an approximately true plane having no projections or depressions over 13 mm [½ in] under a 600 mm [2 ft] straightedge or over 25 mm [1 in] under a 1200 mm [4 ft] straightedge. The arris at the intersection of the top surface and exposed front face shall be pitched so that the arris line is uniform throughout the length of the installed slabs. The sides shall be square to the exposed face unless the slabs are to be set on a radius or other special condition which requires that the joints be cut to fit, but in any case shall be so finished that when the stones are placed side by side no space more than 20 mm [¾ in] shall show in the joint for the full exposed height.

Liftpin holes in all sides will be allowed except on the exposed face.

SPECIAL PROVISION SECTION 717 ROADSIDE IMPROVEMENT MATERIAL

717.05 Mulch Binder. Change the third sentence to read as follows:

“Paper fiber mulch may be used as a binder at the rate of 2.3 kg/unit [5 lb/unit].”

Town: Athens – Cambridge, Rt. 150
Project: STP-1121(400)X, PIN 11214.00
Date: April 26, 2004

**SPECIAL PROVISION
SECTIONS 104
UTILITIES**

MEETING

A pre-construction utility meeting, as defined in Article 104.4.6 of the Standard Specifications, is hereby called for.

GENERAL

These Special Provisions outline the arrangements that have been made by the Department for utility work to be undertaken in conjunction with this project. The following list identifies all known utilities having facilities presently located within the limits of this project or intending to install facilities during project construction.

Overview:

Utility/Railroad	Aerial	Underground
Central Maine Power	X	
Somerset Telephone Company (TDS)	X	X

Temporary utility adjustments are not anticipated at this time. If temporary relocation becomes necessary, sufficient time will need to be allowed prior to the construction for all required temporary relocation.

All utility crossings over highways will provide not less than 18 feet vertical clearance over existing ground in cut or over finished grade in fill, during construction of this project.

Any times and dates mentioned are estimates only and are dependent upon favorable weather, working conditions, and freedom from emergencies. The Contractor shall have no claim against the Department if they are exceeded.

Utility working days are Monday through Friday, conditions permitting. Times are estimated on the basis of a single crew for each utility.

In all cases the Utilities shall be advised well in advance (generally three weeks) before work, dependent upon other work to be done by the Contractor, in any particular area, is to be commenced by them.

AERIAL

Athens

Central Maine Power Company plans to relocate approximately 10-20 poles as part of this project. The existing pole list and estimated times for setting and transferring is noted below.

Special Provisions - Utilities
Athens – Cambridge, Rt. 150
STP-1121(400)X, PIN 11214.00
April 26, 2004

Utility/Railroad	Pole Set	Transfer wire or Install new wire	Remove Poles	Estimated Working Days
Central Maine Power	X	X	X	30
Somerset Telephone Co.		X		20
			Total:	50

Pole List:

Existing Pole #	Existing Station	Left/Right		Offset	Proposed Station	Left/Right		Offset	Comments
		LT	RT			LT	RT		
CMP 443/18	25+61	X		28'					OK
CMP 445/17	27+28	X		17'	TBD			21'min	Crossing Rd. Option
CMP 446/16	29+10	X		24'					OK
									HMM Downtown Area
	88+00								Large Fill Area Starts
CMP 21/10	88+72	X		20'				OK	Possible taller pole
CMP 23/11	90+48	X		22'				OK	Possible taller pole
CMP 24/12	91+70	X		22'				OK	Possible taller pole
CMP 25/13	93+00	X		22'				OK	Possible taller pole
CMP 26/14	94+29	X		23'				OK	Possible taller pole
CMP 27/15	95+74	X		25'				OK	Possible taller pole
CMP 28/16	97+34	X		27'				OK	Possible taller pole
CMP 29/17	98+48	X		25'				OK	Possible taller pole
CMP 30/18	99+54	X		25'				OK	Possible taller pole
CMP 34/19	101+14	X		26'				OK	Possible taller pole
CMP 33/20	103+06	X		20'				21'min	Possible taller pole
CMP 34/21	104+67	X		20'				21'min	Possible taller pole
CMP 35S/22	105+88		X	26'					OK
CMP 35/22	105+90	X		21'				OK	Close
CMP 37/24	108+50	X		22'					OK
CMP 38/25	110+14	X		21'				OK	Close
CMP 39/26	111+58	X		17'	TBD			21'min	Relocate
CMP 40/27	113+14	X		16'	TBD			21'min	Relocate
CMP 36/23	114+46		X	16'	TBD			21'min	Relocate
CMP 41/28	114+70	X		19'	TBD			21'min	Relocate
CMP 43/29	116+25	X		20'	TBD			21'min	Relocate
CMP 44/30	117+95	X		21'	TBD			21'min	Close

Special Provisions - Utilities
Athens – Cambridge, Rt. 150
STP-1121(400)X, PIN 11214.00
April 26, 2004

CMP 45/31	119+36	X		21'	TBD			21' min	Close
CMP46/32	120+64	X		23'					OK

*TBD = To be determined

Cambridge

There are no anticipated pole relocations on the Cambridge end of the project as the scope of work would not require utilities to relocate. Any above ground utility locations seen as an immediate safety concern will be require relocation to the proper offset.

SUBSURFACE

Somerset Telephone Company has buried cable in the shoulder the entire length of the project. Contractor shall notify the telephone companies at least three (3) days prior to any guardrail relocation or ditching operations to allow the utility to determine the cable locations in that area. The contact for **Somerset Telephone Company** is **Larry Cole at 634-7300**. After the initial layout, it is the Contractor's responsibility to maintain the location markings. Any damage to the buried cable caused by the Contractor during construction shall be repaired by the utility at the contractor's expense.

UTILITY SIGNING

Any utility working within the construction limits of this project shall ensure that the traveling public is adequately protected at all times. All work areas shall be signed, lighted, and traffic flaggers employed as determined by field conditions. All traffic controls shall be in accordance with the latest edition of the Manual on Uniform Traffic Control Devices for Streets and Highways, as issued by the Federal Highway Administration.

DIG SAFE

The Contractor shall be responsible for determining the presence of underground utility facilities prior to commencing any excavation work and shall notify utilities of proposed excavation in accordance with M.R.S.A. Title 23 §3360-A, Maine "Dig Safe" System.

MAINTAINING UTILITY LOCATION MARKINGS

The Contractor will be responsible for maintaining the buried utility location markings following the initial locating by the appropriate utility or their designated representative.

THE CONTRACTOR SHALL PLAN AND CONDUCT HIS WORK ACCORDINGLY.

The following utilities are known to be located on this project:

Central Maine Power Company	Dennis Chadbourne	828-2860
Somerset Telephone Company (TDS)	Larry Cole	634-7300

Town: **Cornville, Rt. 150**
Project: **STP-1128(500)X, PIN 11285.00**
Date: **April 26, 2004**

**SPECIAL PROVISIONS
SECTION 104
UTILITIES**

MEETING

A pre-construction utility meeting, as defined in Article 104.4.6 of the Standard Specifications, is **not** hereby called for.

GENERAL

These Special Provisions outline the arrangements which have been made by the Department for coordination of work and for utility adjustments, as defined in Section 104 of the Standard Specifications,

Overview:

Utility/Railroad	Aerial	Underground
Central Maine Power Company	X	
Verizon	X	X

All utility crossings over highways will provide not less than 18 feet vertical clearance over existing ground in cut or over finished grade in fill, during construction of this project.

Any times and dates mentioned are estimates only and are dependent upon favorable weather, working conditions, and freedom from emergencies. The Contractor shall have no claim against the Department if they are exceeded.

Manholes, valve boxes, service connections, and similar incidental utility plant are to be adjusted by the appropriate utility in cooperation with work being done by the Contractor.

Utility working days are Monday through Friday, conditions permitting. Times are estimated on the basis of a single crew for each utility.

Temporary utility adjustments are not anticipated at this time. If temporary relocation becomes necessary, sufficient time will need to be allowed prior to the construction for all required temporary relocation.

In all cases the Utilities shall be advised well in advance (generally three weeks) before work, dependent upon other work to be done by the Contractor, in any particular area, is to be commenced by them.

AERIAL

No Aerial Utility adjustments are anticipated as part of this project. All above ground utility locations (hydrants, poles, guys, etc.) will be reviewed for compliance with the Department's Above Ground Pole Policy following the completion of the paving operation. Any above ground utility

Special Provisions - Utilities
Cornville, Rt. 150
STP-1128(500)X, PIN 11285.00
June 15, 2004

locations not meeting the Department's Above Ground Pole Policy will require relocation to the proper offset.

UTILITY SIGNING

Any utility working within the construction limits of this project shall ensure that the traveling public is adequately protected at all times. All work areas shall be signed, lighted, and traffic flaggers employed as determined by field conditions. All traffic controls shall be in accordance with the latest edition of the Manual on Uniform Traffic Control Devices for Streets and Highways, as issued by the Federal Highway Administration.

DIG SAFE

The Contractor shall be responsible for determining the presence of underground utility facilities prior to commencing any excavation work and shall notify utilities of proposed excavation in accordance with M.R.S.A. Title 23 §3360-A, Maine "Dig Safe" System.

MAINTAINING UTILITY LOCATION MARKINGS

The Contractor will be responsible for maintaining the buried utility location markings following the initial locating by the appropriate utility or their designated representative.

THE CONTRACTOR SHALL PLAN AND CONDUCT HIS WORK ACCORDINGLY.

The following utilities are known to be located on this project:

Central Maine Power Company	Dennis Chadbourne	828-2860
Verizon	David Leavitt	990-5239

Town: **Dexter, Rt. 7**
Project: **STP-A134(000)X, PIN 11340.00**
Date: **April 26, 2004**

SPECIAL PROVISIONS
SECTION 104
UTILITIES

MEETING

A pre-construction utility meeting, as defined in Article 104.4.6 of the Standard Specifications, is **not** hereby called for.

GENERAL

These Special Provisions outline the arrangements which have been made by the Department for coordination of work and for utility adjustments, as defined in Section 104 of the Standard Specifications,

Overview:

Utility/Railroad	Aerial	Underground
Central Maine Power Company	X	
Adelphia	X	
Verizon	X	
Dexter Utilities District		X

All utility crossings over highways will provide not less than 18 feet vertical clearance over existing ground in cut or over finished grade in fill, during construction of this project.

Any times and dates mentioned are estimates only and are dependent upon favorable weather, working conditions, and freedom from emergencies. The Contractor shall have no claim against the Department if they are exceeded.

Manholes, valve boxes, service connections, and similar incidental utility plant are to be adjusted by the appropriate utility in cooperation with work being done by the Contractor.

Utility working days are Monday through Friday, conditions permitting. Times are estimated on the basis of a single crew for each utility.

Temporary utility adjustments are not anticipated at this time. If temporary relocation becomes necessary, sufficient time will need to be allowed prior to the construction for all required temporary relocation.

In all cases the Utilities shall be advised well in advance (generally three weeks) before work, dependent upon other work to be done by the Contractor, in any particular area, is to be commenced by them.

AERIAL

No Aerial Utility adjustments are anticipated as part of this project. All above ground utility locations (hydrants, poles, guys, etc.) will be reviewed for compliance with the Department's Above

Special Provisions - Utilities

Dexter, Rt. 7

STP-A134(000)X, PIN 11340.00

June 15, 2004

Ground Pole Policy following the completion of the paving operation. Any above ground utility locations not meeting the Department's Above Ground Pole Policy will require relocation to the proper offset.

SUBSURFACE

The **City of Dexter** has facilities within the limits of this project but no adjustments are anticipated. Contractor shall notify City of Dexter at least three (3) days prior to any excavating operations to allow the utility to determine the facility locations in that area. The contact for the **City of Dexter** is Randy Webber 934-3075

UTILITY SIGNING

Any utility working within the construction limits of this project shall ensure that the traveling public is adequately protected at all times. All work areas shall be signed, lighted, and traffic flaggers employed as determined by field conditions. All traffic controls shall be in accordance with the latest edition of the Manual on Uniform Traffic Control Devices for Streets and Highways, as issued by the Federal Highway Administration.

DIG SAFE

The Contractor shall be responsible for determining the presence of underground utility facilities prior to commencing any excavation work and shall notify utilities of proposed excavation in accordance with M.R.S.A. Title 23 §3360-A, Maine "Dig Safe" System.

MAINTAINING UTILITY LOCATION MARKINGS

The Contractor will be responsible for maintaining the buried utility location markings following the initial locating by the appropriate utility or their designated representative.

THE CONTRACTOR SHALL PLAN AND CONDUCT HIS WORK ACCORDINGLY.

The following utilities are known to be located on this project:

Central Maine Power Company	Dennis Chadbourne	828-2860
Adelphia	Steve Bossie	1-877-500-1055 (2421)
Verizon	David Leavitt	990-5239
City of Dexter	Randy Webber	934-3075

Town: Athens/Cambridge

PIN #: 11214.00

Date: 5/24/04

SPECIAL PROVISION

SECTION 105

General Scope of Work
(Environmental Requirements)

Instream Work shall not be allowed between the dates of 10/2 and 7/14.
(Instream work is allowed from 7/15 to 10/1.)

Stream Name(s) with Station #: 100+70, 131+46

Special Conditions: Instream work shall be conducted during low flows.

Culverts shall be placed below stream bed elevation.

Instream work consists of any activity conducted below the normal high water mark.

During the instream work window restriction, all activities are prohibited (including placement and removal of cofferdams) below the normal high water mark and during high flow conditions, except for the following:

- Work within a sealed and dewatered cofferdam. Maintenance pumping within a sealed cofferdam is also allowed.

No construction activity, whether temporary or permanent, is allowed that completely blocks a river, stream, or brook without providing downstream flow.

The contractor shall abide by all permits and conditions.

Town: Cornville
PIN #: 11285.00
Date: 5/24/04

SPECIAL PROVISION
SECTION 105
General Scope of Work
(Environmental Requirements)

Instream Work shall not be allowed between the dates of 10/2 and 7/14.
(Instream work is allowed from 7/15 to 10/1.)

Stream Name(s) with Station #s: un-named tribs. To Wesserunsett, Sta. 56+11 & 103+68

Special Conditions: Instream work shall be conducted during low flows.

Culverts shall be placed below stream bed elevation.

Two weeks notice shall be given to the Resident, prior to any culvert replacements at Sta. 56+11.

Instream work consists of any activity conducted below the normal high water mark.

During the instream work window restriction, all activities are prohibited (including placement and removal of cofferdams) below the normal high water mark and during high flow conditions, except for the following:

- Work within a sealed and dewatered cofferdam. Maintenance pumping within a sealed cofferdam is also allowed.

No construction activity, whether temporary or permanent, is allowed that completely blocks a river, stream, or brook without providing downstream flow.

The contractor shall abide by all permits and conditions.

Special Provision
Section 105
General Scope of Work
(Limitations of Operations)

- 1) Unless otherwise authorized, this contract allows for only one paving operation per day including placement of PMRAP (excluding hand work paving).
- 2) The Plant Mix Recycled Asphalt Pavement (PM RAP) work will have the following limitations.
 - A. The Contractor will be limited to having only one project with the pavement removed at any time.
 - B. PM RAP must be placed within 28 calendar days of having pavement removed.
 - C. PM RAP must be placed on one project before the pavement can be removed on the other project.
 - D. Once PM RAP has been placed, HMA base pavement shall be placed within 14 calendar days.
 - E. The Contractor will be charged \$1,500 per day for every day that the above requirements are not met.
 - F. All areas where pavement has been removed shall have surface pavement placed in the same construction season unless otherwise approved by the Project Manager.
 - G. Failure to fulfill the above requirements will result in supplemental liquidated damages in the amount of \$1,500 per calendar day.
- 3) A 24 hour notice is required for any changes in work schedule.
- 4) A 48 hour notice is required prior to paving or milling operations.

April 6, 1999

SPECIAL PROVISION
SECTION 105
CONTROL OF WORK
(Cooperation Between Contractors)

It is hereby brought to the Contractor's attention that the Department has awarded and plans to award contracts adjacent to the limits of this contract, which may be in progress simultaneously.

The Contractor shall cooperate with other Contractors at all times and provide project access as necessary and as directed by the Resident.

SPECIAL PROVISION
SECTION 107
SCHEDULING OF WORK

Replace Section 107.4.2 with the following:

"107.4.2 Schedule of Work Required Within 21 Days of Contract Execution and before beginning any on-site activities, the Contractor shall provide the Department with its Schedule of Work. The Contractor shall plan the Work, including the activity of Subcontractors, vendors, and suppliers, such that all Work will be performed in Substantial Conformity with its Schedule of Work. The Schedule must include sufficient time for the Department to perform its functions as indicated in this Contract, including QA inspection and testing, approval of the Contractor's TCP, SEWPCP and QCP, and review of Working Drawings.

At a minimum, the Schedule of Work shall include a bar chart which shows the major Work activities, milestones, durations, and a timeline. Milestones to be included in the schedule include: (A) start of Work, (B) beginning and ending of planned Work suspensions, (C) Completion of Physical Work, and (D) Completion. If the Contractor Plans to Complete the Work before the specified Completion date, the Schedule shall so indicate.

Any restrictions that affect the Schedule of Work such as paving restrictions or In-Stream Work windows must be charted with the related activities to demonstrate that the Schedule of Work complies with the Contract.

The Department will review the Schedule of Work and provide comments to the Contractor within 20 days of receipt of the schedule. The Contractor will make the requested changes to the schedule and issue the finalized version to the Department."

STP-1121(400)X
STP-1128(500)X
STP-A134(000)X
PIN: 12261.00

Special Provision
Section 107
Prosecution and Progress
(Contract Time)

- 1) The Contractor will be allowed to commence work at anytime as long as all applicable plans as required under this contract have been submitted and approved.
- 2) The completion date for this project is August 13, 2005.
- 3) For every weekday not worked once operations commence, the contractor will be charged supplemental liquidated damages per standard specification 107.7.2 (excluding days lost to inclement weather).
- 4) All work on Project STP-A134(000)X will be completed between the dates of August 16, 2004 and September 30, 2004 due to Essential Habitat restrictions.

SPECIAL PROVISION

SECTION 108RECYCLED ASPHALT PAVEMENT WITH BITUMINOUS ADDITIVE
PERFORMANCE GRADED BINDER PRICE ADJUSTMENT

Price adjustments will be based on the variance in costs for the performance graded binder component of recycled asphalt pavement with bituminous additive. They will be determined as follows:

Performance Graded Asphalt Binder The quantity of asphalt cement will be determined by taking the quantity of recycled asphalt pavement with bituminous additive (**38,000 yd²**) and multiplying by (**0.0028 for item 310.23**) times the difference in price in excess of 5 percent between the base price and the period price of asphalt cement. Adjustments will be made upward or downward, as prices increase or decrease.

Recycled Asphalt Pavement with Bituminous Additive The quantity of recycled asphalt pavement with bituminous additive will be determined from field measurements and shown on the progress estimate for each pay period.

Base Price The base price of performance graded binder to be used is the price per standard ton current with the bid opening date. This price is determined by using the average N.E. Barge Price, FOB, as listed in the Asphalt Weekly Monitor.

Period Price The period price of performance graded binder will be determined by the Department by using the average N.E. Barge Price, FOB, listed in the Asphalt Weekly Monitor current with the pay period ending date of the progress estimate.

SPECIAL PROVISION
SECTION 108
RECYCLED ASPHALT PAVEMENT WITH BITUMINOUS ADDITIVE
PERFORMANCE GRADED BINDER PRICE ADJUSTMENT

Price adjustments will be based on the variance in costs for the performance graded binder component of recycled asphalt pavement with bituminous additive. They will be determined as follows:

Performance Graded Asphalt Binder The quantity of asphalt cement will be determined by taking the quantity of recycled asphalt pavement with bituminous additive (**42,030 yd²**) and multiplying by (**0.0028 for item 310.23**) times the difference in price in excess of 5 percent between the base price and the period price of asphalt cement. Adjustments will be made upward or downward, as prices increase or decrease.

Recycled Asphalt Pavement with Bituminous Additive The quantity of recycled asphalt pavement with bituminous additive will be determined from field measurements and shown on the progress estimate for each pay period.

Base Price The base price of performance graded binder to be used is the price per standard ton current with the bid opening date. This price is determined by using the average N.E. Barge Price, FOB, as listed in the Asphalt Weekly Monitor.

Period Price The period price of performance graded binder will be determined by the Department by using the average N.E. Barge Price, FOB, listed in the Asphalt Weekly Monitor current with the pay period ending date of the progress estimate.

SPECIAL PROVISION
SECTION 310
PLANT MIX RECYCLED ASPHALT PAVEMENT
(PM RAP)

Mix Design

The PLANT MIX RECYCLED ASPHALT PAVEMENT on this project will be treated with the following material proportions:

EMULSION	3.50 %
Water	3.0 %-6.0 %
Portland cement (Type I or II)	1.50 %

The optimum moisture content for compaction shall be determined by the Department using samples obtained from the roadway, by means of AASHTO T 180, Method D.

A contract modification will be executed if percentages change from the requirements above for added asphalt, Portland cement or lime changes by more than 0.10%. Positive and negative price adjustments will be made. The price adjustment will be based upon receipted bills for materials delivered the project site. If a price adjustment is warranted, the contractor will supply the Department with all receipted bills for PG asphalt binder, Portland cement or lime for the entire project. Adjustments in water content exceeding the initial targets shall not be paid for directly, but shall be incidental.

SPECIAL PROVISION
SECTION 310
PLANT MIXED RECYCLED ASPHALT PAVEMENT

310.01 Description This work shall consist of the removal of all bituminous pavement from the existing roadway, hauling the bituminous pavement to an approved location, and processing as per Section 310.020. The gravel base of the existing roadway shall be regraded and compacted to the tolerances shown on the typicals, or as directed by the Resident prior to placing new gravel or PM RAP.

All plant mixed recycled asphalt pavement shall be placed in one or more courses on an approved base and in accordance with these specifications, and in reasonably close conformity with the lines, grades and thicknesses indicated on the plans, or as established by the Resident. Excess recycled material not used in the PMRAP process will become the property and responsibility of the contractor.

MATERIALS

310.020 Composition of Mixture The mixture shall be composed as directed in the job mix formula. The recycled asphalt pavement shall be processed by the Contractor so all material will be no larger than 37.5 mm [1.5 in] and stockpiled so as to minimize segregation. The stockpile shall be free of any materials not generally considered to be asphalt pavement. If additional material is required, the material will be supplied by the State or acquired from the Contractor through the Contract Modification process.

A job mix formula shall be furnished by the Department establishing the percentage of emulsified asphalt cement, Portland Cement, aggregate, and water to be used in the mixture. The JMF additive proportions will be verified by taking a second recycled material sample once the stockpiles have been constructed.

Emulsion, water, aggregate and Portland Cement shall be added in percentage by weight and verified by tank checks done in accordance with the minimum quality control frequencies. Cement additive may be done in dry form or introduced as a cement slurry.

310.021 Emulsified Asphalt The emulsified asphalt shall be grade MS-2, MS-4, CSS-1, or HFMS-2 meeting the requirements of Section 702.04 - Emulsified Asphalt.

310.022 Portland Cement Portland Cement shall be Type I or II meeting the requirements of AASHTO M85.

310.023 Water Water shall be clean and free from deleterious concentrations of acids, alkalis, salts or other organic or chemical substances.

310.024 New Aggregate New aggregate, if required by the contract or job mix, shall meet the requirements of Section 411.02 - Untreated Aggregate Surface Course.

EQUIPMENT

310.030 Mixing Plant The mixing plant shall be of sufficient capacity and coordinated to adequately handle the proposed construction. Either a continuous pugmill mixer or a continuous drum type mixing plant shall be used. If a

drum mixing plant is used it shall meet the requirements of Section 401.07. The mixing plant shall be capable of producing a uniform mixture meeting the requirements of the job mix formula.

310.031 Hauling Equipment Trucks used for hauling the mixture shall meet the requirements of Section 401.08.

310.032 Bituminous Pavers Pavers shall meet the requirements of Section 401.09.

310.033 Rollers Rollers shall meet the requirements of Section 401.10.

CONSTRUCTION REQUIREMENTS

310.040 Mixing The recycled asphalt pavement shall be delivered to the mixer at a temperature of not less than 10°C [50°F]. The emulsified asphalt shall meet the mixing temperature requirements listed in Section 702.05 - Application Temperatures. Recycled pavement and emulsified asphalt, and cement shall be proportioned and the mixing time set to produce a mixture in which uniform distribution of the emulsified asphalt and coating of the recycled pavement is obtained.

If a drum type mixing plant is used, the recycled asphalt pavement may be heated prior to being mixed with the emulsified asphalt to a temperature not to exceed 90°C [195°F].

Following mixing, the recycled asphalt pavement material shall be stockpiled and incorporated into the work. The material shall not be stockpiled for longer than 24 hours.

310.041 Weather Limitations The plant mixed recycled asphalt pavement shall be performed when:

- a. PM-RAP operations will be allowed between May 15th and September 15th inclusive in Zone 1 - Areas north of US Route 2 from Gilead to Bangor and north of Route 9 from Bangor to Calais. PM-RAP will be allowed between May 1st and September 30th inclusive in Zone 2 - Areas south of Zone 1 including the US Route 2 and Route 9 boundaries.
- b. The atmospheric temperature, as determined by an approved thermometer placed in the shade at the recycling location, is 10°C [50°F] and rising.
- c. When there is no standing water on the surface.
- d. During generally dry conditions, or when weather conditions are such that proper pulverizing, adding, mixing, and curing can be obtained using proper procedures, and when compaction can be accomplished as determined by the Resident. **No placement shall be allowed in the rain.**
- e. When the surface is not frozen and when overnight temperatures are expected to be above 0°C [32°F].

310.042 Spreading and Finishing The mixture shall be spread and finished in accordance with Section 401.15. Total layer thickness greater than 100 mm [4 in] will be placed in 2 lifts.

310.043 Compaction Compaction of the mixture shall be in accordance with Section 401.16. Rolling may be delayed to avoid lateral displacement as directed by the Resident. See also Section 310.051.

310.044 Joints Joints shall be constructed in accordance with Section 401.17 and shall be tacked.

310.045 Surface Tolerances The surface tolerances shall be as specified in Section 401.101, except that the maximum allowable variation shall be 10 mm [$\frac{3}{8}$ in]. The surface tolerance in existing gravel areas covered by PMRAP, with no additional gravel, shall be ± 10 mm [$\frac{3}{8}$ in].

TESTING REQUIREMENTS

310.050 Quality Control The Contractor shall operate in accordance with the approved Quality Control Plan (QCP) to assure a product meeting the contract requirements. The QCP shall meet the requirements of Section 106.6 - Acceptance and this Section. The Contractor shall not begin recycling operations until the Department approves the QCP in writing.

Prior to performing any recycling process, the Department and the Contractor shall hold a Pre-recycle conference to discuss the recycling schedule, type and amount of equipment to be used, sequence of operations, and traffic control. A copy of the QC random numbers to be used on the project shall be provided to the Resident. All field and plant supervisors including the responsible onsite recycling process supervisor shall attend this meeting.

The QCP shall address any items that affect the quality of the Recycling Process including, but not limited to, the following:

- a. JMF(s).
- b. Mixing details, pugmill type, production rates, material processing.
- c. Make and type of paver(s).
- d. Make and type of rollers including weight, weight per inch of steel wheels, and average contact pressure for pneumatic tired rollers.
- e. Testing Plan.
- f. Transportation including process for ensuring that truck bodies are clean and free of debris or contamination that could adversely affect the finished product, type of release agent used (if required)
- g. Laydown operations including procedures for mix design modification, avoiding recycling and curing in inclement weather, material yield monitoring, methods to ensure that segregation is minimized, longitudinal joint construction, procedures to determine the maximum rolling and placing speeds based on field quality control, and achieving the best possible smoothness.
- h. Methods for protecting the finished product from damage and procedures for any necessary corrective action.
- i. Method of grade checks.
- j. Examples of Quality Control forms.
- k. Name, responsibilities, and qualifications of the Responsible onsite Recycling Supervisor experienced and knowledgeable with the process.
- l. Method for calibration/verification of density gauge.
- m. A note that all testing will be done in accordance with AASHTO and MDOT/ACM procedures.
- n. Stockpile procedures including method of moisture control.

The Project Superintendent shall be named in the QCP, and the responsibilities for successful implementation of the QCP shall be outlined.

The Contractor shall sample, test, and evaluate the PMRAP process in accordance with the following procedures and minimum frequencies:

MINIMUM QUALITY CONTROL FREQUENCIES

Test or Action	Frequency	Test Method
Density	1 per 300 m [1000 ft] / lane	ASTM D 2950
Air Temperature	4 per day at even intervals	
Surface Temperature	At the beginning and end of each days operation	
Yield of all materials (Both the daily yield and yield since last test)	4 per day at even intervals	

The Contractor shall submit all QC test reports and summaries in writing, signed by the appropriate technician, and present them to the Department's onsite representative by 1:00 P.M. on the next working day, except when otherwise noted in the QCP due to local restrictions. The Contractor shall make all test results, including randomly sampled densities, available to the Department onsite.

The Contractor shall cease recycling operations whenever one of the following occurs:

- The computed yield differs from the approved Job Mix Formula by 10% or more.
- The Contractor fails to follow the approved QCP.
- The Contractor fails to achieve 98% density after corrective action has been taken.

Recycling operations shall not resume until the Contractor and the Department agree on the corrective action to be taken.

310.051 Test strip The contractor shall assemble all items of equipment for the recycling operation on the first day of the recycling work. The Contractor shall construct a test strip for the project at a location approved by the Resident. The test strip section is required to:

- Demonstrate that the equipment and processes can produce recycled layers to meet the requirements specified in these special provisions;
- Determine the effect on the grading of the recycled material by varying the forward speed of the paving machine; and;
- Determine the sequence and manner of rolling necessary to obtain the compaction requirements and establish a target TMD. The Contractor and the Department will calibrate their respective gauges at this time.

The test strip shall be at least 100 m [300 ft] in length of a full lane-width (or a half-road width).

Full PMRAP production will not begin until an acceptable test strip has been constructed. If a test strip fails to meet the requirements of this specification, the Contractor will be required to repair or replace the test strip to the

satisfaction of the Resident. Any repairs, replacement, or duplication of the test strip will be at the Contractor's expense.

Quality Assurance density testing of the recycled material will be performed by the Department using the nuclear method. After the test strip has been placed, it will be rolled as directed until the nuclear density readings show an increase in density of less than 16 kg/m³ [1 pcf] for the final four roller passes. The test strip density will be used as the target density for the recycled material. The remaining PMRAP material shall be compacted to a minimum density of 98% of the target density as determined in the control section.

ACCEPTANCE TEST FREQUENCY

Property	Frequency	Test Method
In-place Density	1 per 600 m [2000 ft] / lane	ASTM D 2950

310.052 Repairs Repairs and maintenance for the PMRAP layers, during and after the curing period, resulting from damage caused by traffic, weather or environmental conditions, or caused by the Contractor's operations or equipment, shall be completed at no additional cost to the Department.

Low areas will be repaired using a hot mix asphalt shim course. Areas up to 25mm [1 in] high can be repaired by milling or shimming with hot mix asphalt. Areas higher than 25mm [1 in] will be repaired using a hot mix asphalt shim. All repair work will be done with the Resident's approval at the Contractor's expense.

310.06 Curing No new hot mix asphalt pavement or additional layers of PM-RAP shall be placed on the recycled asphalt pavement until a curing period of (4) four days has elapsed. The curing period starts once the PM-RAP has been placed in the roadway. When weather conditions are unfavorable, the curing period may be extended by the Resident.

310.07 Method of Measurement Plant Mixed Recycled Asphalt Pavement shall be measured by the square meter [square yard].

310.08 Basis of Payment The accepted quantity of Plant Mixed Recycled Asphalt Pavement will be paid for at the contract unit price per square meter [square yard], complete in-place which price will be full compensation for furnishing all equipment and labor for removing existing pavement, regrading and compacting existing gravel base, processing, mixing, testing, placing, and compacting, excess material relocation, and for all incidentals necessary to complete the work.

Payments will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
310.23 - 75mm [3 in] Plant Mixed Recycled Asphalt Pavement	Square Meter [yd ²]
310.24 - 100mm [4 in] Plant Mixed Recycled Asphalt Pavement	Square Meter [yd ²]
310.25 - 125mm [5 in] Plant Mixed Recycled Asphalt Pavement	Square Meter [yd ²]
310.26 - 150mm [6 in] Plant Mixed Recycled Asphalt Pavement	Square Meter [yd ²]

SPECIAL PROVISION
SECTION 401
HOT MIX ASPHALT
($\frac{3}{4}$ inch (20mm) Surface Treatment)

Description The Contractor shall furnish and place one or more courses of Hot Mix Asphalt (HMA) pavement on an approved base in accordance with the Contract documents and in reasonably close conformity with the lines, grades, thicknesses and typical cross sections shown on the plans or established. The Department shall accept this work under Quality Assurance provisions as specified in Standard Specifications Section 401 – Hot Mix Asphalt Pavement, and Standard Specifications Section 106 - Quality.

The 20 mm [$\frac{3}{4}$ in] HMA Surface Course shall meet all of the Materials, Seasonal Limitations and Construction requirements of Section 401, with the following additions and changes.

GRADATION REQUIREMENTS

Sieve Size	Percent Passing
12.5 mm	100
9.5 mm	95-100
4.75 mm	-95
2.36 mm	32-67
1.18 mm	-
0.600 mm	-
0.300 mm	-
0.075 mm	2-10

VOLUMETRIC DESIGN CRITERIA

Voids at N_{des}	4.0
VMA	15.0 minimum
VFB	65-80
Fines/Eff.Binder	0.6-1.2

A test strip at a nominal depth of 30mm [$1\frac{1}{4}$ in], full lane width, shall be required if the JMF has not been used or approved on a MDOT project in the current calendar year. If a test strip is required, it shall conform to the following requirements:

On roads open to two way traffic, the test strip shall be placed over the full width of the travel way section, not to exceed 600 meters [2000 ft] in length, or 400 Mg [440 ton] production. Prior to the placement of the test strip a passing verification test is required. A fog coat of Item 409.15, Bituminous Tack Coat, shall be applied to the level course prior to the placement of the 20mm Surface Treatment Course, payment to be made under the 409.15 pay item.

The test strip **shall not** be excluded from QA analysis, but will be evaluated in accordance with Section 401.03. The Contractor shall notify the Department at least 48 hours in advance of placing

the test strip. The test strip is intended to allow the Contractor to establish a method of compaction for the 20mm [$\frac{3}{4}$ in] surface course areas. Once the methods are established, rolling patterns, equipment, and methods will become part of the QCP. The test strip will allow for any necessary adjustments to the mix design and or plant mixing procedures, as well as for the Department to evaluate the quality of the pavement.

Mix samples and cores will be obtained from the test strip. A minimum of three mix samples shall be randomly selected from the test strip. Five cores shall be randomly sampled from the mat and tested for density verification. Should the resulting core values average less than 92.0% TMD, (average of 5 tests), the Department will reject the strip. The Contractor will remove and replace rejected test strips at their expense. After completion of the test strip, the Contractor shall make any final adjustments to the job mix formula in accordance to Standard Specifications, Section 401, subsection 401.03 - Composition of Mixtures, or compaction method. Paving operations shall not resume until the Contractor and the Department determines that material meeting the Contract requirements can be produced, and any changes to the Job Mix Formula have been approved by the Department. The Department shall pay for an accepted test strip as determined Section 401.222 – Pay Factor A and B, for this item. A new test strip shall be required if a current lot is terminated or completed, and a new lot is started.

The Department may halt the production and placement of the 20mm [$\frac{3}{4}$ in] HMA Surface Course and require the construction of a new test strip if the Department finds that material being produced, hauled, or placed does not meet the requirements of Sections 401.08 through 401.18.

The Contractor shall sample, test, and evaluate Hot Mix Asphalt Pavement in accordance with the minimum frequencies outlined in Section 401, Table 2: Minimum Quality Control Frequencies.

The Contractor shall monitor plant production using running average of three control charts as specified in Section 106, and Control Limits as specified in Section 401, Table 3: Control Limits.

The Acceptance Criteria shall be as specified in Section 401, Table 4: Acceptance Criteria.

The Acceptance Limit targets will be as specified on the JMF, and the Department will use the appropriate Acceptance Limits table from Section, Table 5: Method A, or Table 7: Method B and C, for the acceptance method noted in the Special Provision 403.

The Contractor shall cease paving operations whenever one of the following occurs on a lot in progress:

- a) The Pay Factor for VMA, Voids @ N_d , Percent PGAB, composite gradation, VFB, fines to effective binder or density using all Acceptance or all Quality Control tests for the current lot is less than 0.85.
- b) The Coarse Aggregate Angularity or Fine Aggregate Angularity value falls below the requirements of Section 703.07 , Table 3, for the design traffic level.
- c) Each of the first 2 control tests for the lot fall outside the upper or lower limits for VMA, Voids @ N_d , or Percent PGAB. This includes any case where both tests are out on the same, or different properties.

- d) The Flat and Elongated Particles value exceeds 10 percent by ASTM D-4791.
- e) There is any visible damage to the aggregate due to over-densification other than on variable depth shim courses.
- f) The Contractor fails to follow the approved QCP.
- g) The Contractors control chart shows the process to be out of control on any property listed in Section 401, subsection 401.18 , Table 3: Control Limits

Price Adjustment The Department will apply price adjustments for the Hot Mix Asphalt utilized under this Special Provision as outlined in Section 401.222 : Pay Factor for methods A and B; mixes with Volumetric Property requirements.

Dispute Resolution The Contractor may dispute an acceptance test for this item as outlined in Section 401.223 for PGAB, Air Void, and VMA Content only.

Method of Measurement The Department will measure Hot Mix Asphalt pavement by the megagram in accordance with Section 109 - Measurement and Payment.

Basis of Payment The Department will pay for the Work, in place and accepted, in accordance with the applicable sections of the Special Provisions at the contract unit price per megagram(ton).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
403.210 9.5mm Hot Mix Asphalt Pavement	Megagram (ton)

SPECIAL PROVISION
SECTION 403
HOT MIX ASPHALT OVERLAY

Desc. of Course	Grad. Design	Item Number	Bit Cont. % of Mix	Total Thick	No. Of Layers	Comp. Notes
<u>Main Line Traveled Way And Shoulders</u>						
<u>Over Plant Mixed Recycled Asphalt Pavement</u>						
Wearing	9.5 mm	403.210	N/A	1¼"	1	4,7
Base	12.5 mm	403.213	N/A	1½"	1/more	4,7
<u>Plant Mixed Recycled Asphalt Pavement</u>						
<u>Main Line Traveled Way And Shoulders</u>						
Base	See Special Prov.	310.23	See Special Prov.	3"	1	Special Prov.
<u>Approach Roads</u>						
Wearing	9.5mm	403.210	N/A	1¼"	1	4,7
Base	12.5mm	403.213	N/A	1½"	1/more	4,7
<u>Drives, Misc.</u>						
Wearing	9.5mm	403.209	N/A	2"	1/more	2,3,9,10,13

COMPLEMENTARY NOTES

2. The density requirements are waived.
3. The design traffic level for mix placed shall be <0.3 million ESALS.
4. The design traffic level for mix placed shall be 0.3 to <3 million ESALS. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **50 gyrations.**
7. Section 106.6 Acceptance, (1) Method A.
8. Section 106.6 Acceptance, (2) Method B.
9. Section 106.6 Acceptance, (2) Method C.
10. A **"FINE"** 9.5 mm mix with a gradation above or through the restricted zone shall be used for this item.
13. A mixture meeting the requirements of section 703.09 Grading 'D', with a minimum PGAB content of 6%, and the limits of Special Provision 401, Table 9 (Drives and Sidewalks) for PGAB content and gradation may be substituted for this item. A job mix formula shall be submitted to the department for approval.

Tack Coat

A tack coat of emulsified asphalt, RS-1 or HFMS-1, Item #409.15 shall be applied to any existing pavement at a rate of approximately 0.025 G/SY, and on milled pavement approximately 0.05G/SY, prior to placing a new course. **A fog coat of emulsified asphalt shall be applied between Plant Mixed Recycled Asphalt Pavement course and the Base course, at a rate not to exceed 0.025 G/SY. A fog coat of emulsified asphalt shall be applied between the Base course and the Surface course, at a rate not to exceed 0.025 G/SY.**

Tack used between new layers of pavement will be paid for at the contract unit price for Item 409.15 Bituminous Tack Coat.

STP-A134(000)X Dexter
PIN 12261.00 Athens & Cambridge
¾ inch Surface Treatment & Maintenance Surface Treatment
April 27, 2004

SPECIAL PROVISION

SECTION 403

HOT MIX ASPHALT OVERLAY

Desc. of Course Notes	Grad. Design	Item Number	Bit Cont. % of Mix	Total	No. of Thick Layers	Comp.
<u>Main Line Traveled Way and Shoulders</u>						
<u>¾ inch Overlay</u>						
Wearing	9.5mm	403.210	N/A	¾"	1	4,7,10,22
Shim	9.5mm	403.211	N/A	variable	1/more	2,4,7,10
<u>Approach Roads</u>						
Wearing	9.5mm	403.210	N/A	1"	1	4,7,10,22
<u>Drives, Misc.</u>						
Wearing	9.5mm	403.209	N/A	1 – 2 inch	1/more	2,3,9,10,13
<u>Maintenance Surface Treatment</u>						
Wearing	9.5mm	461.210	N/A	5/8"	1	4,7,10,22
Shim	9.5mm	461.210	N/A	variable	1/more	2,4,7,10

COMPLEMENTARY NOTES

2. The density requirements are waived.
3. The design traffic level for mix placed shall be <0.3 million ESALS.
4. The design traffic level for mix placed shall be 0.3 to <3 million ESALS. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **50 gyrations.**
7. Section 106.6 Acceptance, (1) Method A.
9. Section 106.6 Acceptance, (2) Method C.
10. A **"FINE"** 9.5 mm mix with a gradation above or through the restricted zone shall be used for this item.
13. A mixture meeting the requirements of section 703.09 Grading 'D', with a minimum PGAB content of 6%, and the limits of Special Provision 401, Table 9 (Drives and Sidewalks) for PGAB content and gradation may be substituted for this item. A job mix formula shall be submitted to the department for approval.
22. See Special Provision 401 – ¾ inch (20mm) Surface Treatment for project specifics.

Tack Coat

A tack coat of emulsified asphalt, RS-1 or HFMS-1, Item 409.15 shall be applied to any existing pavement at a rate of approximately 0.025 gal/yd², and on milled pavement approximately 0.05 gal/yd², prior to placing a new course. A fog coat of emulsified asphalt shall be applied between shim / intermediate course and the surface course, at a rate not to exceed 0.025 gal/yd².

Tack used between layers of pavement will be paid for at the contract unit price for Item 409.15 Bituminous Tack Coat.

SPECIAL PROVISION
SECTION 652
MAINTENANCE OF TRAFFIC
(Traffic Control)

652.7 Method of Measurement. This entire Subsection is revised to read:
Traffic Control Supervisor, furnishing, installation, and maintenance of all traffic control devices will be measured as one **lump sum** for all work authorized and performed.

652.8 Basis of Payment. This entire Subsection is revised to read:
Traffic Control will be paid for at the contract **lump sum** price. Payment will be full compensation for the Traffic Control Supervisor, approach signs, work area signs, drums, cones, panel markers, barricades, arrow boards etc. and maintenance thereof including the setting up and taking down of lane closures as many times as necessary shall be considered part of the lump sum price.

Maintenance of signs includes: replacing devices damaged, lost, or stolen, and cleaning and moving as many times as necessary throughout the life of the contract, regardless whether the work areas or projects are geographically separated or not separated.

The Lump Sum will be payable in installments as follows: 5% of the Lump Sum once the approach signing is complete and approved, with the 95% balance to be paid as the work progresses at a rate proportional to the percentage completion of the Contract.

Failure by the contractor to follow the Contracts 652 Special Provisions and/or The Manual on Uniform Traffic Control Devices (MUTCD) and/or The Contractors own Traffic Control Plan will result in a reduction in payment, computed by reducing The Lump Sum Total by 5% per occurrence. The Departments Resident Engineer or any other representative of The Department reserves the right to suspend the work at any time and request a meeting to discuss violations and remedies. The Department shall not be held responsible for any delay in the work due to any suspension under this item.

All other requirements under the Standard Specifications Section 652 will be a part of the lump sum item.

There will be no extra payment for this pay item after the expiration of contract time.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
652.39 Work Zone Traffic Control	Lump Sum

SPECIAL PROVISION
SECTION 652
MAINTENANCE OF TRAFFIC

Approaches Approach signing shall include the following signs as a minimum. Field conditions may warrant the use of additional signs as determined by the Resident.

Road Work Next x Miles
Road Work 500 Feet
End Road Work

Work Area At each work site, signs and channelizing devices shall be used as directed by the Resident. Signs include:

Road Work xxxx¹
One Lane Road Ahead
Flagger Sign

Other typical signs include:

Be Prepared to Stop
Low Shoulder
Bump
Pavement Ends


The above lists of Approach signs and Work Area signs are representative of the contract requirements. Other sign legends may be required.

The Contractor shall conduct their operations in such a manner that the roadway will not be restricted to one lane for more than 800 m [2,500 ft] at each work area. Where more than one work area restricts traffic to one lane operation, these work areas shall be separated by at least 1.6 km [1 mile] of two way operation.


Temporary Centerline A temporary centerline shall be placed each day on all new pavement to be used by traffic. The temporary centerline, when specified of reflectorized traffic paint, shall conform to the standard marking patterns used for permanent markings.

Failure to apply a temporary centerline daily will result in suspension of paving until temporary markers are applied to all previously placed pavement.

¹ "Road Work Ahead" to be used in mobile operations and "Road Work xx ft" to be used in stationary operations as directed by the Resident.



TYPICAL -- PROJECT APPROACH SIGNING -- TWO WAY TRAFFIC



TYPICAL APPLICATION: TWO - WAY, TWO LANE ROADWAY,
CLOSING ONE LANE USING FLAGGERS

* Formulas for L are as follows:

For speed limits of 40 mph (60 km/h) or less:

$$L = \frac{WS^2}{60} \quad (L = \frac{WS^2}{155})$$

For speed limits of 45 mph (70 km/h) or greater:

$$L = WS \quad (L = \frac{WS}{1.6})$$

* Formulas for L are as follows:

A minimum of 5 channelization devices shall be used in the taper.

TYPE OF TAPER	TAPER LENGTH (L)*
Merging Taper	at least L
Shifting Taper	at least 0.5L
Shoulder Taper	at least 0.33L
One-Lane, Two-Way Traffic Taper	100 ft (30 m) maximum
Downstream Taper	100 ft (30 m) per lane

CHANNELIZATION DEVICE SPACING

The spacing of channelization devices shall not exceed a distance equal to 1.0 times the speed limit in mph when used for taper channelization, and a distance in feet of 2.0 times the speed limit in mph when used for tangent channelization.

GENERAL NOTES;

1. Final placement of signs and devices may be changed to fit field conditions as approved by the Resident.

SIGN SPACING TABLE			
Road Type	Distance Between Signs**		
	A	B	C
Urban 30 mph (50 km/h) or less	100 (30)	100 (30)	100 (30)
Urban 35 mph (55 km/h) and greater	350 (100)	350 (100)	350 (100)
Rural	500 (150)	500 (150)	500 (150)
Expressway / Urban Parkway	2,640 (800)	1,500 (450)	1000 (300)

**Distances are shown in feet (meters).

SUGGESTED BUFFER ZONE LENGTHS

Speed (mph)	Length (feet)	Speed (mph)	Length (feet)
20	115	40	325
25	155	45	360
30	200	50	425
35	250	55	495

**SPECIAL PROVISION
SECTION 656**

Temporary Soil Erosion and Water Pollution Control

The following is added to Section 656 regarding Project Specific Information and Requirements. All references to the Maine Department of Transportation Best Management Practices for Erosion and Sediment Control (a.k.a. Best Management Practices manual or BMP Manual) are a reference to the latest revision of said manual. The "Table of Contents" of the latest version is dated "1/19/00" (available at <http://www.state.me.us/mdot/mainhtml/bmp/bmpjan2000.pdf>.) **Procedures specified shall be according to the BMP Manual unless stated otherwise.**

Any and all references to "bark mulch" or "composted bark mix" shall be a reference to "Erosion Control Mix" in accordance with *Standard Specification, Section 619 - Mulch*.

Project Specific Information and Requirements

The following information and requirements apply specifically to this Project. The temporary soil erosion and water pollution control measures associated with this work shall be addressed in the SEWPCP.

This project is in the Wesserunett Stream & Cambridge Pond watersheds, which are considered **SENSITIVE** in accordance with the BMP Manual. The Contractor's SEWPCP shall comply with Section II.B., Guidelines for Sensitive Waterbodies in the BMP Manual.

Newly disturbed earth shall be mulched by the end of each workday. Mulch shall be maintained on a daily basis.

The SEWPCP shall describe the location and method of temporary erosion and sediment control for existing and proposed catch basins, outlet areas and culvert inlets and outlets.

Dust control items other than those under Standard Specification 637 and Special Provision 637, if applicable, shall be included in the plan.

Permanent slope stabilization measures shall be applied within one week of the last soil disturbance.

Permanent seeding shall be done in accordance with *Special Provision, Section 618, Seeding* unless the Contract states otherwise.

Culvert inlet and outlet protection shall be installed within 48 hours of culvert installation, or prior to a storm event, whichever is sooner.

After November 1 the Contractor shall use winter stabilization methods, such as Wood Waste Erosion Control Mix as specified in Special Provision § 617. If required, spring procedures for permanent stabilization shall also be described in the plan. Use of this product for over-winter temporary erosion control will be incidental to the contract and be paid for as part of Pay Item 656.75.

All disturbed ditches shall be stabilized by the end of each workday. Stabilization shall be maintained on a daily basis.

SPECIAL PROVISION
SECTION 656
Temporary Soil Erosion and Water Pollution Control

Erosion control blanket shall be installed in the bottoms of all ditches except where a stone lining is planned. Seed shall be applied prior to the placement of the blanket.

If check dams are used, they shall be constructed of stone in accordance with BMP Manual, Section 9.

Hay Bale check dams will not be allowed.

The Contractor's SEWPCP shall address in-stream work at the following locations:

sta. 100+70 & 131+46

Stream flow shall be maintained at all times.

A cofferdam sedimentation basin is required if cofferdams are used. The basin shall be located in an upland area where the water can settle and seep into the ground or be released slowly to the resource in a manner that will not cause erosion. The location of such a cofferdam sedimentation basin shall be addressed in the SEWPCP.

Instream culverts shall be placed below stream bed elevation.

SPECIAL PROVISION

SECTION 656

Temporary Soil Erosion and Water Pollution Control

The following is added to Section 656 regarding Project Specific Information and Requirements. All references to the Maine Department of Transportation Best Management Practices for Erosion and Sediment Control (a.k.a. Best Management Practices manual or BMP Manual) are a reference to the latest revision of said manual. The "Table of Contents" of the latest version is dated "1/19/00" (available at <http://www.state.me.us/mdot/mainhtml/bmp/bmpjan2000.pdf>.) **Procedures specified shall be according to the BMP Manual unless stated otherwise.**

Any and all references to "bark mulch" or "composted bark mix" shall be a reference to "Erosion Control Mix" in accordance with *Standard Specification, Section 619 - Mulch*.

Project Specific Information and Requirements

The following information and requirements apply specifically to this Project. The temporary soil erosion and water pollution control measures associated with this work shall be addressed in the SEWPCP.

This project is in the Wesserunsett watershed, which is considered **SENSITIVE** in accordance with the BMP Manual. The Contractor's SEWPCP shall comply with Section II.B., Guidelines for Sensitive Waterbodies in the BMP Manual.

Two weeks notice shall be given to the Resident before the contractor will be allowed to replace the two culverts at Station 56+11.

Newly disturbed earth shall be mulched by the end of each workday. Mulch shall be maintained on a daily basis.

The SEWPCP shall describe the location and method of temporary erosion and sediment control for existing and proposed catch basins, outlet areas and culvert inlets and outlets.

Dust control items other than those under Standard Specification 637 and Special Provision 637, if applicable, shall be included in the plan.

Permanent slope stabilization measures shall be applied within one week of the last soil disturbance.

Permanent seeding shall be done in accordance with *Special Provision, Section 618, Seeding* unless the Contract states otherwise.

Culvert inlet and outlet protection shall be installed within 48 hours of culvert installation, or prior to a storm event, whichever is sooner.

After November 1 the Contractor shall use winter stabilization methods, such as Wood Waste Erosion Control Mix as specified in Special Provision § 617. If required, spring procedures for permanent stabilization shall also be described in the plan. Use of this product for over-winter temporary erosion control will be incidental to the contract and be paid for as part of Pay Item 656.75.

SPECIAL PROVISION

SECTION 656

Temporary Soil Erosion and Water Pollution Control

All disturbed ditches shall be stabilized by the end of each workday. Stabilization shall be maintained on a daily basis.

Erosion control blanket shall be installed in the bottoms of all ditches except where a stone lining is planned. Seed shall be applied prior to the placement of the blanket.

If check dams are used, they shall be constructed of stone in accordance with BMP Manual, Section 9.

Hay Bale check dams will not be allowed.

The Contractor's SEWPCP shall address in-stream work at the following locations:

Stations 56+11 & 103+68

Stream flow shall be maintained at all times.

A cofferdam sedimentation basin is required if cofferdams are used. The basin shall be located in an upland area where the water can settle and seep into the ground or be released slowly to the resource in a manner that will not cause erosion. The location of such a cofferdam sedimentation basin shall be addressed in the SEWPCP.

Instream culverts shall be placed below stream bed elevation.

Permits & Cultural Resources Unit

PIN #: 11285.00

Location: Cornville

Permit Member: Laurie Rowe

Photographs ☐

Database/Projex ☒

Package to ENV Coordinator: 5/24/04

☒ Section 106 and Tribal Consultation

Architectural Resources

MOA ☐

Applicable ☒

Approved ☒

Archeological Resources

MOA ☐

Applicable ☒

Approved ☒

Tribal Consultation

N/A ☒

Applicable ☐

Approved ☐

☒ 4(f) and 6(f)

Section 4(f)

N/A ☒

Applicable ☐

Approved ☐

LAWCON 6(f)

N/A ☒

Applicable ☐

Approved ☐

☒ FEMA

N/A ☒

Applicable ☐

Approved ☐

☒ Maine Department of Environmental Protection (MDEP) Site Location of Development

N/A ☒

Applicable ☐

Approved ☐

☒ Local Zoning, Title 30-A, Section 4325-6.

Is the project something other than the highway and bridge system, such as a maintenance lot, building/parking facility? Yes

☐ No ☒. If no, the project is exempt.

If yes, continue. Does the town in which the project is located have a comprehensive plan consistent with the Growth Management Program? Yes ☐ No ☐. If no, the project is exempt.

If yes, local zoning ordinances and/or permits are needed.

Approved ☐

☒ Maine Department of Inland Fisheries and Wildlife (MDIFW) Essential Habitat

Eagle Nest

N/A ☒

Applicable ☐

Approved ☐

Piping Plover

N/A ☒

Applicable ☐

Approved ☐

Roseate Tern

N/A ☒

Applicable ☐

Approved ☐

☒ United States Fish and Wildlife Service (USFWS), Migratory Bird Act

N/A ☒

Applicable ☐

☒ Maine Department of Conservation/ Public Lands, Submerged Land Lease

N/A ☒

Applicable ☐

☒ Land Use Regulation Commission (LURC) ☒ Not Applicable

No permit

☐

Notice

☐

Approved ☐

Permit

☐

Approved ☐

☒ Maine Department of Environmental Protection (MDEP), Natural Resource Protection Act

No permit required ☐

Exempt ☐ (Must use erosion and sediment control and not block fish passage.)

PBR ☒

Approved ☒

Tier 1 ☐

Approved ☐

Tier 2 ☐

Approved ☐

Tier 3 ☐

Approved ☐

☒ Army Corps of Engineers (ACOE), Section 10 of the Rivers and Harbors Act and Section 404 of the Clean Water Act.

No permit required ☐

Category 1-NR ☒

Approved ☒

Category 2 ☐

Approved ☐

Category 3 ☐

Approved ☐

☒ IN-WATER TIMING RESTRICTIONS: 105 Special Provision ☒ n/a ☐

Dates instream work is allowed: 7/15 to 10/1

☒ Special Provision 656, Erosion Control Plan

Boxes marked in red indicate items that are attached and need to be placed in the contract by the Project Manager.

Permits & Cultural Resources Unit

PIN #: 11340.00

Location: Dexter

Permit Member: Laurie Rowe

Photographs ☐

Database/Projex ☒

Package to ENV Coordinator: 5/25/04

☒ **Section 106 and Tribal Consultation**

Architectural Resources

MOA ☒ Applicable ☐ Approved ☐

Archeological Resources

MOA ☒ Applicable ☐ Approved ☐

Tribal Consultation

N/A ☒ Applicable ☐ Approved ☐

☒ **4(f) and 6(f)**

Section 4(f)

N/A ☒ Applicable ☐ Approved ☐

LAWCON 6(f)

N/A ☒ Applicable ☐ Approved ☐

☒ **FEMA**

N/A ☒ Applicable ☐ Approved ☐

☒ **Maine Department of Environmental Protection (MDEP) Site Location of Development**

N/A ☒ Applicable ☐ Approved ☐

☒ **Local Zoning, Title 30-A, Section 4325-6.**

Is the project something other than the highway and bridge system, such as a maintenance lot, building/parking facility? Yes

☐ No ☒. If no, the project is exempt.

If yes, continue. Does the town in which the project is located have a comprehensive plan consistent with the Growth Management Program? Yes ☐ No ☐. If no, the project is exempt.

If yes, local zoning ordinances and/or permits are needed. Approved ☐

☒ **Maine Department of Inland Fisheries and Wildlife (MDIFW) Essential Habitat**

Eagle Nest N/A ☐ Applicable ☒ Approved ☒

Piping Plover N/A ☒ Applicable ☐ Approved ☐

Roseate Tern N/A ☒ Applicable ☐ Approved ☐

☒ **United States Fish and Wildlife Service (USFWS), Migratory Bird Act**

N/A ☒ Applicable ☐

☒ **Maine Department of Conservation/ Public Lands, Submerged Land Lease**

N/A ☒ Applicable ☐

☒ **Land Use Regulation Commission (LURC)** ☒ Not Applicable

No permit ☐

Notice ☐ Approved ☐

Permit ☐ Approved ☐

☒ **Maine Department of Environmental Protection (MDEP), Natural Resource Protection Act**

No permit required ☒

Exempt ☐ (Must use erosion and sediment control and not block fish passage.)

PBR ☐ Approved ☐

Tier 1 ☐ Approved ☐

Tier 2 ☐ Approved ☐

Tier 3 ☐ Approved ☐

☒ **Army Corps of Engineers (ACOE), Section 10 of the Rivers and Harbors Act and Section 404 of the Clean Water Act.**

No permit required ☒

Category 1-NR ☐ Approved ☐

Category 2 ☐ Approved ☐

Category 3 ☐ Approved ☐

☒ **TIMING RESTRICTIONS: 105 Special Provision** ☒ n/a ☐

Dates work is allowed: Work within Essential Habitat area is limited to July 15 to January 31. See Attached map for Essential Habitat Area.

☒ **Special Provision 656, Erosion Control Plan**

Boxes marked in red indicate items that are attached and need to be placed in the contract by the Project Manager.

DEPARTMENT OF ENVIRONMENTAL PROTECTION (DEP)
PERMIT BY RULE NOTIFICATION FORM
(For use with DEP Regulation, Chapter 305)

■ MDOT PIN: 11214.00

Name of Applicant: State of Maine Department of Transportation Name of Contact: David Gardner
Mailing Address: 16 Station State House Town/City: Augusta State: Me. Zip Code: 04330-0016
Daytime Telephone #: (207)-624-3105 Name of Wetland, Water Body or Stream: West Branch Wesserunsett
Strea, Unnamed streams

Detailed Directions to Site: Project begins 0.85 miles north of the Athens/Cornville towline and extends northerly 2.50 miles, and then begins again 0.90 miles north of the Harmony/Cambridge town line and extends northerly 0.71 miles.

Town/City: Athens-Cambridge

Map #: N/A

Lot #: N/A

County: Somerset

Description of Project: Highway Improvement project involving culvert, guardrail, slope and ditch maintenance and repairs and vertical and horizontal alignment changes. The project will be performed in accordance with erosion control measures conforming with the latest versions of the *State of Maine Department of Transportation Standard Specifications for Highways and Bridges* and the *Department of Transportation's Best Management Practices for Erosion and Sediment Control*.

Part of a larger project? ☐ Yes ☒ No

(CHECK ONE) This project... ☒ does ☐ does not ...involve work below mean low water.

I am filing notice of my intent to carry out work which meets the requirements for Permit By Rule (PBR) under DEP Regulation, Chapter 305. I have a copy of PBR Sections checked below. I have read and will comply with all of the standards.

- | | | |
|---|---|---|
| <input type="checkbox"/> Sec. (2) Soil Disturbance | <input type="checkbox"/> Sec. (8) Shoreline stabilization | <input type="checkbox"/> Sec. (14) Piers, Wharves & Pilings |
| <input type="checkbox"/> Sec. (3) Intake Pipes | <input type="checkbox"/> Sec. (9) Utility Crossing | <input type="checkbox"/> Sec. (15) Public Boat Ramps |
| <input type="checkbox"/> Sec. (4) Replacement of Structures | <input type="checkbox"/> Sec. (10) Stream Crossing | <input type="checkbox"/> Sec. (16) Coastal Sand Dune Projects |
| <input type="checkbox"/> Sec. (5) REPEALED | <input checked="" type="checkbox"/> Sec. (11) State Transport. Facilities | <input type="checkbox"/> Sec. (17) Transfers/Permit Extension |
| <input type="checkbox"/> Sec. (6) Movement of Rocks or Vegetation | <input type="checkbox"/> Sec. (12) Restoration of Natural Areas | <input type="checkbox"/> Sec. (18) Maintenance Dredging |
| <input type="checkbox"/> Sec. (7) Outfall Pipes | <input type="checkbox"/> Sec. (13) F&W Creation/Enhance/Water Quality Improvement | |

I authorize staff of the Departments of Environmental Protection, Inland Fisheries & Wildlife, and Marine Resources to access the project site for the purpose of determining compliance with the rules. I also understand that **this permit is not valid until approved by the Department or 14 days after receipt by the Department, whichever is less.**

I have attached all of the following required submittals. **NOTIFICATION FORMS CANNOT BE ACCEPTED WITHOUT THE NECESSARY ATTACHMENTS:**

- A \$50 (non-refundable) payment shall be done by internal billing.
- **Attach** a U.S.G.S. topo map or Maine Atlas & Gazetteer map with the project site clearly marked.
- ☐ **Attach** photographs showing existing site conditions (unless not required under standards).

Signature of Applicant:

John E. Dority, Chief Engineer

Date:

01/22/04

Keep the bottom copy as a record of permit. Send the form with attachments via certified mail to the Maine Dept. of Environmental Protection at the appropriate regional office listed below. The DEP will send a copy to the Town Office as evidence of the DEP's receipt of notification. No further authorization by DEP will be issued after receipt of notice. Permits are valid for two years. **Work carried out in violation of any standard is subject to enforcement action.**

AUGUSTA DEP STATE HOUSE STATION 17 AUGUSTA, ME 04333-0017 (207)287-2111 PORTLAND DEP 312 CANCO ROAD PORTLAND, ME 04103 (207)822-6300 BANGOR DEP 106 HOGAN ROAD BANGOR, ME 04401 (207)941-4570 PRESQUE ISLE DEP 1235 CENTRAL DRIVE PRESQUE ISLE, ME 04769 (207)764-0477

OFFICE USE ONLY
PBR # FP

Ck.#

Date

Staff

Acc. Date

Staff

Def. Date

After Photos

DEPARTMENT OF ENVIRONMENTAL PROTECTION (DEP)
PERMIT BY RULE NOTIFICATION FORM
(For use with DEP Regulation, Chapter 305)

■ MDOT PIN: 11285.00

Name of Applicant: State of Maine Department of Transportation Name of Contact: David Gardner
Mailing Address: 16 Station State House Town/City: Augusta State: Me. Zip Code: 04330-0016
Daytime Telephone #: (207)-624-3105 Name of Wetland, Water Body or Stream: Devils Bog, Unnamed Stream

Detailed Directions to Site: Project is located on Rte 150, Beginning 0.51 of a mile northerly of the Skowhegan town line and extending northerly 2.41 miles.

Town/City: Cornville Map #: N/A Lot #: N/A County: Somerset

Description of Project: Highway overlay involving culvert, guardrail, slope and ditch maintenance and repairs. The project will be performed in accordance with erosion control measures conforming with the latest versions of the *State of Maine Department of Transportation Standard Specifications for Highways and Bridges* and the *Department of Transportation's Best Management Practices for Erosion and Sediment Control*.

Part of a larger project? ☐ Yes ☒ No

(CHECK ONE) This project... ☒ does ☐ does not ...involve work below mean low water.

I am filing notice of my intent to carry out work which meets the requirements for Permit By Rule (PBR) under DEP Regulation, Chapter 305. I have a copy of PBR Sections checked below. I have read and will comply with all of the standards.

- | | | |
|---|---|---|
| <input type="checkbox"/> Sec. (2) Soil Disturbance | <input type="checkbox"/> Sec. (8) Shoreline stabilization | <input type="checkbox"/> Sec. (14) Piers, Wharves & Pilings |
| <input type="checkbox"/> Sec. (3) Intake Pipes | <input type="checkbox"/> Sec. (9) Utility Crossing | <input type="checkbox"/> Sec. (15) Public Boat Ramps |
| <input type="checkbox"/> Sec. (4) Replacement of Structures | <input type="checkbox"/> Sec. (10) Stream Crossing | <input type="checkbox"/> Sec. (16) Coastal Sand Dune Projects |
| <input type="checkbox"/> Sec. (5) REPEALED | <input checked="" type="checkbox"/> Sec. (11) State Transport. Facilities | <input type="checkbox"/> Sec. (17) Transfers/Permit Extension |
| <input type="checkbox"/> Sec. (6) Movement of Rocks or Vegetation | <input type="checkbox"/> Sec. (12) Restoration of Natural Areas | <input type="checkbox"/> Sec. (18) Maintenance Dredging |
| <input type="checkbox"/> Sec. (7) Outfall Pipes | <input type="checkbox"/> Sec. (13) F&W Creation/Enhance/Water Quality Improvement | |

I authorize staff of the Departments of Environmental Protection, Inland Fisheries & Wildlife, and Marine Resources to access the project site for the purpose of determining compliance with the rules. I also understand that **this permit is not valid until approved by the Department or 14 days after receipt by the Department, whichever is less.**

I have attached all of the following required submittals. **NOTIFICATION FORMS CANNOT BE ACCEPTED WITHOUT THE NECESSARY ATTACHMENTS:**

- A \$50 (non-refundable) payment shall be done by internal billing.
- Attach a U.S.G.S. topo map or Maine Atlas & Gazetteer map with the project site clearly marked.
- ☐ Attach photographs showing existing site conditions (unless not required under standards).

Signature of Applicant: _____

John E. Dority, Chief Engineer

Date: _____

10/23/03

Keep the bottom copy as a record of permit. Send the form with attachments via certified mail to the Maine Dept. of Environmental Protection at the appropriate regional office listed below. The DEP will send a copy to the Town Office as evidence of the DEP's receipt of notification. No further authorization by DEP will be issued after receipt of notice. Permits are valid for two years. **Work carried out in violation of any standard is subject to enforcement action.**

AUGUSTA DEP STATE HOUSE STATION 17 AUGUSTA, ME 04333-0017 (207)287-2111 PORTLAND DEP 312
CANCO ROAD PORTLAND, ME 04103 (207)822-6300 BANGOR DEP 106 HOGAN ROAD BANGOR, ME
04401 (207)941-4570 PRESQUE ISLE DEP 1235 CENTRAL DRIVE PRESQUE ISLE, ME 04769 (207)764-0477

OFFICE USE ONLY
PBR # FP

Ck.#

Date

Staff

Acc. Date

Staff

Def. Date

After Photos



REPLY TO
ATTENTION OF

DEPARTMENT OF THE ARMY
NEW ENGLAND DISTRICT, CORPS OF ENGINEERS
696 VIRGINIA ROAD
CONCORD, MASSACHUSETTS 01742-2751

MAINE PROGRAMMATIC GENERAL PERMIT (PGP)
AUTHORIZATION LETTER AND SCREENING SUMMARY

OFFICE OF ENVIRONMENTAL SERVICES
MAINE DEPT. OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333

CORPS PERMIT # NAE-2004-838
CORPS PGP ID# _____
STATE ID# PBR

DESCRIPTION OF WORK:

Place fill below the ordinary high water line of the West Branch of the Wesserunsett Stream and other unnamed streams and adjacent freshwater wetlands off Route 150 between Athens/Cornville and Harmony/Cambridge, Maine in order to reconstruct two sections of the roadway. Approximately 6334 s.f. (0.14 acres) of stream bottom and wetland will be impacted by the project.

PIN # 11214.00

LAT/LONG COORDINATES : 44.9169333° N 70.6854567° W USGS QUAD: ATHENS, ME

I. CORPS DETERMINATION:

Based on our review of the information you provided, we have determined that your project will have only minimal individual and cumulative impacts on waters and wetlands of the United States. Your work is therefore authorized by the U.S. Army Corps of Engineers under the enclosed Federal Permit, the Maine Programmatic General Permit (PGP).

You must perform the activity authorized herein in compliance with all the terms and conditions of the PGP [including any attached Additional Special Conditions and any conditions placed on the State 401 Water Quality Certification including any required mitigation]. Please review the enclosed PGP carefully, including the PGP conditions beginning on page 5, to familiarize yourself with its contents. You are responsible for complying with all of the PGP requirements; therefore you should be certain that whoever does the work fully understands all of the conditions. You may wish to discuss the conditions of this authorization with your contractor to ensure the contractor can accomplish the work in a manner that conforms to all requirements.

If you change the plans or construction methods for work within our jurisdiction, please contact us immediately to discuss modification of this authorization. This office must approve any changes before you undertake them.

Condition 36 of the PGP (page 12) provides one year for completion of work that has commenced or is under contract to commence prior to the expiration of the PGP on September 29, 2005. You will need to apply for reauthorization for any work within Corps jurisdiction that is not completed by September 29, 2006.

No work may be started unless and until all other required local, State and Federal licenses and permits have been obtained. **This includes but is not limited to a Flood Hazard Development Permit issued by the town if necessary.** Also, this permit requires you to notify us before beginning work and allow us to inspect the project. Hence, you must complete and return the attached Work Start Notification Form(s) to this office no later than 2 weeks before the anticipated starting date. (For projects requiring mitigation, be sure to include the MITIGATION WORK START FORM).

II. STATE ACTIONS: PENDING [☒], ISSUED [☐], DENIED [☐] DATE _____

APPLICATION TYPE: PBR: ☒ TIER 1: ☐ TIER 2: ☐ TIER 3: ☐ LURC: ☐ DMR LEASE: ☐ NA: ☐

III. FEDERAL ACTIONS:

JOINT PROCESSING MEETING: 4/29/04 LEVEL OF REVIEW: CATEGORY 1: ☒ CATEGORY 2: ☐

AUTHORITY: SEC 10 ☐ 404 ☒ 10/404 ☐ 103 ☐

EXCLUSIONS: The exclusionary criteria identified in the general permit do not apply to this project.

ESSENTIAL FISH HABITAT (EFH): EFH PRESENT Y/N (CIRCLE ONE)

IF YES: Based on the terms and conditions of the PGP, which are intended to ensure that authorized projects cause no more than minimal environmental impacts, the Corps of Engineers has preliminary determined that this project will not cause more than minimal adverse effects to EFH identified under the Magnuson-Stevens Fisheries Conservation and Management Act.

FEDERAL RESOURCE AGENCY OBJECTIONS: EPA NO USF&WS NO NMFS NO

If you have any questions on this matter, please contact my staff at 207-623-8367 at our Manchester, Maine Project Office.

Jay L. Clement
JAY L. CLEMENT
SENIOR PROJECT MANAGER
MAINE PROJECT OFFICE

Frank J. DelGiudice 5/7/04
FRANK J. DELGIUDICE DATE
ACTING CHIEF, PERMITS & ENFORCEMENT BRANCH
REGULATORY DIVISION



US Army Corps
of Engineers®
New England District

DEPARTMENT OF THE ARMY
NEW ENGLAND DISTRICT
ADDENDUM NO. 1
NAME OF PROJECT
ADDRESS
CITY
STATE
ZIP
DATE
NO. NAE-2004-838

1. Adequate sedimentation and erosion control devices, such as geotextile silt fences or other devices capable of filtering the fines involved, shall be installed and properly maintained to minimize impacts during construction. These devices must be removed upon completion of work and stabilization of disturbed areas. The sediment collected by these devices must also be removed and placed upland, in a manner that will prevent its later erosion and transport to a waterway or wetland.
2. All exposed soils resulting from the construction will be promptly seeded and mulched in order to achieve vegetative stabilization.
3. The permittee shall assure that a copy of this permit is at the work site whenever work is being performed and that all personnel performing work at the site of the work authorized by this permit are fully aware of the terms and conditions of the permit. This permit, including its drawings and any appendices and other attachments, shall be made a part of any and all contracts and sub-contracts for work which affects areas of Corps of Engineers' jurisdiction at the site of the work authorized by this permit. This shall be done by including the entire permit in the specifications for the work. If the permit is issued after construction specifications but before receipt of bids or quotes, the entire permit shall be included as an addendum to the specifications. The term "entire permit" includes permit amendments. Although the permittee may assign various aspects of the work to different contractors or sub-contractors, all contractors and sub-contractors shall be obligated by contract to comply with all environmental protection provisions of the entire permit, and no contract or sub-contract shall require or allow unauthorized work in areas of Corps of Engineers jurisdiction.
4. Replacement culverts shall be installed with their inverts at or below existing stream bed grade so as to avoid "hanging" and associated impediments to fish passage.
5. Instream work shall occur from July 15 to October 1 to protect fisheries and local water quality.



United States Department of the Interior

FISH AND WILDLIFE SERVICE

Maine Field Office
1168 Main Street
Old Town, ME 04468-2023
(207) 827-5938



In Reply Refer To:
FWS/Region 5/ES/MEFO

May 10, 2004

Mr. Richard Bostwick
MDOT - Environmental Office
16 State House Station
Augusta, ME 04333-0016

Dear Mr. Bostwick:

Thank you for your letter requesting information or recommendations from the U.S. Fish and Wildlife Service. This letter provides the Service's response pursuant to Section 7 of the Endangered Species Act (ESA), as amended (16 U.S.C. 1531-1543), and the Fish and Wildlife Coordination Act, as amended (16 U.S.C. 661-667d).

Project Name/Location/County: MDOT, Dexter PIN 11340 Eagle nest Route 7

Date of Receipt of Incoming Letter: April 12, 2004


Log Number: 04-249

We have reviewed your request for information about endangered and threatened species and their habitats for the above referenced project. As you have indicated, the federally threatened bald eagle (*Haliaeetus leucocephalus*) is known to occur at this location, ¼ mile from the project. Based on the project description (paving to be done at any time of the year, location ¼ mile or greater from the eagle nest, screening by vegetation, and behavior of this particular pair of eagles) the Fish and Wildlife Service concurs with your determination that the project is not likely to adversely affect bald eagles. Accordingly, no further action is required under Section 7 of the ESA, unless: (1) new information reveals impacts of this identified action that may affect listed species or critical habitat in a manner not previously considered; (2) this action is subsequently modified in a manner that was not considered in this review; or (3) a new species is listed or critical habitat determined that may be affected by the identified action.

A list of federally-listed species in Maine is enclosed for your information. Please contact the Maine Department of Inland Fisheries (Beth Swartz, Natural Heritage Data Manager, Maine Inland Fisheries and Wildlife, 650 State St., Bangor, ME 04401 Phone: 207 941-4476) and Wildlife and Maine Natural Areas Program (Emily Pinkham, Natural Heritage Data Manager, Maine Natural Areas Program, 93 State House Station, Augusta, ME 04333 207 287-8044) for further information on state-listed species in the project area.

If you have any questions, please call me at (207) 827-5938.

Sincerely,

A handwritten signature in cursive script that reads "Mark A. McCollough". The signature is written in dark ink and is positioned above the printed name.

Mark A. McCollough,
Endangered Species Biologist

Enclosure



JOHN ELIAS BALDACCI
GOVERNOR

STATE OF MAINE
DEPARTMENT OF
INLAND FISHERIES AND WILDLIFE
284 STATE STREET
41 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0041

ROLAND D. MARTIN
COMMISSIONER

April 15, 2004

John E. Dority, Chief Engineer
Maine Department of Transportation
16 State House Station
Augusta, ME 04333

Ref: Essential Habitat Evaluation; BE 275B, Dexter
MDOT PIN 11340.00


Dear Mr. Dority,

This Department has received a Request for Project Evaluation from the Maine Department of Transportation (MDOT) for permission to undertake a Pavement Preservation Management project on Route 2 within the Town of Dexter, Penobscot County, including a section within Essential Habitat BE 275B, as designated by Maine Statute 12 MRSA, Section 7754.2. This project will involve overlay of approximately $\frac{3}{4}$ inch of pavement to be placed on existing pavement. Project work within the Essential Habitat is proposed to start after August 15, and be completed within one to two days.

Upon review of the information provided by the applicant, my staff has recommended, and I agree, that the proposed activities will not significantly alter this Essential Habitat or violate the protection guidelines adopted by this Department (Chapter 8.03 A.4) in conformance with Maine Statute 12 MRSA, Section 7754.3. Therefore this letter constitutes our approval for you to undertake the proposed activity for the work specifically described in the request.

A March 23, 2004, nest survey indicated this nest site was currently active. If nesting were successful then fledging would be expected to occur no later than July 15. Based upon this information, and specific to this location, type of project and for the (2004) nesting season only, it would be acceptable to us for MDOT to start work within the Essential Habitat any time after July 15. Please re-initiate consultation with MDIFW if the project is not undertaken in 2004 and is rescheduled

Sincerely,




Kenneth D. Elowe, Director
Bureau of Resource Management

cc: David Gardner, Supervisor, Permits & Cultural Resources, MDOT
James Connolly, MDIFW Regional Headquarters
Charles Todd, MDIFW Resource Assessment



PRINTED ON RECYCLED PAPER

FISH AND WILDLIFE ON THE WEB: www.mefishwildlife.com
EMAIL ADDRESS - ifw.webmaster@maine.gov



0.25 0 0.25 0.5 0.75 1 Miles



ESSENTIAL HABITAT FOR ENDANGERED AND THREATENED SPECIES

DEPARTMENT OF INLAND FISHERIES AND WILDLIFE, Augusta, Maine 04333



MAP LEGEND

BE 000A Bald Eagle (BE) Nest Site No. 000A

All boundaries are shown as a solid circular line (O) and the inside of the line is the edge of the boundary. Each circle has a radius of approximately 1,320 feet and a center located approximately on the nest. The line on the map determines the boundary. The area within each circle is approximately 126 acres.

For a complete description of Essential Habitat and regulations pertaining thereto, refer to Chapter 8.05 of the Department Regulations and 12 M.S.R.A., Chapter 713, Subchapter V.

This map of Essential Habitat For Endangered and Threatened Species is adopted by the Department of Inland Fisheries and Wildlife on March 28, 2002.

This map is certified to be a true and correct copy of the official map of Essential Habitat For Endangered and Threatened Species by the Department of Inland Fisheries and Wildlife.

By:

Al E. Farley

Commissioner
Department of Inland Fisheries and Wildlife
This 7th day of May 2002.

Authority: 12 M.R.S.A., Section 7754(2)

Effective Date: May 31, 2002

Chapter 305: PERMIT BY RULE Section 11
State Transportation Facilities

- 1. Introduction.** A "permit by rule" or "PBR", when approved by the Department of Environmental Protection (DEP), is an approval for an activity that requires a permit under the Natural Resources Protection Act (NRPA). Only those activities described in this chapter may proceed under the PBR process. A PBR activity will not significantly affect the environment if carried out in accordance with this chapter, and generally has less of an impact on the environment than an activity requiring an individual permit. A PBR satisfies the Natural Resources Protection Act (NRPA) permit requirement and Water Quality Certification requirement.

If a proposed activity is not described in this chapter, or will not be conducted in accordance with the standards of this chapter, the applicant must obtain an individual permit prior to beginning the activity.

- A. Location of activity.** The location of an activity may affect whether an activity qualifies for PBR, and whether review by the Department of Inland Fisheries and Wildlife is required.

- (1) Type of resource. For some types of activities, the availability of a PBR is affected by the type of natural resource in or adjacent to which the activity is proposed. For example, an applicant proposing an activity consisting of "Movement of rocks or vegetation" may receive a PBR only if the activity will take place in a great pond, river, stream or brook. Limitations concerning the location of activities are addressed in the "Applicability" provision in each section of this chapter.
- (2) Essential habitat. Essential habitats include areas critical to the survival of threatened and endangered species such as the bald eagle, least tern, roseate tern, and piping plover. If the activity is located in essential habitat, such as near an eagle nesting site, a PBR is only available if the applicant obtains written approval from the Department of Inland Fisheries and Wildlife (IF&W). This approval from IF&W must be submitted to the DEP with the PBR notification form, and the applicant must follow any conditions stated in the IF&W approval.

NOTE: Maps showing areas of essential habitat are available from the Department of Inland Fisheries and Wildlife regional headquarters, municipal offices, the Land Use Regulation Commission (for unorganized territories) and DEP regional offices. If the activity is located in essential habitat, IF&W must be contacted to request and obtain a "certification of review and approval".

- B. Notification.** The applicant must file notice of the activity with the DEP prior to beginning work on the activity. The notification must be on a form provided by the DEP and must include any submissions required in this chapter. The applicant must keep a copy to serve as the permit.

The notification form must be sent to the DEP by certified mail (return receipt requested), or hand delivered to the DEP and date stamped by the department.

C. Effective period

- (1) Beginning of period. The PBR becomes effective 14 calendar days after the DEP receives the notification form, unless the DEP approves or denies the PBR prior to that date. If the DEP does not speak with or write to the applicant within this 14 day period regarding the PBR notification, the applicant may proceed to carry out the activity.

There are three exceptions regarding the effective date of an approved PBR:

- (a) Activities listed in Section 10 (Stream crossings) occurring in association with forest management are exempt from the 14 day waiting period.
- (b) Activities listed in Section 2 (Soil disturbance) and Section 10 (Stream crossings) performed or supervised by individuals currently certified in erosion control practices by the DEP are exempt from the 14 day waiting period. To be certified in erosion control practices, an individual must successfully complete all course requirements of the Voluntary Contractor Certification Program administered by the DEP's Nonpoint Source Training and Resource Center.
- (c) Activities that are part of a larger project requiring a permit under the Site Location of Development or the Storm Water Management Acts may not proceed until any required permit under those laws is obtained.

NOTE: Activities that are part of a larger project may require other permits from the DEP also. These other laws may prohibit the start of construction of any part of the project unless a permit under that law is obtained. In these cases, while not a violation of this rule, starting work on a PBR approved activity would be a violation of those other applicable laws.

- (2) End of period. The PBR is generally effective for 2 years from the date of approval, except that a PBR for "Replacement of structures" under Section 4 is effective for 3 years.

NOTE: Activities that qualify under this chapter may need to meet other local, state and federal requirements. Examples -- (1) If an activity extends below the low water line of a lake, coastal wetland or international boundary water, the applicant should contact the Bureau of Parks and Lands (287-3061) concerning possible lease or easement requirements, or (2) If an activity will involve work below the mean high water line in navigable waters of the United States, the applicant should contact the Army Corps of Engineers (623-8367).

D. Discretionary authority. Notwithstanding compliance with the PBR applicability requirements and standards set forth in this chapter, the DEP may require an individual permit application to be filed in any case where credible evidence indicates that the activity:

- (1) May violate the standards of the NRPA (38 M.R.S.A. Section 480-D);
- (2) Could lead to significant environmental impacts, including cumulative impacts; or
- (3) Could adversely impact a resource of special concern.

If an individual permit is required pursuant to this subsection, the DEP shall notify the applicant in writing within the 14 calendar day waiting period described in sub-section (C) above. When the DEP notifies an applicant that an individual permit is required, no work may be conducted unless and until the individual permit is obtained.

E. Violations. A violation of law occurs when a person, or his or her agent, performs or causes to be performed any activity subject to the NRPA without first obtaining a permit from the DEP, or acts contrary to the provisions of a permit. The person, his or her agent, or both, may be held

responsible for the violation. Commonly, the "person" is the landowner, and the "agent" is the contractor carrying out the activity. A violation occurs when:

- (1) An activity occurs that is not allowed under PBR, whether or not a PBR notification form has been filed with and/or approved by the DEP;
- (2) An activity occurs that is allowed under PBR, but a PBR for the activity has not become effective prior to the beginning of the activity; or
- (3) An activity occurs that is allowed under PBR and a PBR for the activity is in effect, but the standards specified in this chapter are not met.

See the "applicability" provision under each activity for rules concerning what activities are allowed under PBR. A PBR is only valid for the person listed on the notification form, or for his or her agent.

Each day that a violation occurs or continues is considered a separate offense. Violations are subject to criminal penalties and civil penalties of not less than \$100 nor more than \$10,000 for each day of that violation (38 M.R.S.A. Section 349).

NOTE: A local Code Enforcement Officer (CEO) may take enforcement action for a violation of the Natural Resources Protection Act if he or she is authorized to represent a municipality in District Court, and he or she has been certified as familiar with court procedures, 30-A M.R.S.A. Section 4452(7).

Chapter 305 Section 11**State transportation facilities****A. Applicability**

- (1) This section applies to the maintenance, repair, reconstruction, rehabilitation, replacement or minor construction of a State Transportation Facility carried out by, or under the authority of, the Maine Department of Transportation or the Maine Turnpike Authority, including any testing or preconstruction engineering, and associated technical support services.
- (2) This section does not apply to an activity within a coastal sand dune system.

NOTE: The construction of a transportation facility other than roads and associated facilities may be subject to the Storm Water Management Law, 38 M.R.S.A. Section 420-D.

B. Standards

- (1) Photographs of the area to be altered by the activity must be taken before work on the site begins. The photographs must be kept on file and be made available at the request of the DEP.
- (2) The activity must be reviewed by the Department of Inland Fisheries and Wildlife, the Department of Marine Resources, the Atlantic Salmon Authority, and the DEP's Division of Environmental Assessment prior to the notification being filed with the DEP. The activity must be performed according to any recommendations from these authorities.
- (3) The activity must be performed in accordance with erosion control measures conforming with the State of Maine Department of Transportation Standard Specifications for Highways and Bridges Revision of April 1995 and with the Department of Transportation's Best Management Practices for Erosion and Sediment Control, September 1997.

NOTE: Guidance on the use of erosion control best management practices can be obtained from the on site Construction Manager.

- (4) Alignment changes may not exceed a distance of 200 feet between the old and new center lines in any natural resource.
- (5) The activity may not alter more than 300 feet of shoreline (both shores added together) within a mile stretch of any river, stream or brook, including any bridge width or length of culvert.
- (6) The activity may not alter more than 150 feet of shoreline (both shores added together) within a mile stretch of any outstanding river segment identified in 38 M.R.S.A. 480-P, including any bridge width or length of culvert.
- (7) The activity must minimize wetland intrusion. The activity is exempt from the provisions of Chapter 310, the Wetland Protection Rules, if the activity alters less than 15,000 square feet of natural resources per mile of roadway (centerline measurement) provided that the following impacts are not exceeded within the 15,000 square foot area:

- (a) 1,000 square feet of coastal wetland consisting of salt tolerant vegetation or shellfish habitat; or
- (b) 5,000 square feet of coastal wetland not containing salt tolerant vegetation or shellfish habitat; or
- (c) 1,000 square feet of a great pond.

All other activities must be performed in compliance with all sections of Chapter 310, the Wetland Protection Rules, except 310.2(C), 5(A), 9(1), 9(B) and 9(C).

- (8) The activity may not permanently block any fish passage in any watercourse containing fish. The applicant must improve passage beyond what restriction may already exist unless the Department of Inland Fisheries and Wildlife, the Department of Marine Resources, the Atlantic Salmon Authority and the DEP's Division of Environmental Assessment concur that the improvement is not necessary.
- (9) Rocks may not be removed from below the normal high water line of any coastal wetland, freshwater wetland, great pond, river, stream or brook except to the minimum extent necessary for completion of work within the limits of construction.
- (10) If work is performed in a river, stream or brook that is less than three feet deep at the time and location of the activity, with the exception of culvert installation, the applicant must divert flow away from the activity while work is in progress.
 - (a) Diversion may be accomplished by the use of stable, inert material. No more than two thirds (2/3) of stream width may be diverted at one time.
 - (b) Any material used to divert water flow must be completely removed upon completion of the activity, and the stream bottom must be restored to its original condition.
 - (c) A pump may be operated, where necessary, for a temporary diversion. The pump outlet must be located and operated such that erosion or the discharge of sediment to the water is prevented.

NOTE: Guidance on the appropriate location of a diversion and materials which should be used for a stream diversion can be obtained from the on site Construction Manager.

- (11) Wheeled or tracked equipment may not operate in the water. Equipment operating on the shore may reach into the water with a bucket or similar extension. Equipment may cross streams on rock, gravel or ledge bottom.
- (12) All wheeled or tracked equipment that must travel or work in a vegetated wetland area must travel and work on mats or platforms.
- (13) Any debris or excavated material must be stockpiled either outside the wetland or on mats or platforms. Hay bales or silt fence must be used, where necessary, to prevent sedimentation. Any debris generated during the activity must be prevented from washing downstream and must be removed from the wetland or water body. Disposal of debris must be in conformance with the Maine Hazardous Waste, Septage and Solid Waste Management Act, 38 M.R.S.A. Section 1301 et seq.

- (14) Work below the normal high water line of a great pond, river, stream or brook must be done at low water except for emergency work or work agreed to by the resource agencies listed in paragraph 2 above. Measures, such as a silt boom or staked fencing, must be employed to reduce and isolate turbidity.
- (15) Perimeter controls must be installed before the work starts. Disturbance of natural resources beyond the construction limits shown on the plans is not allowed under this rule.

NOTE: Guidance on the location of construction limits can be obtained from the on site Construction Manager.

- (16) The use of untreated lumber is preferred. Lumber pressure treated with chromated copper arsenate (CCA) may be used, provided it is cured on dry land in a manner that exposes all surfaces to the air for a period of at least 21 days prior to construction. Wood treated with creosote or pentachlorophenol may not be used where it will contact water.
- (17) A temporary road for equipment access must be constructed of crushed stone, blasted ledge, or similar materials that will not cause sedimentation or restrict fish passage. Such roads must be completely removed at the completion of the activity. In addition, any such temporary roads which are in rivers, streams or brooks, must allow for a passage of stormwater flows associated with a 10-year storm.
- (18) Soil may not be disturbed during any period when soils are saturated due to rain or snow melt, except as necessary to protect work in progress or as required for bridge maintenance activities. Areas where soils are saturated (i.e. water drips from the soil when squeezed by hand, or the soil is capable of being rolled into a rod 1/8th inch in diameter that does not crumble) must be immediately mulched if they are disturbed.
- (19) Disturbed soil must be protected within one week from the time it was last actively worked, and prior to any storm event, using temporary or permanent measures such as the placement of riprap, sod, mulch, erosion control blankets, or other comparable measures.
- (20) Hay bale or straw mulch, where used, must be applied at a rate of at least one bale per 500 square feet (1 to 2 tons per acre).
- (21) If mulch is likely to be moved because of steep slopes or wind exposure, it must be anchored with netting, peg and twine, binder or other suitable method and must be maintained until a catch of vegetation is established over the entire disturbed area.
- (22) In addition to the placement of riprap, sod, erosion control blankets or mulch, additional steps must be taken where necessary to prevent sedimentation of the water. Evidence of sedimentation includes visible sheet, rill or gully erosion, discoloration of water by suspended particles and/or slumping of banks. Silt fences, staked hay bales and other sedimentation control measures, where planned for, must be in place prior to the commencement of an activity, but must also be installed whenever necessary to prevent erosion and sedimentation.

NOTE: Guidance on the location and proper installation of erosion control measures can be obtained from the on site Construction Manager.

- (23) Temporary erosion control measures must be maintained and inspected weekly until the site is permanently stabilized with vegetation or other permanent control measures. Erosion control measures must also be inspected immediately prior to and following storms.
- (24) Permanent erosion control measures protecting all disturbed areas must be implemented within 30 days from the time the areas were last actively worked, or for fall and winter activities by the following June 15, except where precluded by the type of activity (e.g. riprap, road surfaces, etc.). The permanent erosion control measures must be maintained.
- (25) The applicant shall immediately take appropriate measures to prevent erosion or sedimentation from occurring or to correct any existing problems, regardless of the time of year.
- (26) Non-native species may not be planted in restored areas.
- (27) Disposal of debris must be in conformance with Maine Hazardous Waste, Septage and Solid Waste Management Act, 38 M.R.S.A. Sections 1301 et seq.
- (28) Disturbance of vegetation must be avoided, if possible. Where vegetation is disturbed outside of the area covered by any road or structure construction, it must be reestablished immediately upon completion of the activity and must be maintained.
- (29) A vegetated area at least 25 feet wide must be established and maintained between any new stormwater outfall structure and the high water line of any open water body. A velocity reducing structure must be constructed at the outlet of the stormwater outfall that will create sheet flow of stormwater, and prevent erosion of soil within the vegetated buffer. If the 25 foot vegetated buffer is not practicable, the applicant must explain the reason for a lesser setback in writing. Approval from the DEP must be in writing and any recommendations must be incorporated into the activity.

C. Definitions. The following terms, as used in this chapter, have the following meanings, unless the context indicates otherwise:

- (1) Diversion. A rerouting of a river, stream or brook to a location outside of its established channel.
- (2) Fill. a. (verb) To put into or upon, supply to, or allow to enter a water body or wetland any earth, rock, gravel, sand, silt, clay, peat, or debris; b. (noun) Material, other than structures, placed in or immediately adjacent to a wetland or water body.
- (3) Floodplain wetlands. Freshwater wetlands that are inundated with flood water during a 100-year flood event based on flood insurance maps produced by the Federal Emergency Agency or other site specific information.
- (4) Riprap. Rocks that are fit into place, usually without mortar, on a slope as defined in the State of Maine, Department of Transportation, Standard Specifications for Highway and Bridges, revision of April 1995.

Permit No: GP-39

Effective Date: Sept. 29, 2000
Expiration Date: Sept. 29, 2005

Applicant: General Public, State of Maine

**DEPARTMENT OF THE ARMY
PROGRAMMATIC GENERAL PERMIT
STATE OF MAINE**

The New England District of the U.S. Army Corps of Engineers hereby issues a programmatic general permit (PGP) that expedites review of minimal impact work in coastal and inland waters and wetlands within the State of Maine. Activities with minimal impacts, as specified by the terms and conditions of this general permit and on the attached DEFINITION OF CATEGORIES sheets, are either non-reporting (provided required local and state permits are received), or are reporting, to be screened by the Corps and Federal Resource Agencies for applicability under the general permit. This general permit does not affect the Corps individual permit review process or activities exempt from Corps jurisdiction.

Activities Covered: work and structures that are located in, or that affect, navigable waters of the United States (regulated by the Corps under Section 10 of the Rivers and Harbors Act of 1899) and the discharge of dredged or fill material into waters of the United States (regulated by the Corps under Section 404 of the Clean Water Act), and the transportation of dredged material for the purpose of disposal in the ocean (regulated by the Corps under Section 103 of the Marine Protection, Research and Sanctuaries Act).

PROCEDURES:

A. State Approvals

For projects authorized pursuant to this general permit that are also regulated by the State of Maine, the following state approvals are also required and must be obtained in order for this general permit authorization to be valid (applicants are responsible for ensuring that all required state permits and approval have been obtained):

- (a) Maine Department of Environmental Protection (DEP): Natural Resources Protection Act permit, including permit-by-rule and general permit authorizations; Site Location and Development Act permit; and Maine Waterway Development and Conservation Act.
- (b) Maine Department of Conservation: Land Use Regulation Commission (LURC) permit.
- (c) Maine Department of Marine Resources: Lease.
- (d) Bureau of Public Lands, Submerged Lands: Lease.

Note that projects not regulated by the State of Maine (e.g., seasonal floats or moorings) may still be authorized by this general permit.

B. Corps Authorizations: Category I (Non-Reporting)

Work in Maine subject to Corps jurisdiction that meets the definition of Category I on the attached DEFINITION OF CATEGORIES sheets and that meets all of this permit's other conditions, does not require separate application to the Corps of Engineers. If the State or the Corps does not contact the applicant for PBRs and Tier One permits during the State's Tier One 30-day review period, Corps approval may be assumed and the project may proceed. Refer to the Procedures Section at Paragraph E below for additional information regarding screening.

Note that the review thresholds under Category I apply to single and complete projects i only (see special condition 5). **Also note that Category I does not apply to projects occurring in a component of, or within 0.25 miles up and downstream of the main stem or tributaries of a river segment of the National Wild and Scenic River System** (see condition 11, and page 9 for the listed rivers in Maine).

There are also restrictions on other national lands or concerns, which must be met in order for projects to be eligible for authorization under this PGP. Refer to special conditions 6-13 under Paragraph F below.

Work that is not regulated by the State of Maine, but that is subject to Corps jurisdiction, is eligible for Corps authorization under this PGP in accordance with the review thresholds and conditions contained herein.

Although Category I projects are non-reporting, the Corps reserves the right to require screening or an individual permit review if there are concerns for the aquatic environment or any other factor of the public interest (see special condition 4 on Discretionary Authority). The Corps review or State/Federal screening process may also result in project modification, mitigation or other special conditions necessary to minimize impacts and protect the aquatic environment as a requirement for PGP approval.

C. Corps Authorization: Category II (Reporting - requiring screening) **APPLICATION PROCEDURES**

For projects that do not meet the terms of Category I (see DEFINITION OF CATEGORIES sheets), the Corps, State, and Federal Resource Agencies will conduct joint screening meetings to review applications. If projects are concurrently regulated by the DEP or LURC, applicants do not need to submit separate applications to the Corps. For projects not regulated by DEP or LURC, applicants must submit an application to the Corps Maine Project Office for a case-by-case determination of eligibility under this general permit (Category II). **Category II projects may not proceed until written notification is received from the Corps.**

Category II projects which occur in a component of, or within 0.25 mile up or downstream of the main stem or tributaries of a river segment of the National Wild and Scenic River System, will be coordinated with the National Park Service (see special condition 11, and page 9 for listed rivers in Maine).

There are also restrictions on other national lands or concerns, which must be met in order for projects to be eligible for authorization under this PGP. Refer to special conditions 6-14 under Paragraph E below.

Category II applicants shall submit a copy of their application materials to the Maine Historic Preservation Commission and/or applicable Indian tribe(s) at the same time, or before, they apply to the DEP, LURC, or the Corps so that the project can be reviewed for the presence of historic/archaeological resources in the project area that may be affected by the proposed work. **Applications to the DEP or the Corps should include information to indicate that this has been done (applicant's statement or copy of cover letter to Maine Historic Preservation Commission and/or Indian tribe(s)).**

The Corps may require additional information on a case-by-case basis as follows:

- (a) purpose of project;
- (b) 8 1/2" by 11" plan views of the entire property including property lines and project limits with existing and proposed conditions **(legible, reproducible plans required)**;
- (c) wetland delineation for the site, information on the basis of the delineation, and calculations of waterway and wetland impact areas (see special condition 2);
- (d) typical cross-section views of all wetland and waterway fill areas and wetland replication areas;
- (e) delineation of submerged aquatic vegetation, e.g., eel grass beds, in tidal waters;
- (f) area, type and source of fill material to be discharged into waters and wetlands, including the volume of fill below ordinary high water in inland waters and below the high tide line in coastal waters;
- (g) mean low, mean high water and high tide elevations in navigable waters;
- (h) limits of any Federal navigation project in the vicinity and State Plane coordinates for the limits of the proposed work closest to the Federal project;
- (i) on-site alternatives analysis (contact Corps for guidance);
- (j) identify and describe potential impacts to Essential Fish Habitat (contact Corps for guidance);
- (k) for dredging projects, include:
 - 1) the volume of material and area in square feet to be dredged below mean high water,
 - 2) existing and proposed water depths,
 - 3) type of dredging equipment to be used,
 - 4) nature of material (e.g., silty sand),

- 5) any existing sediment grain size and bulk sediment chemistry data for the proposed or any nearby projects,
- 6) information on the location and nature of municipal or industrial discharges and occurrences of any contaminant spills in or near the project area,
- 7) location of the disposal site (include locus sheet),
- 8) shellfish survey, and
- 9) sediment testing, including physical, chemical and biological testing. For projects proposing open water disposal, applicants are encouraged to contact the Corps as early as possible regarding sampling and testing protocols.

The Corps may request additional information. Dredging applicants may be required to conduct a shellfish and/or eel grass survey and sediment testing, including physical, chemical and biological testing. Sediment sampling and testing plans should be prepared or approved by the Corps before the samples are collected.

STATE-FEDERAL SCREENING PROCEDURES:

The Corps intends to utilize the application information required by the State for its regulatory program to the maximum extent practicable and the Corps normally will not be interacting with an applicant who is concurrently making application to the DEP or LURC. Projects not regulated by the State, but needing Corps of Engineers approval, **must apply directly to the Corps**. The joint screening meeting for Category II projects will occur regularly at the Corps or State of fices and will involve representatives from the DEP, the Corps, the U.S. Environmental Protection Agency, the U.S. Fish and Wildlife Service, and the National Marine Fisheries Service.

The Corps and Federal Resource Agencies will classify the project within the State's review period, not to exceed 60 days, as: 1) approvable under the PGP as proposed; 2) needs additional information, including possible project modification, mitigation or other special conditions to minimize impacts; or 3) exceeds the terms or conditions of the PGP, including the minimal effects requirement, and an individual permit review will be required. In addition, the Corps retains the ability to exercise its discretionary authority and require an individual permit, irrespective of whether the terms and conditions of this general permit are met, based on concerns for the aquatic environment or any factor of the public interest (see special condition 4 on Discretionary Authority). All Category II projects must receive written approval from the Corps before work can proceed. If the project is not approvable as proposed, the DEP, LURC, or the Corps will contact the applicant to discuss the concerns raised. If the applicant is unable to resolve the concerns, the Corps, independently or at the request of the Federal Resource Agencies, will require an individual permit for the project. The applicant will be notified of this in writing, along with information about submitting the necessary application materials. The comments from the Federal Resource Agencies to the Corps may be verbal initially, and must be made within 10 working days of the screening meeting. These comments must be confirmed in writing within 10 calendar days of the verbal response if the Resource Agency(ies) will request an individual permit. The Federal Resource Agency's comments must reflect a concern within their area of expertise, state the species or resources that could be impacted by the project, and describe the impacts that either individually or cumulatively will be more than minimal.

MINERALS MANAGEMENT SERVICE (MMS) REVIEW

For Category II projects which involve construction of solid fill structures or discharge of fills along the coast which may extend the coastline or baseline from which the territorial sea is measured, coordination between the Corps and Minerals Management Service (MMS), Continental Shelf (OCS) Survey Group, will be needed (pursuant to the Submerged Lands Act, 43 U.S.C., Section 1301-1315, 33 CFR 320.4(f)). During the screening period, the Corps will forward project information to MMS for their review. MMS will coordinate their determination with the Department of the Interior (DOI) Solicitor's Office. The DOI will have 15 calendar days from the date MMS is in receipt of project information to determine if the baseline will be affected. No notification to the Corps within 15 day review period will constitute a "no affect" determination. Otherwise, the solicitor's notification to the Corps may be verbal but must be followed with a written confirmation within 10 business days from the date of the verbal notification. This procedure will be eliminated if the State of Maine provides a written waiver of interest in any increase in submerged lands caused by a change in the baseline resulting from solid fill structure or fills authorized under this general permit.

D. Corps Authorization: Category III (Individual Permit)

Work that is in the INDIVIDUAL PERMIT category on the attached DEFINITION OF CATEGORIES sheets, or that does not meet the terms and conditions of this general permit, will require an application for an individual permit from the Corps of Engineers (see 33 CFR Part 325.1). The screening procedures outlined above will only serve to delay project review in such cases. The applicant should submit the appropriate application materials (including the Corps application form) at the earliest possible date. General information and application forms can be obtained at (207) 623-8367 (Maine Field Office), (800) 343-4789, or (800) 362-4367 in Massachusetts. Individual water quality certification and coastal zone management consistency concurrence will be required from the State of Maine before Corps permit issuance.

E. Programmatic General Permit Conditions:

The following conditions apply to activities authorized under the PGP, including all Category I (non-reporting) and Category II (reporting - requiring screening) activities:

GENERAL REQUIREMENTS:

1. **Other Permits.** Authorization under this general permit does not obviate the need to obtain other Federal, state, or local authorizations required by law.
2. **Applicability of this general permit shall be evaluated with reference to Federal jurisdictional boundaries.** Applicants are responsible for ensuring that the boundaries used satisfy the federal criteria defined at 33 CFR 328-329.
3. **Minimal Effects.** Projects authorized by this general permit shall have minimal individual and cumulative adverse environmental impacts as determined by the Corps.

4. **Discretionary Authority.** Notwithstanding compliance with the terms and conditions of this permit, the Corps of Engineers retains discretionary authority to require review for an individual permit based on concerns for the aquatic environment or for any other factor of the public interest. This authority is invoked on a case-by-case basis whenever the Corps determines that the potential consequences of the proposal warrant individual review based on the concerns stated above. This authority may be invoked for projects with cumulative environmental impacts that are more than minimal or if there is a special resource or concern associated with a particular project that is not already covered by the remaining conditions of the PGP and that warrants greater review.

Whenever the Corps notifies an applicant that an individual permit may be required, authorization under this general permit is void and no work may be conducted until the individual Corps permit is obtained or until the Corps notifies the applicant that further review has demonstrated that the work may proceed under this general permit.

5. **Single and Complete Projects.** This general permit shall not be used for piecemeal work and shall be applied to single and complete projects. All components of a single project and/or all planned phases of multi-phased projects shall be treated together as constituting one single and complete project (e.g., subdivisions should include all work such as roads, utilities, and lot development). This general permit shall not be used for any activity that is part of an overall project for which an individual permit is required.

NATIONAL CONCERNS:

6. **St. John/St. Croix Rivers.** This covers work within the Saint John and Saint Croix River basins that requires approval of the International Joint Commission. This includes any temporary or permanent use, obstruction or diversion of international boundary waters which could affect the natural flow or levels of waters on the Canadian side of the line, as well as any construction or maintenance of remedial works, protective works, dams, or other obstructions in waters downstream from boundary waters when the activity could raise the natural level of water on the Canadian side of the boundary.
7. **Historic Properties.** Any activity authorized by this general permit shall comply with Section 106 of the National Historic Preservation Act. Information on the location and existence of historic resources can be obtained from the Maine Historic Preservation Commission and the National Register of Historic Places. Federally recognized tribes (Penobscots, Passamaquoddys, Micmacs, and Maliseets) may know of the existence of other sites that may be of significance to their tribes. See page 14 for historic properties contacts.

Applicants with projects which will undergo the screening process (Category II) shall submit a copy of their application materials, with the name and address of the applicant clearly indicated, to the Maine Historic Preservation Commission, 55 Capitol Street, State House Station 65, Augusta, Maine 04333, and to the applicable tribe(s) to be reviewed for the presence of historic and/or archaeological resources in the permit area that may be affected by the proposed work. The Corps will then be notified by the Commission and/or

Tribe within 10 days if there are State and/or tribal concerns that the proposed work will have an effect on historic resources. The applicant should include with their application to the State or the Corps either a copy of their cover letter or a statement of having sent their application material to the Commission and Tribe(s).

If the permittee, either prior to construction or during construction of the work authorized herein, encounters a previously unidentified archaeological or other cultural resource, within the area subject to Department of the Army jurisdiction, that might be eligible for listing in the National Register of Historic Places, he/she shall stop work and immediately notify the District Engineer and the Maine Historic Preservation Commission and/or applicable Tribe(s).

8. **National Lands.** Activities authorized by this general permit shall not impinge upon the value of any National Wildlife Refuge, National Forest, or any area administered by the National Park Service.

9. **Endangered Species.** No activity is authorized under this general permit which

- may affect a threatened or endangered species or a species proposed for such designation as identified under the Federal Endangered Species Act (ESA),
- is likely to destroy or adversely modify the critical habitat or proposed critical habitat of such species,
- would result in a 'take' of any threatened or endangered species of fish or wildlife, or
- would result in any other violation of Section 9 of the ESA protecting threatened or endangered species of plants.

Applicants shall notify the Corps if any listed species or critical habitat, or proposed species or critical habitat, is in the vicinity of the project and shall not begin work until notified by the District Engineer that the requirements of the Endangered Species Act have been satisfied and that the activity is authorized. Information on the location of threatened and endangered species and their critical habitat can be obtained from the U.S. Fish and Wildlife Service and National Marine Fisheries Service (addresses attached, page 14).

10. **Essential Fish Habitat.** As part of the PGP screening process, the Corps will coordinate with the National Marine Fisheries Service (NMFS) in accordance with the 1996 amendments to the Magnuson-Stevens Fishery and Conservation Management Act to protect and conserve the habitat of marine, estuarine and anadromous finfish, mollusks, and crustaceans. This habitat is termed "essential fish habitat (EFH)", and is broadly defined to include "those waters and substrate necessary to fish for spawning, breeding, feeding, or growth to maturity." Applicants may be required to describe and identify potential impacts to EFH based upon the location of the project, the activity proposed, and the species present. Conservation recommendations made by NMFS will normally be included as a permit requirement by the Corps. Information on the location of EFH can be obtained from the NMFS regulations (50 CFR Part 600) (address listed on page 14) and on their web site (<http://www.nero.nmfs.gov/ro/doc/webintro.html>).

The EFH designation for Atlantic salmon includes all aquatic habitats in the watershed of the following rivers and streams, including all tributaries to the extent that they are currently or were historically accessible for salmon migration:

St. Croix River	Pleasant River	Union River
Boyden River	Narraguagus River	Ducktrap River
Dennys River	Tunk Stream	Sheepscot River
Hobart Stream	Patten Stream	Kennebec River
Aroostook River	Orland River	Androscoggin River
East Machias River	Penobscot River	Presumpscot River
Machias River	Passagassawaukeag River	Saco River

11. **Wild and Scenic Rivers.** Any activity that occurs in a component of, or within 0.25 mile up or downstream of the main stem or tributaries of a river segment of the National Wild and Scenic River System, **must be reviewed by the Corps under the procedures of Category II of this general permit regardless of size of impact.** This condition applies to both designated wild and scenic rivers and rivers designated by Congress as study rivers for possible inclusion while such rivers are in an official study status. The Corps will consult with the National Park Service (NPS) with regard to potential impacts of the proposed work on the resource values of the Wild and Scenic River. The culmination of this coordination will be a determination by the NPS and the Corps that the work: (1) may proceed as proposed; (2) may proceed with recommended conditions; or (3) could pose a direct and adverse effect on the resource values of the river and an individual permit is required. If pre-application consultation between the applicant and the NPS has occurred whereby the NPS has made a determination that the proposed project is appropriate for authorization under this PGP (with respect to wild and scenic river issues), this determination should be furnished to the Corps with submission of the application. The address of the NPS can be found on Page 14 of this permit. *National Wild/Scenic Rivers System (Designated River in Maine) as of 5/2/00:* Allagash River beginning at Telos Dam continuing to Allagash checkpoint at Eliza Hole Rapids, approximately 3 miles upstream of the confluence with the St. John River. Length = 92 miles

12. **Federal Navigation Project.** Any structure or work that extends closer to the horizontal limits of any Corps navigation project than a distance of three times the project's authorized depth (see attached map following page 16 for locations of these projects) shall be subject to removal at the owner's expense prior to any future Corps dredging or the performance of periodic hydrographic surveys.

13. **Navigation.** There shall be no unreasonable interference with navigation by the existence or use of the activity authorized herein and no attempt shall be made by the permittee to prevent the full and free use by the public of all navigable waters at or adjacent to the activity authorized herein.

The permittee understands and agrees that, if future operations by the United States require the removal, relocation, or other alteration, of the structure or work herein authorized, or if, in the opinion of the Secretary of the Army or his authorized representative, said structure

or work shall cause unreasonable obstruction to the free navigation of the navigable waters, the permittee will be required, upon due notice from the Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the United States. No claim shall be made against the United States on account of any such removal or alteration.

14. **Federal Liability.** In issuing this permit, the Federal Government does not assume any liability for the following: (a) damages to the permitted project or uses thereof as a result of other permitted or unpermitted activities or from natural causes; (b) damages to the permitted project or uses thereof as a result of current or future activities undertaken by or on behalf of the United States in the public interest; (c) damages to persons, property, or to other permitted or unpermitted activities or structures caused by the activity authorized by this permit; (d) design or construction deficiencies associated with the permitted work; (e) damage claims associated with any future modification, suspension, or revocation of this permit.

MINIMIZATION OF ENVIRONMENTAL IMPACTS:

15. **Minimization.** Discharges of dredged or fill material into waters of the United States shall be avoided and minimized to the maximum extent practicable, regardless of review category.
16. **Work in Wetlands.** Heavy equipment working in wetlands shall be avoided if possible, **and if required, shall be placed on mats or other measures taken** to minimize soil and vegetation disturbance. Disturbed areas in wetlands shall be restored to preconstruction contours and conditions upon completion of the work.
17. **Temporary Fill.** Temporary fill in waters and wetlands authorized by this general permit (e.g., access roads, cofferdams) shall be properly stabilized during use to prevent erosion. Temporary fill in wetlands shall be placed on geotextile fabric laid on existing wetland grade. Temporary fills shall be disposed of at an upland site, suitably contained to prevent erosion and transport to a waterway or wetland. Temporary fill areas shall be restored to their approximate original contours but not higher. No temporary fill shall be placed in waters or wetlands unless specifically authorized by the Corps.
18. **Sedimentation and Erosion Control.** Adequate sedimentation and erosion control management measures, practices and devices, such as phased construction, vegetated filter strips, geotextile silt fences or other devices, shall be installed and properly maintained to reduce erosion and retain sediment on-site during and after construction. They shall be capable of preventing erosion, of collecting sediment, suspended and floating materials, and of filtering fine sediment. These devices shall be removed upon completion of work and the disturbed areas shall be stabilized. The sediment collected by these devices shall be removed and placed at an upland location in a manner that will prevent its later erosion into a waterway or wetland. All exposed soil and other fills shall be permanently stabilized at the earliest practicable date.

19. **Waterway Crossings.**

- (a) All temporary and permanent crossings of waterbodies shall be suitably culverted, bridged, or otherwise designed to withstand and to prevent the restriction of high flows, to maintain existing low flows, and to not obstruct the movement of aquatic life indigenous to the waterbody beyond the actual duration of construction.
- (b) Temporary bridges, culverts, or cofferdams shall be used for equipment access across streams (NOTE: areas of fill and/or cofferdams must be included in total waterway/wetlands impacts to determine applicability of this general permit).
- (c) For projects that otherwise meet the terms of Category I, instream construction work shall be conducted during the low flow period July 15 - October 1 in any year. Projects that are not to be conducted during that time period are ineligible for Category I and shall be screened pursuant to Category II, regardless of the waterway and wetland fill and/or impact area.

20. **Discharge of Pollutants.** All activities involving any discharge of pollutants into waters of the United States authorized under this general permit shall be consistent with applicable water quality standards, effluent limitations, standards of performance, prohibitions, and pretreatment standards and management practices established pursuant to the Clean Water Act (33 U.S.C. 1251) and applicable state and local laws. If applicable water quality standards, limitations, etc., are revised or modified during the term of this permit, the authorized work shall be modified to conform with these standards within six months of the effective date of such revision or modification, or within a longer period of time deemed reasonable by the District Engineer in consultation with the Regional Administrator of the Environmental Protection Agency. Applicants may presume that state water quality standards are met with issuance of the 401 Water Quality Certification.

21. **Spawning Areas.** Discharges into known 1) fish and shellfish spawning or nursery areas; and 2) amphibian and waterfowl breeding areas, during spawning or breeding seasons shall be avoided, and impacts to these areas shall be avoided or minimized to the maximum extent practicable during all times of year.

22. **Storage of Seasonal Structures.** Coastal structures such as pier sections and floats that are removed from the waterway for a portion of the year shall be stored in an upland location located above mean high water and not in tidal marsh.

23. **Environmental Values.** The permittee shall make every reasonable effort to carry out the construction or operation of the work authorized herein in a manner so as to maintain as much as is practicable, and to minimize any adverse impacts on, existing fish and wildlife and natural environmental values.

24. **Protection of Vernal Pools.** Impacts to uplands in proximity (within 500 feet) to the vernal pools referenced in DEFINITIONS OF CATEGORIES shall be minimized to the maximum extent possible.

PROCEDURAL CONDITIONS:

25. **Cranberry Development Projects.** For Cranberry development projects authorized under the PGP, the following conditions apply:

4

1. If a cranberry bog is abandoned for any reason, the area must be allowed to convert to natural wetlands unless an individual permit is obtained from the Corps of Engineers allowing the discharge of fill for an alternate use.
2. No stream diversion shall be allowed under this permit.
3. No impoundment of perennial streams shall be allowed under this permit.
4. The project shall be designed and constructed to not cause flood damage on adjacent properties.

26. **Inspections.** The permittee shall permit the District Engineer or his authorized representative(s) to make periodic inspections at any time deemed necessary in order to ensure that the work is being performed in accordance with the terms and conditions of this permit. The District Engineer may also require post-construction engineering drawings for completed work, and post-dredging survey drawings for any dredging work. **To facilitate these inspections, the attached work notification form should be filled out and returned to the Corps for all Category II projects.**

27. **Maintenance.** The permittee shall maintain the work or structures authorized herein in good condition, including maintenance, to ensure public safety. Dredging projects: note that this does not include maintenance of dredging projects. Maintenance dredging is subject to the review thresholds described on the attached DEFINITION OF CATEGORIES sheets and/or any conditions included in a written Corps authorization.

28. **Property Rights.** This permit does not convey any property rights, either in real estate or material, or any exclusive privileges, nor does it authorize any injury to property or invasion of rights or any infringement of federal, state, or local laws or regulations. **If property associated with work authorized by the PGP is sold, the PGP authorization is automatically transferred to the new property owner. The new property owner should provide this information to the Corps in writing. No acknowledgement from the Corps is necessary.**

29. **Modification, Suspension, and Revocation.** This permit may be either modified, suspended, or revoked, in whole or in part, pursuant to the policies and procedures of 33 CFR 325.7 and any such action shall not be the basis for any claim for damages against the United States.

30. **Restoration.** The permittee, upon receipt of a notice of revocation of authorization under this permit, shall restore the wetland or waterway to its former condition without expense to the United States and as directed by the Secretary of the Army or his authorized representative. If the permittee fails to comply with such a directive, the Secretary or his designee may restore the wetland or waterway to its former condition, by contract or otherwise, and recover the cost from the permittee.

31. **Special Conditions.** The Corps, independently or at the request of the Federal Resource Agencies, may impose other special conditions on a project authorized pursuant to this general permit that are determined necessary to minimize adverse environmental effects or based on any other factor of the public interest. Failure to comply with all conditions of the authorization, including special conditions, will constitute a permit violation and may subject the permittee to criminal, civil, or administrative penalties or restoration.
32. **False or Incomplete Information.** If the Corps makes a determination regarding the eligibility of a project under this permit and subsequently discovers that it has relied on false, incomplete, or inaccurate information provided by the permittee, the permit shall not be valid and the government may institute appropriate legal proceedings.
33. **Abandonment.** If the permittee decides to abandon the activity authorized under this general permit, unless such abandonment is merely the transfer of property to a third party, he/she must restore the area to the satisfaction of the District Engineer.
34. **Enforcement cases.** This general permit does not apply to any existing or proposed activity in Corps jurisdiction associated with an on-going Corps of Engineers or Environmental Protection Agency enforcement action until such time as the enforcement action is resolved or the Corps determines that the activity may proceed independently without compromising the enforcement action. The Corps may choose not to accept applications or issue permits to any applicant with outstanding violations.
35. **Emergency situations.** This PGP can be used to authorize the repair, rehabilitation, or replacement of those structures destroyed by storms, floods, fire or other discrete unexpected and catastrophic event. In such situations and if the work exceeds Category I limitations, if applicant applies to the Corps within 30 days of the event, the Corps will attempt to contact the resource agencies for their approvals but, if unable to contact them, will issue an emergency permit and review them after-the-fact with the agencies at the next joint processing meeting. Proposed work submitted more than 30 days after the emergency will go through the standard PGP procedures.

DURATION OF AUTHORIZATION/GRANDFATHERING:

36. **Duration of Authorization.** Activities authorized under this general permit that have commenced (i.e., are under construction) or are under contract to commence in reliance upon this authorization will remain authorized provided the activity is completed within twelve months of the date of the general permit's expiration, modification, or revocation, unless discretionary authority has been exercised on a case-by-case basis to modify, suspend, or revoke the authorization in accordance with 33 CFR 325.2 (e)(2). Activities completed under the authorization of the general permit that was in effect at the time the activity was completed will continue to be authorized by the general permit.

37. Previously Authorized Activities.

- (a) Activities which have commenced (i.e., are under construction or are under contract to commence) prior to the issuance date of this general permit, in reliance upon the terms and conditions of the non-reporting category of the previous Maine PGP shall remain authorized provided the activity is completed within twelve months of the date of issuance of this general permit, unless discretionary authority has been exercised on a case-by-case basis to modify, suspend, or revoke the authorization in accordance with special condition 4. The applicant must be able to document to the Corps satisfaction that the project was under construction or contract by the appropriate date.
- (b) Projects that have received written verification or approval from the Corps, based on applications made to the Corps prior to issuance of this general permit, for the previous Maine SPGP and PGP, Nationwide permits, regional general permits, or letters of permission shall remain authorized as specified in each authorization.
- (c) This general permit does not affect activities authorized pursuant to 33 CFR Part 330.3 (activities occurring before certain dates).

For DISTRICT ENGINEER Christine Gedfrey DATE 7 / 26 / 00

CONTACTS FOR MAINE PROGRAMMATIC GENERAL PERMIT:

U.S. Army Corps of Engineers
Maine Project Office
675 Western Avenue #3
Manchester, Maine 04351
207-623-8367
Fax # 207-623-8206

Federal Endangered Species
U.S. Fish and Wildlife Service
Maine Field Office
1033 South Main Street
Old Town, Maine 04468
207-827-5938
Fax # 207-827-6099

Wild and Scenic Rivers
National Park Service
North Atlantic Region
15 State Street
Boston, MA 02109
617-223-5203

Maine Historic Preservation Commission
55 Capitol Street
State House Station 65
Augusta, Maine 04333
207-287-2132
Fax # 207-287-2335
Aroostook Band of Micmacs
P.O. Box 772
Presque Isle, Maine 04769
207-764-1972
Fax # 207-764-7667

Passamaquoddy Tribe of Indians
Pleasant Point Reservation
Attn: Tribal Council
P.O. Box 343
Perry, Maine 04667
207-853-2600
Fax # 207-853-6039

*Federal Endangered Species and Essential
Fish Habitat*
National Marine Fisheries Service
One Blackburn Drive
Gloucester, Massachusetts 01939
978-281-9102
Fax # 978-281-9301

Houlton Band of Maliseet Indians
Attn: Brenda Commander, Tribal Chief
Route 3 - Box 450
Houlton, Maine 04730
207-532-4273
Fax # 207-532-2660
Passamaquoddy Tribe of Indians
Indian Township Reservation
Attn: Donald Soctomah
P.O. Box 301
Princeton, Maine 04668
207-796-2301
Fax # 207-796-5256

Penobscot Indian Nation
Richard Hamilton, Chief
6 River Road
Indian Island Reservation
Old Town, Maine 04468
(207) 827-7776
Fax # 207-827-1137

*Maine Department of Environmental Protection
(For State Permits and Water Quality
Certifications)*

Natural Resources Division
Bureau of Land and Water Quality Control
State House Station 17
Augusta, Maine 04333
207-287-2111

Southern Maine Regional Office
312 Canco Road
Portland, Maine 04103
201-822-6300

Eastern Maine Regional Office
106 Hogan Road
Bangor, Maine 04401
207-941-4570

Northern Maine Regional Office
1235 Central Drive
Skyway Park
Presque Isle, Maine 04769
207-764-0477

*MaineLand UseRegulation Commission (LURC)
offices*

22 State House Station
Augusta, ME 04333-0022
207-287-2631
800-452-8711 (call to obtain appropriate LURC
of fice)
Fax # 207-287-7439

45 Radar Road
Ashland,ME 04732-3600
207-435-7963
Fax # 207-435-7184

Lakeview Drive
P.O.Box1107
Greenville, ME 04441
207-695-2466
Fax # 207-695-2380

191 Main Street
EastMillinocket,ME 04430
207-746-2244
Fax # 207-746-2243

i

(For CZMDeterminations)

State Planning Office
Coastal Program
184 State Street
State House Station 38
Augusta, Maine 04333
207-287- 1009

*Maine Department of Marine Resources
(For Aquaculture Leases)*
McKown Point
Boothbay Harbor, Maine 04575
207-633-9500

(For Submerged Lands Leases)

Maine Department of Conservation
Bureau of Parks and Lands
22 State House Station
207-287-3061

9129/00

15

A. INLAND WETLANDS (WATERS OF THE U.S.) ¹	CATEGORY I	CATEGORY II	INDIVIDUAL PERMIT
(a) NEW FILL/ EXCAVATION DISCHARGES	<p>Less than 4,300 sf inland waterway and /or wetland fill and secondary impacts (e.g., areas drained, flooded or cleared).</p> <p>-- Includes projects covered by a State Tier One permit with no cumulative impacts over 15,000 sf in inland wetlands from previous permits, unauthorized work, and/or other state permits.</p> <p>-- Includes crossing of perennial waterways designated as Essential Fish Habitat (EFH) for Atlantic salmon² if the waterway is crossed with a span and footprints of the span abutments are outside ordinary high water with no more than 4,300 sf of associated wetland impact.</p> <p>-- Includes in-stream work of up to 4,300 sf of fill below ordinary high water in waterways not designated as EFH for Atlantic salmon² and performed in accordance with Maine Permit By Rule standards or a LURC permit.</p>	<p>4,300 sf to 3 acres inland waterway and/or wetland fill and secondary impacts (e.g., areas drained, flooded or cleared).</p> <p>-- Impact area includes all temporary and permanent fill and excavation except for incidental fallback.</p> <p>-- Includes in-stream work, including crossings (other than a spanned crossing as described in Category I) with any discharge of fill below ordinary high water in perennial waterways designated as EFH for Atlantic salmon².</p> <p>-- Time of year restrictions determined case-by-case.</p>	<p>Greater than 3 acres inland waterway and/or wetland fill and secondary impacts (e.g., areas drained, flooded or cleared).</p> <p>-- Impact area includes all temporary and permanent fill and excavation discharges except for incidental fallback³.</p> <p>In-stream work exceeding Category II limits.</p> <p>If EIS required by the Corps.</p>

¹ Water of the U.S. in inland areas: inland rivers, streams, lakes, ponds and wetlands.

² Essential Fish Habitat for Atlantic salmon includes all aquatic habitats in the watersheds of the following rivers and streams, including all tributaries to the extent that they are currently or were historically accessible for salmon migration: St. Croix, Boyden, Dennys, Hobart Stream, Aroostook, East Machias, Machias, Pleasant, Narraguagus, Tunk stream, Patten Stream, Orland, Penobscot, Passagassawaukeag, Union, Ducktrap, Sheepscot, Kennebec, Androscoggin, Presumpscot and Saco River.

³ The larger the impacts, the more likely an individual permit will be required. Projects involving widening, expansion or impacts to degraded or low value wetlands between 1-3 acres may be approved under Category II, subject to the Federal screening. The Corps recognizes and endorses the DEP Tier 2 upper thresholds of 1 acre. Compensatory mitigation is likely to be required at this level of impact.

	CATEGORY I	CATEGORY II	INDIVIDUAL PERMIT
(a) NEW FILL/ EXCAVATION DISCHARGES	<p>-- Impact area includes all temporary and permanent fill and excavation discharges except for incidental fallback.</p> <p>-- In-stream work limited to July 15 - Oct. 1.</p> <p>-- This category excludes situations when a vernal pool of any size may be impacted, in accordance with the ME DEP definition of vernal pool⁴</p> <p>-- This category excludes work within ¼ mile or a Wild and Scenic River⁵</p> <p>-- This category excludes dams, dikes, or activities involving water withdrawal or water diversion.</p> <p>-- This category excludes work in National Wildlife Refuges.</p>	Proactive restoration projects with any amount of impact can be reviewed under Category II. The Corps, in consultation with State and Federal agencies, must determine that net adverse effects are not more than minimal.	
(b) BANK STABILIZATION PROJECTS	<p>Inland bank stabilization less than 500 ft. long and less than 1 cy fill per linear foot below ordinary high water in ponds, lakes, and waterway not designated as EFH for Atlantic salmon², provided there is no wetland fill.</p> <p>-- In-stream work limited to July 15 - Oct. 1.</p>	<p>Inland bank stabilization in ponds, lakes, and waterways not designated as EFH for Atlantic salmon² which exceeds Category I limits.</p> <p>Inland bank stabilization of any size below ordinary high water in waterways designed as EFH for Atlantic salmon².</p> <p>-- Other stabilization exceeding Category I.</p>	
(C) REPAIR AND MAINTENANCE OF AUTHORIZED FILLS	Repair or maintenance of existing, currently serviceable, authorized fills with no substantial expansion or change in use.	Replacement of non-serviceable fills, or repair or maintenance of serviceable fills with expansion of any amount up to 1 acre, or with a change in use.	Replacement of non-serviceable fills, or repair or maintenance of serviceable fills with greater than 1 acre of expansion.

⁴ Vernal Pool: Naturally-occurring, or intentionally created for the purposes of compensatory mitigation, temporary to permanent bodies of water occurring in shallow depressions that fill during the spring and fall and may dry during the summer. Vernal pools have no permanent or viable populations of predatory fish. Vernal pools provide the primary breeding habitat for wood frogs, spotted salamanders, blue-spotted salamanders, and fairy shrimp, and provide habitat for other wildlife including several endangered and threatened species.

⁵ National Wild/Scenic Rivers System (Designated River in Maine): Allagash River beginning at Telos Dam continuing to Allagash checkpoint at Eliza Hole Rapids, approximately 3 miles upstream of the confluence with the St. John River. Length = 92 miles.

4 5 6 7 8 ?

B. TIDAL WATERS AND NAVIGABLE WATERS ⁶	CATEGORY I	CATEGORY II	INDIVIDUAL PERMIT
(a) FILL		Up to 1 acre waterway or wetland fill and secondary impacts (e.g., areas drained, flooded or cleared). Includes temporary and permanent waterway fill. -- Temporary tidal marsh impacts up to 1 acre. -- Permanent tidal marsh, mudflat, or vegetated shallows 7 fill up to 1,000 sf. -- Proactive restoration projects with any amount of impact can be reviewed under Cat. II. The Corps, in consultation with State and Federal agencies, must determine that net adverse effects are not more than minimal.	Greater than 1 acre waterway fill and secondary impacts (e.g., areas drained, flooded or cleared). Includes -- Temporary tidal marsh impacts over 1 acre. -- Permanent tidal marsh, mudflat, or vegetated shallows 7 fill over 1,000 sf.
(b) REPAIR AND MAINTENANCE WORK	Repair or maintenance of existing, currently serviceable, authorized structure or fills with no substantial expansion or change in use. -- Work must be in same footprint as original structure or fill	Repair or replacement of any non-serviceable structures or fill, or repair or maintenance of serviceable fills with expansion of any amount up to 1 acre, or with a change in use.	Replacement of non-serviceable structures or fill or repair or maintenance of serviceable structure or fill with expansion greater than 1 acre.

6 Navigable Waters: waters that are subject to the ebb and flow of the tide and Federally designated navigable waters (Penobscott River to Medway, Kennebec River to Moosehead Lake, and the portion of Umbagog Lake in Maine).

7 Vegetated Shallows: subtidal areas that support rooted aquatic vegetation such as eelgrass.

	CATEGORY I	CATEGORY II	INDIVIDUAL PERMIT
(c) DREDGING	Maintenance dredging of less than 1,000 cy with upland disposal. -- Proper siltation controls used -- Limited to work between November 1 and January 15. -- No impact to special aquatic sites ⁸	Maintenance dredging of greater than 1,000 cy, new dredging of up to 25,000 cy, or projects that do not meet Category I. Disposal includes upland, open water or beach nourishment (above mean high water), only if material is determined suitable.	Maintenance dredging (any amount) in or affecting special aquatic sites ⁷ . See B(a) above for dredge disposal in wetlands or water. New dredging greater than 25,000 cy or any amount in or affecting special aquatic sites ⁷ .
(d) MOORINGS	-- Private, non-commercial, non-rental single boat moorings not associated with any boating facility? ⁹ provided not located in a Federal Navigation Project, there is no interference with navigation, it is not located in vegetated shallows ⁶ , and it is within ¼ mile of the owner's residence or a public access point ¹⁰ . -- Minor relocation or previously authorized mooring and moored floats consistent with Harbormaster recommendations, provided it is also consistent with local regulations, is not located in vegetated shallows, and does not interfere with navigation.	Moorings that do not meet the terms of Category I (e.g., rental or service moorings) and moorings that meet the terms of Category I that are located in a Federal anchorage.	Moorings within the horizontal limits, or with moored vessels that extend, into the horizontal limits of a Federal Navigation Project, except those in Federal anchorages under Category II.

⁸Special Aquatic Sites: include wetlands and salt marsh, mudflats, riffles and pools, and vegetated shallows.

? Boating Facilities: facilities that provide, rent, or sell mooring space, such as marinas, yacht, clubs, boat clubs, boat yards, town facilities, dockominiums, etc.

¹⁰ Cannot be at a remote location to create a convenient transient anchorage.

	CATEGORY I	CATEGORY II	INDIVIDUAL PERMIT
(e) PILE-SUPPORTED STRUCTURES AND FLOATS	Reconfiguration of existing authorized docks, provided structures are not positioned over vegetated shallows or salt marsh and provided floats are supported off substrate at low tide. No dredging, addition slips or expansion allowed.	Private piers and floats for navigational access to waterway (seasonal and permanent).	Structures, piers or floats that extend, or with docked/moored vessels that extend, into the horizontal limits of a Federal Navigation Project. Structures, including piers and floats, associated with a new or previously unauthorized boating facility ⁸ .
(f) MISCELLANEOUS	<ul style="list-style-type: none"> -- Temporary buoys, markers, floats, etc., for recreational use during specific events, provided they are removed within 30 days after use is discontinued. -- Coast Guard approved aids to navigation. -- Oil spill clean-up temporary structures or fill. -- Fish/wildlife harvesting structures/fill (as defined by 33 CFR 330, App. A-4) -- Scientific measurement devices and survey activities such as exploratory drilling, surveying or sampling. -- Shellfish seeding (brushing the flats) projects¹¹. -- Does <u>not</u> include oil or gas exploration and fills for roads or construction pads. -- This category excludes work in National Wildlife Refuges. 	<ul style="list-style-type: none"> -- Structures or work in or affecting tidal or navigable waters that are not defined under any or the previous headings. Includes, but is not limited to, utility lines, aerial transmission lines, pipelines, outfalls, boat ramps, bridge fills/abutments, etc. -- Shellfish/finfish (other than Atlantic salmon), or other aquaculture facilities which are consistent with the Corps revised standard siting requirements and standard permit conditions dated 7/6/94, or as revised. 	If EIS required by Corps.

¹¹ Brushing the flats: the placement of tree boughs, wooden lath structures, or small-mesh fencing on mudflats for the purpose of enhancing recruitment of soft-shell clams (*Mya arenaria*).